


Connectors for Cold-Formed Steel Construction

C-CF-2026 | (800) 999-5099 | strongtie.com


SIMPSON

Strong-Tie®



70
YEARS
OF BREAKING
NEW GROUND

Commercial Connector Solutions



Mid-Rise Connector Solutions

SSC
p. 87

FC
p. 78

S/H2.5
p. 217

H6
p. 218

S/H1A
p. 220

FCB
p. 73

PHC™
p. 136

SUBH
p. 138

SBR
p. 150

SHH
p. 109

LTP5
p. 238

S/LS
pp. 108,
212,
229

SFC
p. 102

RCA
p. 104

S/JCT
p. 204

SJC
p. 96

S/DHUTF
p. 209

S/LBV
and **S/B**
p. 206

WBT
p. 237

GP
pp. 113,
232


S/LTTP2, S/DTT
and **HTT**
p. 195

S/HDU
p. 192


S/HDS
and **S/HDB**
p. 197

RCKW™
p. 119


Curved-Framing Solutions




**Ready-Track®
Framing**
p. 166




**Ready-Angle®
Framing**
p. 167



**Ready-Arch®
Framing**
p. 166



**Ready-Hat®
Framing**
p. 167



Index

Table Of Contents

General Information	2–30	Rigid Connectors	73–137
Commercial Connector Solutions.....	2	Bridging, Bracing and Backing	138–165
Mid-Rise Connector Solutions.....	3	Curved Hand-Bendable Framing	166–168
Curved-Framing Solutions.....	4	Concrete Connectors	169–173
New Products for 2026.....	8–10	Anchors	174–189
New Testing for 2026.....	11–13	Fasteners	190–191
Load Table Explanation.....	14	Holdowns and Tension Ties	192–202
Code Listing Key Chart.....	15	Joist Framing Connectors	203–214
Important Information and General Notes	16–20	Roof, Truss and Rafter Connectors, Ties and Straps	215–232
Corrosion Information.....	21–25	Lateral Connectors, Ties and Straps	233–238
Fastening Information.....	26	Lateral Systems	239
Curtain-Wall Framing Information	28	Miscellaneous	240–241
Custom Clips and Special Orders	29	Simpson Strong-Tie Limited Warranty.....	241
Innovative Solutions for Curtain-Wall Framing.....	30		
Deflection Connectors	31–57		
Drift Connectors	58–72		

Alphabetical Product Index

ABL Anchor Bolt Locator	172	FSB Bypass Framing Fixed-Clip Strut Connector	82–83
ABS Anchor Bolt Stabilizer	169	GP Gusset Plate.....	113–114, 232
AHEP Adjustable Hip-End Purlin	229	H10S Seismic and Hurricane Tie	226–227
Anchor Designer™ for Concrete Software.....	189	HETA Embedded Truss Anchor	222–223
AnchorMate® Anchor Bolt Holders.....	169	HHETA Embedded Truss Anchor	222–223
Anchor Solutions for CFS Construction	174–175	H Hybrid Connectors.....	218–219
BP Bearing Plate.....	170	HPA Purlin Anchor.....	199–200
CFS Designer™ Software.....	27	HRS Strap Tie	233–235
CMST Coiled Strap	236	H Seismic and Hurricane Tie	217
CNW Coupler Nuts.....	171	HTSM Twist Strap	221
CS Coiled Strap	161, 214, 236	HTS Twist Strap	224
Custom Clips and Special Orders	29	HTT Tension Tie	195–196
✓ DBC Drywall Bridging Connector.....	159–160	HUC Hanger	211
✓ DBR Spacer Bracer.....	150–156	HU Hanger	211
DSP Stud Plate Tie.....	215	✓ HWDC Head-of-Wall Drift-Clip Connector	71–72
✓ DSSCB Bypass Framing Drift Strut Connector	59–70	✓ HWSC® Head-of-Wall Slide-Clip Connector	52–53
DTC Head-of-Wall Slide-Clip	54	HYS Hybrid Strut.....	46–49
DTC Roof Truss Clip.....	230	ICFVL® Ledger Connector System	213
Fasteners for CFS Construction.....	190–191	IDCB Drift-Clip Bypass Framing Connector	58
✓ FCB Bypass Framing Fixed-Clip Connector	73–77	L Angle.....	212
FC Bypass Framing Fixed-Clip Connector	78–81	LBP Bearing Plate.....	170
FHA Strap Tie.....	233–235	LS Skewable Angle	108, 212, 229

VALUE ENGINEERED



This icon indicates a product that is preferable to similar connectors because of
a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

Index

LSTA Strap Tie	233–235	SCS Hybrid Bypass Framing Connector	34–39
✓ LSTHD Strap Tie Holdown	201–202	SCW Head-of-Wall Slide-Clip Connector	50–51
LSTI Strap Tie	233–235	S/DHUTF Drywall Hangers	209
✓ LSUBH Bridging Connector	138–147	S/DTT Tension Tie	195–196
LTA2 Seismic and Hurricane Tie	226–227	✓ SFC Steel Framing Connector	102–103, 158
LTB Bridging	162, 214	S/H1A Seismic and Hurricane Ties	220
LTP5 Lateral Tie Plate	238	S/HDB Holdown	197–198
LTS Twist Strap	224	S/HDS Holdown	197–198
MASAP™ Mud sill Anchor	173	S/HDU Holdowns	192–194
MASA™ Mud sill Anchor	173	S/HGAM10 Seismic and Hurricane Tie	226–227
META Embedded Truss Anchor	222–223	✓ SHH Header Hanger	109–112
✓ MFCB Bypass Framing Fixed-Clip Connector	73–77	✓ S/HJCT Steel-Joist Connector	204–205
✓ MSCB™ Bypass Framing Slide-Clip Connector	31–33	S/H Seismic and Hurricane Tie	217
MSSC4.25KW Kneewall Connector	133–135	S/HTC Heavy Truss Clips	231
MSSC6.25KW Kneewall Connector	133–135	Simpson Strong-Tie Software	189
MSTA Strap Tie	233–235	✓ SJC Steel-Joist Connector	96–101, 203
MSTC Strap Tie	233–235	✓ S/JCT Steel-Joist Connector	204–205
MSTI Strap Tie	233–235	S/LBV Hanger	206–208
MST Strap Tie	233–235	S/LS Skewable Angle	108, 212, 229
✓ MSUBH Bridging Connector	138–147	S/LTTP2 Tension Tie	195–196
MTSM Twist Strap	221	SP Stud Plate Ties	216
MTS Twist Strap	224	SSB Bypass Framing Slide-Clip Strut Connector	44–45
PAB® Pre-assembled Anchor Bolt	187–188	✓ SSC Steel-Stud Connector	87–95, 158
PA Purlin Anchor	199–200	SSP Stud Plate Tie	215
PDPA Powder-Driven Pin	181–183	STC Roof Truss Clip	230
PDPAT Powder-Driven Top-Hat Pin	181–182	STCT Roof Truss Clip	230
PHC™ Panel Hoist Clip	136–137	✓ STHD Strap Tie Holdown	201–202
PSPNZ Protecting Shield Plate	240	StrapMate® Strap Holder	169
PS Strap Tie	233–235	Strong-Wall® High-Strength Steel Shearwalls (SSWH)	239
RCA-C Rigid Connector Angle for Concrete	115–118	ST Strap Tie	233–235
RCA Rigid Connector Angle	104–107	SUBE Bridging Connectors	148–149
✓ RCKW™ Kneewall Connector	119–132	✓ SUBH Bridging Connector	138–147
✓ Ready-Angle® Framing	167	S/VGT2.5 Variable-Pitch Girder Tiedown	225
✓ Ready-Arch® Framing	166	TB Bridging	214
✓ Ready-Hat® Framing	167	Titen HD® Heavy-Duty Screw Anchor	176–180
✓ Ready-Track® Framing	166	TJC Jack Truss and Rafter Connector	228
Ready Track Bender™ Custom Framing Tool	168	TSP Stud Plate Tie	215
RFB Retrofit Bolts	186	VGT Variable-Pitch Girder Tiedown	225
SABR™ Anchor Bolt	184–185	WBAC Wood Backing Steel Connector	163–165
S/B Hanger	206–208	WBT Wall Brace Tensioner	237
✓ SBR Spacer Bracer	150–157	WP Hanger	210
✓ SCB™ Bypass Framing Slide-Clip Connector	31–33		
SC Bypass Framing Slide-Clip Connector	40–43		
✓ SCHA Slide-Clip Connectors for Horizontal Anchorage	55–57		

New Products for 2026



Version 6

Simpson Strong-Tie® CFS Designer™ Software

Simpson Strong-Tie CFS Designer gives cold-formed steel (CFS) designers the ability to design CFS beam-column members according to AISI specifications as well as analyze complex beam loading and span conditions. Intuitive design tools automate common CFS systems such as typical walls, openings, floor joists with unbalanced live-load combinations, low wall, spandrel, 10-story load-bearing systems and shearwalls up to eight stories. Version 6 comes with several new, enhanced features.

See p. 27 for more information.



SCS Hybrid Bypass Connector (14-gauge)

This popular connector is now available in 14 ga. The SCS hybrid bypass connector is designed specifically to allow both slide-clip or fixed-clip applications and engineered to provide increased in-plane capacity.

See pp. 34–39 for more information.



HWSC® Head-of-Wall Slide-Clip Connector

Our innovative HWSC head-of-wall slide clip connector has been extended to 3 $\frac{5}{8}$ " framing. The HWSC is designed for panelizers manufacturing their own studs (e.g., FrameCAD, Arkitech, Howick, Pinnacle and Scottsdale.) The connector is designed to replace slotted track with typical printed track at head-of-wall conditions and is assembly tested to provide optimal strength and performance.

See pp. 52–53 for more information.

New Products for 2026



GP Gusset Plate

The GP Gusset Plate makes connecting trusses, shearwalls and other CFS building components easy with pre-punched holes for simple and fast attachment. Multiple size options are available.

See pp. 113–114, 232 for more information.



RCA-C Rigid Connector Angle for Concrete

New additional product options for the RCA-C have been added to allow attachment to smaller framing widths. The RCA-C223/97 is a 3"-long 2" x 2" angle with options for 1/2"-diameter anchor screw or bolt, or two 1/4"-diameter concrete screws. Easy to specify for tension, shear or moment resisting applications for different anchoring options with intuitive load charts. RCA-C saves cost for contractors by reducing time to drill holes.

See pp. 115–118 for more information.



SUBE Wall-Stud Bridging Connector

The SUBE wall-stud bridging connector for cold-formed steel (CFS) is designed to connect cold-rolled channel (CRC) at the end of a wall or single-stud jamb condition, or at the ends of panel walls, curtain walls or load-bearing conditions. SUBE is the perfect sister product to the popular SUBH product which saves install costs for CRC field attachments.

See pp. 148–149 for more information.

New Products for 2026



S/LTTP2 Tension Tie

The S/LTTP2 tension tie is ideal for retrofit or new construction. It is designed for easy installation with a 1/2"-diameter post-installed or cast-in-place anchor to concrete and #10 screws to a CFS stud. The S/LTTP2 has flanges rolled into the bend and an extruded anchor bolt hole which provides increased strength and limits deflection.

See p. 195 for more information.



ICFVL® Ledger Connector System

The ICFVL ledger connector system is engineered to meet the challenges of mounting wood or steel ledgers to insulated concrete form (ICF) walls up to 4 1/2" in thickness. The system offers many benefits over traditional anchor bolting, including better on-center spacing in most cases, faster installation and no protrusions. The new ICFVL has been redesigned for an increased capacity.

See p. 213 for more information.



WBT Wall Bracing Tensioner

The WBT wall brace tensioner is an easy-to-use device that can reduce the slack from cold-formed steel strap bracing. With the ability to pull as much as 1/2" of slack from a single strap, the WBT can play an important role in reducing deflection in braced wall panels, making installation of cladding over straps easier.

See p. 237 for more information.

New Testing for 2026



SCB™/MSCB™ Bypass Framing Slide-Clip Connector

SCB/MSCB anchorage has been tested into side and end grain of cross-laminated timber (CLT). Anchorage Tables for CLT have been added to SCB/MSCB.

See pp. 31–33 for more information.



SCS Seismic Bypass Framing Connector

For Mass Timber Construction, Simpson Strong-Tie has performed additional testing for the SCS seismic bypass framing connector with the Strong-Drive® Heavy-Duty Connector screws and Strong-Drive® SDWH™ Timber-HEX HDG screws into cross-laminated timber (CLT) supporting structures. New design tables include capacities for F₁, F₂, F₃ and F₄ loads.

See pp. 34–39 for more information.



DSSCB Bypass Framing Drift Strut Connector

The DSSCB is the solution to accommodate building drift or simplify panelized construction. Testing has been performed for use with PAF attachments. Also, additional testing has been performed at the strut splice to evaluate single stud conditions with one clip as well as box stud conditions with two clips. Testing allows engineers to be confident of capacity for all conditions that occur on the project, even worst case conditions where the clip aligns directly at a strut splice.

See pp. 59–70 for more information.



FCB/MFCB Bypass Framing Fixed-Clip Connector

FCB/MFCB anchorage has been tested into side and end grain of cross-laminated timber (CLT). Anchorage Tables for CLT have been added to FCB/MFCB.

See pp. 73–77 for more information.

New Testing for 2026



RCKW™ Kneewall Connector

The RCKW has been updated with capacities for welding to steel, and has also been tested for attachment to CLT and framing-to-wood sill applications. (For welding to steel and attachment to CLT, reference this catalog. For wood-to-wood applications reference *Wood Construction Connectors* catalog or strongtie.com)

See pp. 119–132 for more information.



PHC™ Panel Hoist Clip

The PHC panel hoist clip allows easier installation and lifting of wall panels on the job and at assembly sites. Additional testing provides an option for lighter conditions using fewer screws with our tested five-screw option.

See pp. 136–137 for more information.



WBAC Wood Backing Steel Connector

The WBAC wood backing steel connector is the perfect solution for cabinets, shelves, handrails, heavy wall hangings and more. This connector has been expanded with testing for CFS blocking. The WBAC can now be used with wood or CFS blocking all backed by component testing.

See pp. 163–165 for more information.



S/HDU Holdown

At the request of panelizers, the S/HDU has been tested for welds to the stud in lieu of screws. Design tables have been updated to include weld capacities.

See pp. 192–194 for more information.


New Testing for 2026



S/HDS Holddown

Capacities for single stud attached to S/HDS have been developed based on testing. S/HDS capacities tables now provide options for attachment to single studs, back-to-back studs and $\frac{3}{16}$ " A36 steel.

See pp. 197–198 for more information.



S/LBV and S/B Hanger

The S/LBV and S/B hangers have been tested to provide capacities without web stiffeners for typical joist gauges in order to potentially eliminate web stiffeners and provide a more cost effective design. In addition, load capacities for hangers attached on one side of the joist vs. both sides of the joist are provided.

See pp. 206–208 for more information.



CMST Coiled Medium Strap Tie

Additional options for attachment of CMSTC16 strapping using GDPSK-138 pins in lieu of screws or attaching the strap with screws over OSB sheathing to CFS studs have been provided.

See p. 236 for more information.

How to Use This Catalog

New Products

New products are shown with the symbol. There are also many new sizes within existing model series.



Value Engineered

This icon indicates a product that is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.



Extra Corrosion Protection

The teal arrow icon identifies products that are available with additional corrosion protection (ZMAX®, hot-dip galvanized or double-barrier coating). The SS teal arrow icon identifies products also available in stainless steel. Other products may also be available with additional protection; contact Simpson Strong-Tie for options. The end of the product name will indicate what type of extra corrosion protection is provided (Z = ZMAX, HDG = hot-dip galvanized or SS = stainless steel). Stainless products may need to be manufactured upon ordering. See pp. 21–25 for information on corrosion, and visit our website strongtie.com/info for more technical information on this topic.

Load Table Explanation

Dimensions: This shows the product dimensions (material thickness, length and width in this case.) The product drawing includes these callouts as a cross-reference.

Allowable Design Load: The maximum load imposed on a connection during the life of a structure. There may be multiple design loads acting in different directions (up, down, lateral, perpendicular, etc.) imposed on a connection. When connectors are attached to two CFS members of different thicknesses, the designer shall use the thinner of the two members for selecting allowable loads.

Model No.:

This is the Simpson Strong-Tie product name.

Fasteners: This shows the fastener quantity and type required to achieve the table loads.

Thickness: The thickness of the CFS supporting member to which the product is attached. Allowable load is based on this CFS supporting member thickness.

Code Ref: See p. 15 for the Code Reference Key Chart, to determine which code reports include this product.

Model No.	Connector Material Thickness mil (ga.)	Dimensions (in.)		Fasteners (Total)			Allowable ASD Tension Load			Code Ref.
		W	L	Rafter/Stud/Joist Thickness			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	
				33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)				
LSTA9	33 (20 ga.)	1¼	9	(8) #10	(8) #10	(8) #10	705	1,120	1,190	IBC, FL, LA
LSTA12		1¼	12	(10) #10	(10) #10	(8) #10	885	1,190	1,190	
LSTA15		1¼	15	(12) #10	(12) #10	(10) #10	1,060	1,190	1,190	
LSTA18		1¼	18	(14) #10	(12) #10	(10) #10	1,190	1,190	1,190	

Other Catalog Definitions

Deflection: The distance a point moves when a load is applied.

Nominal Tension Load (Strength): The capacity of a structure or component to resist the effects of loads, as determined in accordance with AISI-S100 using specified material strengths and dimensions. Typically taken as the average value of at least three tests.

The Nominal Tension Load should not be compared against design loads (ASD, LRFD), but used only where the AISI Lateral Design Standard requires the holdown to have nominal tension load (strength) to resist the lesser of the amplified seismic load or the maximum force the system can deliver.

Codes

Code Reference Column in Load Tables

Product evaluation agencies play an important role in the building industry providing an independent third-party review of architectural and structural products. Evaluations use publicly developed criteria to determine if the product meets the intent of the building code. Building officials can use product evaluation reports, often referred to as “code reports,” to review and approve product use on a project.

The most prominent architectural and structural building product certification companies are ICC Evaluation Service (ICC-ES) and IAPMO Uniform Evaluation Service (IAPMO UES), which are both ANSI-accredited to ISO Guide 65 “General Requirements for Bodies Operating Product Certification Systems” as product certification entities. Simpson Strong-Tie currently maintains more than 60 ICC-ES ESR and IAPMO UES ER reports evaluated to the 2018, 2021 and 2024

International Building Code (IBC) and International Residential Code (IRC). We continue to submit product information to evaluation agencies in order to update reports or receive additional reports for products in compliance with the latest codes. Simpson Strong-Tie also has reports for the City of Los Angeles, California and the State of Florida.

We have simplified our code references to make this catalog easier to use. You can quickly determine whether a product has a code report by looking in the Code Reference column of the product load tables. A summary of the code references used is in the table below.

To determine which specific code report applies to a product and download a copy of the code report, you can use our Code Report Finder at strongtie.com/codes.

Code Reference	Evaluation Agency	Building Code Coverage
IBC	ICC-ES IAPMO UES	International Building Code (IBC) International Residential Code (IRC)
FL	Florida Statewide Product Approval	Florida Building Code Visit strongtie.com/codes or floridabuilding.org for accurate and up-to-date product approval and evaluation reports.
LA	City of Los Angeles Department of Building Safety	Los Angeles Building Code and Los Angeles Residential Code These products may have either a City of LA Research Report or a City of LA supplement to their ICC-ES or IAPMO UES evaluation reports.
PR	Prescriptive	Products that meet prescriptive or conventional construction requirements.
—	None	No evaluation report listing. Products are tested and calculated per code. See “How We Determine Allowable Loads” below.

How We Determine Allowable Loads

Allowable loads in this catalog are determined by calculations and test criteria established by industry, such as ICC-ES Acceptance Criteria, IAPMO UES Evaluation Criteria, and AISI or ASTM test standards.

Cold-formed steel connectors are typically evaluated in accordance with ICC-ES AC261 — Acceptance Criteria for Connectors Used with Cold-Formed Steel Structural Members. Evaluation is based on a minimum of three static load tests in CFS assemblies or structural steel jigs. The published allowable load is the lower of the tested ultimate with a safety factor, load at 1/8" deflection or the fastener calculation limits. Safety factors for ASD and resistance factors for LRFD are in accordance with AISI-S100 Section F.

Cast-in-place concrete products are tested in accordance with ICC-ES AC398 — Cast-in-Place, Cold-Formed Steel Connectors in Concrete

for Light-Frame Construction or AC399 — Cast-in-Place Proprietary Bolts in Concrete for Light-Frame Construction. Tapping screw fasteners are evaluated per AC118 — Acceptance Criteria for Tapping Screw Fasteners Used in Steel-to-Steel Connections.

Where a test standard is unavailable, testing is conducted per sound engineering principles. Some tests include only portions of a product, such as purlin anchor tests, wherein only the embedded hook is tested, not the nailed or bolted section of the strap, which is calculated. Testing to determine allowable loads in this catalog is not done on connection systems in buildings. Testing is conducted in an IAS-accredited laboratory.

For detailed information regarding how Simpson Strong-Tie tests specific products, contact Simpson Strong-Tie.

Important Information and General Notes

General Notes

These notes are provided to ensure proper installation of Simpson Strong-Tie® products and must be followed fully.

- a. Simpson Strong-Tie Company Inc. reserves the right to change specifications, designs and models without notice or liability for such changes.
- b. Steel used for each Simpson Strong-Tie product is individually selected based on the product's steel specifications, including strength, thickness, formability, finish, and weldability. Contact Simpson Strong-Tie for steel information on specific products.
- c. Unless otherwise noted, dimensions are in inches and loads are in pounds.
- d. Unless otherwise noted, welds, bolts, screws and nails may not be combined to achieve highest load value.
- e. Unless otherwise noted, catalog loads are based on cold-formed steel members having a minimum yield strength, F_y , of 33 ksi and tensile strength, F_u , of 45 ksi for 43 mil (18 ga.) and thinner, and a minimum yield strength, F_y , of 50 ksi and tensile strength, F_u , of 65 ksi for 54 mil (16 ga.) and thicker.
- f. Simpson Strong-Tie Company Inc. will manufacture non-catalog products provided prior approval is obtained and an engineering drawing is included with the order. Steel specified on the drawings as $\frac{1}{8}$ ", $\frac{3}{16}$ ", and $\frac{1}{4}$ " will be 11 gauge (0.120"), 7 gauge (0.179"), and 3 gauge (0.239"), respectively. The minimum yield and tensile strengths are 33 ksi and 52 ksi, respectively.
- g. All references to bolts are for structural quality through bolts (not lag screws or carriage bolts) equal to or better than ASTM Standard A307, Grade A.
- h. Unless otherwise noted, bending steel in the field may cause fractures at the bend line. Fractured steel will not carry load and must be replaced.
- i. Top flange hangers may cause unevenness. Possible remedies should be evaluated by a professional and include using a face mount hanger or cutting the subfloor to accommodate the top flange thickness.
- j. Built-up members (multiple members) must be fastened together to act as one unit to resist the applied load (excluding the connector fasteners). This must be determined by the designer or Engineer of Record.
- k. Do not overload. Do not exceed catalog allowable loads, which would jeopardize the connection.
- l. Some model configurations may differ from those shown in this catalog. Contact Simpson Strong-Tie for details.
- m. Some combinations of hanger options are not available. In some cases, combinations of these options may not be installable. Horizontal loads induced by sloped joists must be resisted by other members in the structural system. A qualified designer must always evaluate each connection, including carried and carrying member limitations, before specifying the product. Fill all fastener holes with fastener types specified in the tables, unless otherwise noted. Hanger configurations, height and fastener schedules may vary from the tables depending on joist size, skew and slope. See the allowable table load for the non-modified hanger, and adjust as indicated. Material thickness may vary from that specified depending on the manufacturing process used. W hangers normally have single stirrups; occasionally, the seat may be welded. S/B, S/LBV, W and WP hangers for sloped seat installations are assumed backed.
- n. Simpson Strong-Tie will calculate the net height for a sloped seat. The customer must provide the H_1 joist height before slope.
- o. Do not weld products listed in this catalog unless this publication specifically identifies a product as acceptable for welding, or unless specific approval for welding is provided in writing by Simpson Strong-Tie. Some steels have poor weldability and a tendency to crack when welded. Cracked steel will not carry load and must be replaced.
- p. Steel for the framing members must comply with ASTM A1003 Grade 33 minimum. Reference General Note "e" for additional requirements.
- q. Consideration should be given to the screw head specified as this may affect the attached materials.
- r. Do not add fastener holes or otherwise modify Simpson Strong-Tie products. The performance of modified products may be substantially weakened. Simpson Strong-Tie will not warrant or guarantee the performance of such modified products.

Important Information and General Notes

Warning

Simpson Strong-Tie Company Inc. structural connectors, anchors, and other products are designed and tested to provide specified design loads. To obtain optimal performance from Simpson Strong-Tie Company Inc. products and achieve maximal allowable design load, the products must be properly installed and used in accordance with the installation instructions and design limits provided by Simpson Strong-Tie Company Inc. To ensure proper installation and use, designers and installers must carefully read the following General Notes, General Instructions to the Installer and General Instructions to the Designer, as well as consult the applicable catalog pages for specific product installation instructions and notes.

Proper product installation requires careful attention to all notes and instructions, including these basic rules:

1. Be familiar with the application and correct use of the connector.
2. Follow all installation instructions provided in the applicable catalog, website, *Installer's Pocket Guide* or any other Simpson Strong-Tie® publications.
3. Install all required fasteners per installation instructions provided by Simpson Strong-Tie Company Inc.: (a) use proper fastener type; (b) use proper fastener quantity; (c) fill all fastener holes; (d) do not overdrive or underdrive nails, including when using powder nailers; and (e) ensure screws are completely driven.

4. Only bend products that are specifically designed to be bent. For those products that require bending (such as strap-type holdowns, straight-end twist straps, etc.), do not bend more than one full cycle.
5. Cut joists to the correct length, do not "short-cut." The gap between the end of the joist and the header material should be no greater than 1/8" unless otherwise noted.

Failure to follow all of the notes and instructions provided by Simpson Strong-Tie Company Inc. may result in improper installation of products. Improperly installed products may not perform to the specifications set forth in this catalog and may reduce a structure's ability to resist the movement, stress and loading that occurs from gravity loads as well as impact events such as earthquakes and high-velocity winds.

Simpson Strong-Tie Company Inc. does not guarantee the performance or safety of products that are modified, improperly installed or not used in accordance with the design and load limits set forth in this catalog.

Important Information

In addition to following the basic rules provided above as well as all notes, warnings and instructions provided in the catalog, installers, designers, engineers and consumers should consult the Simpson Strong-Tie Company Inc. website at strongtie.com to obtain additional design and installation information.

General Instructions to the Installer

These general instructions to the installer are provided to ensure proper selection and installation of Simpson Strong-Tie® products and must be followed carefully. These general instructions are in addition to the specific installation instructions and notes provided for each particular product, all of which should be consulted prior to and during installation of Simpson Strong-Tie products.

- a. All specified fasteners must be installed according to the instructions in this catalog. Incorrect fastener quantity, size, type, material, or finish may cause the connection to fail.
- b. Holes for 1/2" diameter or greater bolts shall be no more than a maximum of 1/16" larger than bolt diameter per AISI S100 Table E3.
- c. Install all specified fasteners before loading the connection.
- d. Some hardened fasteners may have premature failure if exposed to moisture. The fasteners are recommended to be used in dry interior applications.
- e. Use proper safety equipment.
- f. When installing a joist into a connector with a seat, the joist shall bear completely on the seat. The gap between the end of the joist and the connector or header shall not exceed 1/8" per ICC-ES AC208.1, ASTM D1761 and ASTM D7147 test standards, unless otherwise noted.
- g. For holdowns, anchor bolt nuts should be finger-tight plus 1/2 to 1/2 turn with a hand wrench. Care should be taken to not over-torque the nut and impact wrenches should not be used. This may preload the holdown.
- h. Holdowns and tension ties may be raised off the track as dictated by field conditions to accommodate an anchor mislocated no more than 1 1/2". The holdown shall be raised off the bottom track at least 3" for every 1/4" that the anchor is offset from the model's centerline. Anchor bolt slope shall be no greater than 1:12 (or 5 degrees). Contact the designer if the holdown anchor is offset more than 1 1/2" or raised more than 18". Raised holdown height is measured from the top of the concrete to the top of the holdown bearing plate.
- i. All screws shall be installed in accordance with the screw manufacturer's recommendations. All screws shall penetrate and protrude through the attached materials a minimum of three full exposed threads per AISI S200 General Provisions Section D1.3.
- j. Welding shall be in accordance with American Welding Society AWS D1.1 or D1.3, as applicable. Allowable loads for welded connections require electrodes with minimum tensile strength of 70 ksi. Welding galvanized steel may produce harmful fumes; follow proper welding procedures and precautions. Unless otherwise noted, Simpson Strong-Tie connectors cannot be welded.
- k. Temporary lateral support for members may be required during installation.

Important Information and General Notes

General Instructions to the Designer

These general instructions to the designer are provided to ensure proper selection and installation of Simpson Strong-Tie Company Inc. products and must be followed carefully. These general instructions are in addition to the specific design and installation instructions and notes provided for each particular product, all of which should be consulted prior to and during the design process.

- a. Allowable loads are determined per the AISI S100 unless otherwise specified. Other code agencies may use different methodologies.
- b. The allowable load is typically limited to an average test load at $\frac{1}{8}$ " deflection, or an average or lowest test value (nominal load) divided by a safety factor or the calculation value. The safety factor is prescribed by Section K2.1 of the AISI S100.
- c. To achieve the loads shown in this catalog, the designer must verify that the self-drilling screws used for connector installation have P_{nvs}/Ω and P_{nts}/Ω values greater than or equal to the values given in the table, Minimum ASD Loads for Screws (lb.), per p. 26 of this catalog.
- d. Allowable simultaneous loads in more than one direction on a single connector must be evaluated as follows:

Design Uplift/Allowable Uplift + Design Lateral Parallel to Track/
Allowable Lateral Parallel to Track + Design Lateral Perpendicular
to Track/Allowable Lateral Perpendicular to Track ≤ 1.0 .

The three terms in the unity equation are due to the three possible directions that exist to generate force on a connector. The number of terms that must be considered for simultaneous loading is at the sole discretion of the designer and is dependent on their method of calculating wind forces and the utilization of the connector within the structural system.
- e. The term "designer" used throughout this catalog is intended to mean a licensed/certified building design professional, a licensed professional engineer, or a licensed architect.
- f. All connected members and related elements shall be designed by the designer.
- g. Unless otherwise noted, member strength is not considered in the loads given and, therefore, one should reduce allowable loads when member strength is limiting.
- h. The average ultimate breaking strength for some models is listed under "nominal tension load."
- i. Simpson Strong-Tie strongly recommends the following addition to construction drawings and specifications: "Simpson Strong-Tie connectors and fasteners are specifically required to meet the structural calculations of plan. Before substituting another brand, confirm load capacity based on reliable published testing data or calculations. The designer or Engineer of Record should evaluate and give written approval for substitution prior to installation."
- j. Verify that the dimensions of the supporting member are sufficient to receive the specified fasteners, and develop the top flange bearing length.
- k. Most of the allowable loads published in this catalog are for use when utilizing the traditional Allowable Stress Design (ASD) methodology. A method for using Load and Resistance Factor Design (LRFD) for cold-formed steel is also included in AISI S100. When designing with LRFD, the nominal connector strength multiplied by the resistance factor must be used. If not listed or noted in a table footnote, contact Simpson Strong-Tie for the LRFD values of products listed in this catalog.
- l. All steel-to-steel connector screws must comply with ASTM C1513.
- m. Screw strength shall be calculated in accordance to AISI S100 Section J4 or shall be based upon the manufacturer's design capacity determined from testing.
- n. Simpson Strong-Tie recommends that hanger height be at least 60% of joist height for stability against rotation while under construction prior to sheathing install.
- o. Local and/or regional building codes may require meeting special conditions. Building codes often require special inspection of anchors installed in concrete and masonry. For compliance with these requirements, it is necessary to contact the local and/or regional building authority. Except where mandated by code, Simpson Strong-Tie® products do not require special inspection.
- p. When connectors are attached to two CFS members of different thicknesses, the designer shall use the thinner of the two members for selecting allowable loads.
- q. Welding shall be in accordance with American Welding Society AWS D1.1 or D1.3, as applicable. Allowable loads for welded connections require electrodes with minimum tensile strength of 70 ksi. Welding galvanized steel may produce harmful fumes; follow proper welding procedures and precautions. Unless otherwise noted, Simpson Strong-Tie connectors cannot be welded.
- r. It is acceptable to use the capacity listed in the catalog for the thickest framing member for thicker framing members of the same or higher yield strength.

Additional Instructions for the Installer for Hybrid (Steel-to-Wood) Connections

- a. Bolt holes into wood members shall be at least a minimum of $\frac{1}{32}$ " and no more than a maximum of $\frac{1}{16}$ " larger than the bolt diameter (per the 2015 NDS 12.1.3.2 and AISI S100 Table J3-1, if applicable).
- b. Joist shall bear completely on the connector seat, and the gap between the joist end and the header shall not exceed $\frac{1}{8}$ " per ICC-ES AC261, ASTM D1761 and ASTM D7147 test standards (unless specifically noted otherwise).
- c. For holdowns, anchor bolt nuts should be finger-tight plus $\frac{1}{2}$ turn with a hand wrench, with consideration given to possible future wood shrinkage. Care should be taken to not over-torque the nut and impact wrenches should not be used. This may preload the holdown.

Important Information and General Notes

Additional Important Information and General Notes for Hybrid (Steel-to-Wood) Connections

These notes are in addition to the previous notes for steel-to-steel connections and are provided to ensure proper installation of Simpson Strong-Tie® products and must be followed fully.

- a. Unless otherwise noted, allowable loads are for Douglas Fir–Larch under continuously dry conditions. Allowable loads for other species or conditions must be adjusted according to the code. The section from the AC13 criteria indicating the range of specific gravity reads as follows: 3.2.3 The species of lumber used shall have a specific gravity not greater than 0.55 as determined in accordance with the NDS. This chart shows specific gravity and perpendicular to grain compression capacities for the different wood species:

Species	F _c L	Specific Gravity
Douglas Fir–Larch (DFL)	625 psi	0.50
Southern Pine (SP)	565 psi	0.55
Spruce-Pine-Fir (SPF)	425 psi	0.42
Spruce-Pine-Fir South (SPF-S)	335 psi	0.36
Hem Fir (HF)	405 psi	0.43
Glulam	650 psi	0.50
LVL (DF/SP)	750 psi	0.50
LSL (E = 1.3 × 10 ⁶)	680 psi	0.50
LSL (E ≥ 1.5 × 10 ⁶)	880 psi	0.50
Parallam PSL	625 psi	0.50
Western Cedar	425 psi	0.36

- b. For face-mount hangers and straight straps, use 0.86 of Douglas Fir table loads for Spruce-Pine-Fir.
- c. A fastener that splits the wood will not take the design load. Evaluate splits to determine if the connection will perform as required. Dry wood may split more easily and should be evaluated as required. If wood tends to split, consider preboring holes with diameters not exceeding 0.75 of the nail diameter (2015/ 2018 NDS 12.1.5.3).
- d. Wood shrinks and expands as it loses and gains moisture, particularly perpendicular to its grain. Take wood shrinkage into account when designing and installing connections. Simpson Strong-Tie manufactures products to fit common dry lumber dimensions. If you need a connector with dimensions other than those listed in this catalog, Simpson Strong-Tie may be able to vary connector dimensions; contact Simpson Strong-Tie. The effects of wood shrinkage are increased in multiple lumber connections, such as floor-to-floor installations. This may result in the vertical rod nuts becoming loose, requiring post-installation tightening. (Reference ICC-ES ESR-2320 for information on Take-up Devices.)
- e. Top flange hangers may cause unevenness. Possible remedies should be evaluated by a professional and include using a face mount hanger, and notching the beam or cutting the subfloor to accommodate the top flange thickness.
- f. Built-up lumber (multiple members) must be fastened together to act as one unit to resist the applied load (excluding the connector fasteners). This must be determined by the designer.

Additional Instructions for the Designer for Hybrid (Steel-to-Wood) Connections

- a. Loads are based on the AISI S100 and the 2015 AF National Design Specifications (NDS), unless otherwise specified. Other code agencies may use different methodologies.
- b. Duration of load adjustments for fasteners into wood as specified by the code are as follows:
- Do not alter installation procedures from those set forth in this catalog.
 - “FLOOR” and “DOWN” (100) — no increase for duration of load.
 - “SNOW” (115) — 115% of design load for 2-month duration of load.
 - “ROOF LOAD” (125) — 125% of design load for 7-day duration of load.
 - “EARTHQUAKE/WIND” (160) — 160% of design load for earthquake/wind loading.
- c. Some catalog illustrations show connections that could cause cross-grain tension or bending of the wood during loading if not sufficiently reinforced. In this case, mechanical reinforcement should be considered.
- d. Most of the allowable loads published in this catalog are for use when utilizing the traditional Allowable Stress Design (ASD) methodology. A method for using Load and Resistance Factor Design (LRFD) for cold-formed steel is also included in AISI S100. When designing with LRFD, the nominal connector strength multiplied by the resistance factor must be used. If not listed or noted in a table footnote, contact Simpson Strong-Tie for the LRFD values of products listed in this catalog. A method for using Load and Resistance Factor Design (LRFD) for wood has been published in ASTM D5457. For more information, refer to the 2015/2018 NDS Appendix N, which contains a conversion procedure that can be used to derive LRFD capacities. When designing with LRFD, reference lateral resistances must be used.
- e. Pneumatic or powder-actuated fasteners may deflect and injure the operator or others. Unless otherwise noted, powder-actuated fasteners should not be used to install connectors. Pneumatic nail tools may be used to install connectors, provided the correct quantity and type of fasteners are properly installed in the fastener holes. Tools with fastener hole-locating mechanisms should be used. Follow the manufacturer's instructions and use the appropriate safety equipment. Over driving fasteners may reduce allowable loads. Contact Simpson Strong-Tie as needed.

Important Information and General Notes

Limited Warranty

For the Limited Warranty that applies to Simpson Strong-Tie products, please consult strongtie.com/limited-warranties. See p. 241 for the Limited Warranty in effect when this catalog was first published. To obtain a copy of the current Limited Warranty, contact us at limited_warranty@strongtie.com, (800) 999-5099 or Simpson Strong-Tie Company Inc., 5956 West Las Positas Boulevard, Pleasanton, CA 94588.

The Limited Warranty contains important disclaimers, limitations and exclusions, and applies only if the products have been properly specified, installed, maintained, and used in accordance with the design limits and the structural, technical, and environmental specifications in the Simpson Strong-Tie Documentation. All future purchases of Simpson Strong-Tie products are subject to the terms of the Limited Warranty in effect as of the purchase date.

Although products are designed for a wide variety of uses, Simpson Strong-Tie assumes no liability for confirming that any product is appropriate for an intended use, and each intended use of a product must be reviewed and approved by qualified professionals. Each product is designed for the load capacities and uses listed in the Simpson Strong-Tie Documentation, subject to the limitations and other information set forth therein. Due to the particular characteristics of potential impact events such as earthquakes and high velocity winds, the specific design and location of the structure, the building materials used, the quality of construction, or the condition of the soils or substrates involved, damage may nonetheless result to a structure and its contents even if the loads resulting from the impact event do not exceed Simpson Strong-Tie's specifications and the products are properly installed in accordance with applicable building codes, laws, rules and regulations.

Terms and Conditions of Sale

Product Use

Products in this catalog are designed and manufactured for the specific purposes shown, and should not be used with other connectors not approved by a qualified licensed/certified building design professional, a licensed professional engineer or licensed architect ("designer"). You should review our website and consult a qualified designer familiar with all applicable building codes each time you use a Simpson Strong-Tie product.

Indemnity

Any designer or other person who modifies any products, changes any installation procedures or designs any non-catalog products for fabrication by Simpson Strong-Tie Company Inc. shall, regardless of specific instructions to the user, indemnify, defend, and hold harmless Simpson Strong-Tie Company Inc. for any and all claimed loss or damage occasioned in whole or in part by such products.

Non-Catalog and Modified Products

Modifications to products or changes in installation procedures should only be made by a qualified professional designer. The performance of such modified products or altered installation procedures is the sole responsibility of the designer. Any person modifying Simpson Strong-Tie products must provide the installer with specific instructions on the modified products' specifications, installation and use.

Consult Simpson Strong-Tie Company Inc. for applications for which there is no catalog product, or for connectors for use in hostile environments, with excessive wood shrinkage, or with abnormal loading or erection requirements.

Non-catalog products must be designed by a qualified designer and will be fabricated by Simpson Strong-Tie in accordance with customer specifications.

Any modified, special order or non-catalog products, or any products that are not installed strictly in accordance with Simpson Strong-Tie installation procedures, are provided "AS IS" and without any representation or warranty of any kind.

Important Information and General Notes

Conversion Charts

Metric Conversion

Imperial	Metric
1 in.	25.40 mm
1 ft.	0.3048 m
1 lb.	4.448N
1 Kip	4.448 kN
1 psi	6,895 Pa

Bolt Diameter

in.	mm
3/8	9.5
1/2	12.7
5/8	15.9
3/4	19.1
7/8	22.2
1	25.4

If Common Rafter Roof Pitch is...

Rise/Run	Slope
1:12	5°
2:12	10°
3:12	14°
4:12	18°
5:12	23°
6:12	27°
7:12	30°
8:12	34°
9:12	37°
10:12	40°
11:12	42°
12:12	45°

Then Hip/Valley Rafter Roof Pitch becomes...

Rise/Run	Slope
1:17	3°
2:17	7°
3:17	10°
4:17	13°
5:17	16°
6:17	19°
7:17	22°
8:17	25°
9:17	28°
10:17	30°
11:17	33°
12:17	35°

US Standard Steel Gauge Equivalents in Nominal Dimensions

Min. Thick.	Design Thick.	Ref. Ga. ²	Thickness of Steel Sheets (in.)		
			Uncoated Steel	Galvanized Steel (G90)	ZMAX® (G185)
mil	in.				
229	0.2405	3	0.239	—	—
171	0.1795	7	0.179	0.186	—
155	0.1668	8	—	0.167	0.169
118	0.1240	10	0.134	0.138	0.140
111	0.1163	11	0.120	0.123	0.125
97	0.1017	12	0.105	0.108	0.110
68	0.0713	14	0.075	0.078	0.080
54	0.0566	16	0.060	0.063	0.065
43	0.0451	18	0.048	0.052	0.054
33	0.0346	20	0.036	0.040	0.042
27	0.0283	22	0.030	0.033	0.035

Use these Roof Pitch to Hip/Valley Rafter Roof Pitch conversion tables only for hip/valley rafters that are skewed 45° right or left. All other skews will cause the slope to change from that listed.

1. Steel thickness may vary according to industry mill standards.
2. Gauge numbers shown are for reference only.

Buy America

Simpson Strong-Tie is committed to designing and manufacturing our products with minimal environmental impact. CFS structural connectors, prefabricated shearwalls, moment frames, many Simpson Strong-Tie® screws and Strong-Rod® systems are designed and engineered in the United States. We seek to manufacture and source raw materials domestically when possible. Many of our products are made in the US. However, we also source or manufacture some of our product abroad, whether in Europe, Canada, or Asia. Our objective in all our sourcing and manufacturing practices is to bring the highest-quality products to our customers at the most competitive prices.

If you have a question about the sourcing or manufacture of a specific product, please email us at SimpsonTradeCompliance@strongtie.com.

Corrosion Information

Understanding the Corrosion Issue

Metal connectors, fasteners and anchors can corrode and lose carrying capacity when installed in corrosive environments or when installed in contact with corrosive materials. The many variables present in a building environment make it impossible to predict accurately whether, or when, corrosion will begin to reach a critical level. This relative uncertainty makes it crucial that specifiers and users be knowledgeable about the potential risks and select a product suitable for the intended use. When there is any uncertainty about the possible corrosion risks of any installation, a qualified professional should be consulted. Because of the risks posed by corrosion, periodic inspections should be performed by a qualified engineer or qualified inspector and maintenance performed accordingly.

It's common to see some corrosion in outdoor applications. Even stainless steel can corrode. The presence of some corrosion does not mean that load capacity has been affected or that failure is imminent.

If significant corrosion is apparent or suspected, then the wood, fasteners, anchors, and connectors should be inspected by a qualified engineer or qualified inspector. Replacement of affected components may be appropriate.

Because of the many variables involved, Simpson Strong-Tie cannot provide estimates of the service life of connectors, anchors, and fasteners. We suggest that all users and specifiers obtain recommendations on corrosion from the suppliers of the materials that will be used with Simpson Strong-Tie products, in particular, treated wood or concrete. We have attempted to provide basic knowledge on the subject here, and have additional information in our technical bulletins on the topic (strongtie.com/info). The Simpson Strong-Tie website should always be consulted for the latest information.

Corrosion Information

Corrosion Conditions

Corrosion can result from many combinations of environmental conditions, materials, construction design, and other factors, and no single guideline addresses all corrosion possibilities. Nevertheless, important corrosion information can be obtained from the American Wood Protection Association (AWPA), the International Building Code (IBC), International Residential Code (IRC), and local building codes. The following discussion provides general guidelines and approaches for the selection of Simpson Strong-Tie® products for various construction conditions, but is not intended to supersede the guidelines of the AWPA, IBC, IRC, or local building codes.

Corrosion issues for Simpson Strong-Tie products generally fall into five categories:

1. Environmental and Construction Factors

Many environments and materials can cause corrosion, including ocean salt air, condensation, duration of wetness, fire retardants, fumes, fertilizers, chlorides, sulfates, preservative-treated wood, de-icing salts, dissimilar metals, soils, and more. Designers must take all of these factors into account when deciding which Simpson Strong-Tie products to use with which corrosion-resistant coatings or materials.

The design, quality of construction, and misinstallation can directly affect the corrosion resistance of products. A product intended and installed for use in dry-service environment may corrode if the structure design or building materials allow moisture intrusion, or expose the product to corrosive conditions, such as moisture or chemicals contained in the construction materials, soils, or atmospheres.

2. Chemically Treated Lumber

Some wood-preservative or fire-retardant chemicals or chemical retention levels create increased risk of corrosion and are corrosive to steel connectors and fasteners. For example, testing by Simpson Strong-Tie has shown that ACQ-Type D is more corrosive than Copper Azole, Micronized Copper Azole, or CCA-C. At the same time, other tests have shown that inorganic boron treatment chemicals, specifically SBX-DOT, are less corrosive than CCA-C.

Because different chemical treatments of wood have different corrosion effects, it's important to understand the relationship between the wood treatment chemicals and the coatings and base metals of Simpson Strong-Tie products.

The preservative-treated wood supplier should provide all of the pertinent information about the treated wood product. The information should include the AWPA Use Category Designation, wood species group, wood treatment chemical, and chemical retention. See building code requirements and appropriate evaluation reports for corrosion effects of wood treatment chemicals and for fastener corrosion resistance recommendations.

With Fire-Retardant (FRT) Wood, the 2015 and 2018 IBC Section 2304.10.5.4, 2021 and 2024 IBC Section 2304.10.6.4, and 2015, 2018 and 2021 IRC Section R317.3.4, 2024 IRC R304.3.4 Section refer to the manufacturers for fastener corrosion requirements. In the absence of recommendations from the FRT manufacturer, the building codes require fasteners to be hot-dip galvanized, stainless steel, silicon bronze or copper. Simpson Strong-Tie further requires that the fastener is compatible with the metal connector hardware. Fastener shear and withdrawal allowable loads may be reduced in FRT lumber. Refer to the FRT manufacturer's evaluation report for potential reduction factors.

3. Dissimilar Metals and Galvanic Corrosion

Galvanic corrosion occurs when two electrochemically dissimilar metals contact each other in the presence of an electrolyte (such as water) that acts as a conductive path for metal ions to move from the more anodic to the more cathodic metal. Good detailing practice, including the following, can help reduce the possibility of galvanic corrosion of fasteners and connectors:

- Use fasteners or anchors and connectors with similar electrochemical properties
- Use insulating materials to separate dissimilar metals
- Ensure that the fastener or anchor is the cathode when dissimilar connector metals are present
- Prevent exposure to and pooling of electrolytes

If you are uncertain about the galvanic corrosion potential of any installation, always consult with a corrosion expert. See the product pages for particular parts for more information regarding what coating systems are recommended or required for use with the parts in question.

Galvanic Series of Metals

Corroded End (Anode)
Magnesium, Magnesium alloys, Zinc
Aluminum 1100, Cadmium, Aluminum 2024-T4, Iron and Steel
Lead, Tin, Nickel (active), Inconel Ni-Cr alloy (active), Hastelloy alloy C (active)
Brasses, Copper, Cu-Ni alloys, Monel
Nickel (passive)
Type 304 stainless steel (passive), Type 316 stainless steel (passive), Hastelloy alloy C (passive)
Silver, Titanium, Graphite, Gold, Platinum
Protected End (Cathode)

4. Hydrogen-Assisted Stress-Corrosion Cracking

Some hardened fasteners may experience premature failure from hydrogen-assisted stress-corrosion cracking if exposed to moisture. These fasteners are recommended for use only in dry-service conditions.

5. Indoor Swimming Pools

Indoor swimming pool environments are extremely corrosive to steel products. And some stainless steel is highly susceptible to stress corrosion cracking (SCC) under sustained loads in this environment. SCC can result in sudden failures. Instead of stainless steel, it is advised to use a duplex coated, post-hot-dip galvanized or ZMAX® coated low carbon steel for any load-bearing components used in swimming pool environments. Regular maintenance is strongly advised. See strongtie.com/corrosion for additional information.

Corrosion Information

Guidelines for Selecting Materials and Coatings

In the discussion and charts of this section, Simpson Strong-Tie presents a three-step system to determine which product coatings and base metals to use in a range of corrosion conditions. These are general guidelines that may not consider all relevant application criteria. Refer to product-specific information for additional guidance.

Simpson Strong-Tie evaluated the AWWA Use Categories (See AWWA U1-24) and ICC-ES AC257 Exposure Conditions and developed a set of corrosion resistance recommendations. These recommendations

address the coating systems and materials used by Simpson Strong-Tie for fastener, connector, and anchor products. Although the AWWA Use Categories and ICC-ES AC257 Exposure Conditions specifically address treated-wood applications and some common corrosion agents, Simpson Strong-Tie believes that its recommendations may be applied more generally to other application conditions, insofar as the service environments discussed are similar. You should consult with a corrosion engineer concerning the application where advisable.

Step 1 of 3 – Evaluate the Corrosion Conditions

- Dry Service:** Generally INTERIOR applications including wall and ceiling cavities, and in raised floor applications in enclosed buildings that have been designed to prevent condensation and exposure to other sources of moisture. Prolonged periods of wetness or elevated humidity during construction should also be considered, as this may constitute a Wet Service or Elevated Service condition. Dry Service is typical of AWWA UC1 and UC2 for wood treatment and AC257 Exposure Condition 1. Keep in mind that dry-service environment may contain airborne salts. AC257 Exposure Condition 2 reflects the presence of airborne salt in a dry-service environment and corrosion hazard to exposed metal surfaces. It does not include effects of treatment chemicals. This condition is generally considered in Elevated and Uncertain assessments.
- Wet Service:** Generally EXTERIOR construction in conditions other than elevated service. These include Exterior Protected and Exposed and General Use Ground Contact as described by AWWA UC4A. The AWWA U1 standard classifies exterior above-ground

treatments as Use Categories UC3 (A and B) depending on moisture run-off; and for exterior ground-contact levels of protection, it has Use Categories UC4 (A-C). ICC-ES AC257 considers the exterior exposure to be limited by the presence of treatment chemicals, and corrosion accelerators. In general, the AC257 Exposure Condition 1 includes AWWA Use Categories UC1 (interior/dry) and UC2 (interior/damp), while Exposure Condition 3 is a surrogate to UC3A, 3B, and 4A (exterior, above-ground and ground-contact, general use). The ICC-ES AC257 Exposure Conditions 2 and 4 are exposures that are salt environments.

- Elevated Service:** Includes fumes, fertilizers, soil, some preservative-treated wood (AWPA UC4B and UC4C), industrial-zone atmospheres, acid rain, salt air and other corrosive elements.
- Uncertain:** Unknown exposure, materials or treatment chemicals.
- Ocean/Water Front Service:** Marine environments that include airborne chlorides, salt air, and some salt splash. Environments with deicing salts are included.

Step 2 of 3 – Determine Your Corrosion Resistance Classification

Corrosion Resistance Classifications

Environment	Material to Be Fastened						FRT Wood
	Untreated Wood or Other Material	Preservative-Treated Wood				Other or Uncertain	
		SBX-DOT Zinc Borate	Chemical Retention ≤ AWWA, UC4A	Chemical Retention > AWWA, UC4A	ACZA		
Dry Service	Low	Low	Low	High	Medium	High	Medium ⁷
Wet Service	Medium	N/A	Medium	High	High	High	High
Elevated Service	High	N/A	Severe	Severe	High	Severe	N/A
Uncertain	High	High	High	Severe	High	Severe	Severe
Ocean/Water Front	Severe	N/A	Severe	Severe	Severe	Severe	N/A

Additional Considerations

- Always consider the importance of the connection as well as the cost of maintenance and replacement.
- If the information about treatment chemicals in an application is incomplete, or if there is any uncertainty as to the service environment of any application, Simpson Strong-Tie recommends the use of a Type 300 Series stainless steel. Simpson Strong-Tie has evaluated the corrosion effects of various formulations of wood treatment chemicals ACZA, ACQ, CCA, MCA, CA, and salt as corrosion accelerators. Simpson Strong-Tie has not evaluated all formulations and retentions of the named wood treatment chemicals other than to use coatings and materials in the severe category. Manufacturers may independently provide test results or other product information. Simpson Strong-Tie expresses no opinion regarding such information.
- Type 316/305/304 stainless-steel products are recommended where preservative-treated wood used in ground contact has a chemical retention level greater than those for AWWA UC4A; CA-C, 0.15 pcf

(pounds per cubic foot); CA-B, 0.21 pcf; micronized CA-C, 0.14 pcf; micronized CA-B, 0.15 pcf; ACQ-Type D (or C), 0.40 pcf. When wood treated with micronized CA-C and micronized CA-B with treatment retentions up to UC4B is in dry service, hot-dip galvanized fasteners and connectors may be suitable.

- Mechanical galvanizations C3 and N2000 should not be used in conditions that would be more corrosive than AWWA UC3A (exterior, above ground, rapid water run off).
- Some chemically treated wood may have chemical retentions greater than specification, particularly near the surface, making it potentially more corrosive than chemically treated wood with lower retentions. If this condition is suspected, use Type 316/305/304 stainless-steel, silicon bronze or copper fasteners.

- Some woods, such as cedars, redwood and oak, contain water-soluble tannins and are susceptible to staining when in contact with metal connectors and fasteners. Applying a quality finish to all surfaces of the wood prior to installation can help reduce staining.
- Anchors, fasteners and connectors in contact with FRT lumber shall be hot-dip galvanized or stainless steel, unless recommended otherwise by the FRT manufacturer. Many FRT manufacturers permit low-corrosion-resistant connector and fastener coatings for dry-service conditions.
- Simpson Strong-Tie does not recommend painting stainless-steel anchors, fasteners or connectors. Imperfections or damage to the paint can facilitate collection of dirt and water that can degrade or block the passive formation of the protective chromium oxide film. When this happens, crevice corrosion can initiate and eventually become visible as a brown stain or red rust. Painting usually does not improve the corrosion resistance of stainless steel.

Corrosion Information

Guidelines for Selecting Materials and Coatings (cont.)

Step 3 of 3 – Match Your Corrosion Resistance Classification to the Coatings and Materials Available

Not all products are available in all finishes. Contact Simpson Strong-Tie for product availability, ordering information and lead times.

Coatings and Materials Available for Connectors

Level of Corrosion Resistance	Coating or Material	Description	
Connectors			Fastener Material or Finish
Low	Gray or Black Paint	Organic paint intended to protect the product while it is warehoused and in transit to the jobsite.	Bright, Hot-Dip Galvanized, Mechanically Galvanized, or Double-Barrier Coating
	Powder Coating	Baked-on paint finish that is more durable than standard paint.	
	Galvanized	Standard (G90) zinc-galvanized coating containing 0.90 oz. of zinc per square foot of surface area (total both sides).	
Medium	 ZMAX [®] G185	Galvanized (G185) 1.85 oz. of zinc per square foot of surface area (hot-dip galvanized per ASTM A653) total for both sides. Products with a powder-coat finish over a ZMAX [®] base have the same level of corrosion resistance.	Hot-Dip Galvanized, Mechanically Galvanized, or Double-Barrier Coating <i>* Bright fasteners may be used with ZMAX or HDG connectors where low corrosion resistance is allowed.</i>
	 HDG GALVANIZED [®]	Products are hot-dip galvanized after fabrication (14 ga. and thicker). The coating weight increases with material thickness. The minimum average coating weight is 2.0 oz./ft. ² (per ASTM A123) total for both sides. Anchor bolts are hot-dip galvanized per ASTM F2329.	
High/Severe	 316 Stainless Steel	Type 316 stainless steel is a nickel-chromium austenitic grade of stainless steel with 2–3% molybdenum. Type 316 stainless steel is not hardened by heat treatment and is inherently nonmagnetic. It provides a level of corrosion protection suitable for severe environments, especially environments with chlorides.	Type 316 Stainless Steel

Dry Service



Wet Service



Elevated Service / Severe



Corrosion Information

Guidelines for Selecting Materials and Coatings (cont.)

Step 3 of 3 – Match Your Corrosion Resistance Classification to the Coatings and Materials Available (cont.)

Not all products are available in all finishes. Contact Simpson Strong-Tie for product availability, ordering information and lead times.

Coatings and Materials Available for Fasteners and Anchors

Level of Corrosion Resistance	Coating or Material	Description	Applicable Products
Fasteners and Anchors			
Low	Bright	No surface coating.	Nails
	Black and Gray Phosphate	Black and gray phosphate coatings provide a minimum level of corrosion resistance and are intended for dry, low-corrosion applications.	Strong-Drive® TB and TF WOOD-TO-STEEL Screws DWF Drywall-to-CFS Screw
	Blue-Bright Zinc	Electroplated zinc applied in accordance with ASTM F1941. In the ASTM B117 salt spray test, blue-bright zinc provides at least 36 hours of corrosion protection before the first appearance of red rust.	Strong-Drive FPHSD FRAMING-TO-CFS Screw Strong-Drive Self-Drilling X Metal Screw Self-Drilling E Metal Screw
	Zinc Plating	Electroplated zinc coating applied in accordance with ASTM B633, Class SC1, Type III for use in dry service and low-corrosive environmental conditions.	Titen HD® Heavy-Duty Screw Anchor
	Zinc Plating with Baked-On Ceramic Coating	A baked ceramic barrier coating applied over top of electroplated zinc provides increased protection in mildly corrosive environments.	Titen Turbo™ Concrete and Masonry Screw
	Yellow Zinc	Electroplated zinc applied in accordance with ASTM F1941. In the ASTM B117 salt spray test, yellow zinc provides at least 72 hours of corrosion protection before the first appearance of red rust.	DWFS Drywall-to-CFS Screw Strong-Drive PHSD FRAMING-TO-CFS Screw Strong-Drive PPHD SHEATHING-TO-CFS Screw
Medium	 ASTM A153, Class D	Hot-dip galvanized fasteners 3" and smaller in diameter in accordance with ASTM A153, Class D. Hot-dip galvanized fasteners are compliant with the 2018, 2021 and 2024 IRC and IBC.	Strong-Drive SCN SMOOTH-SHANK CONNECTOR Nail
	Quik Guard® Coating	Quik Guard coatings are proprietary coating systems that consist of an electroplated zinc base layer and organic top coats. The corrosion resistance is equivalent to hot-dip galvanization (ASTM A153, Class D) in some exposures and in most non-marine environments, and described by ICC-ES, AC257 Exposures 1 and 3.	Strong-Drive XM MEDIUM-HEAD, XL LARGE-HEAD and XE EXTERIOR STRUCTURAL METAL Screws CBSDQ Sheathing-to-CFS Screw
	Type 410 Stainless Steel with Protective Top Coat	Carbon martensitic grade of stainless steel that is inherently magnetic, with an added protective top coat. This material can be used in mild atmospheres and many mild chemical environments.	Titen Stainless-Steel Concrete and Masonry Screw
	Mechanically Galvanized Coating, ASTM B695	Strong-Drive SD Connector screws are manufactured with a mechanically applied zinc coating in accordance with ASTM B695, Class 55, with a supplemental overcoat. Titen HD Mechanically Galvanized anchors comply with ASTM B695, Class 65. These fasteners are compatible with painted and zinc-coated (G90 and ZMAX®) connectors and are recognized in evaluation reports that can be found on strongtie.com .	Strong-Drive SD CONNECTOR Screw Titen HD Heavy-Duty Screw Anchor Mechanically Galvanized
	N2000® Mechanically Galvanized	Mechanically applied proprietary zinc coating with a supplementary overcoat. In the ASTM B117 salt spray test at 1000 hours of exposure, fasteners with the N2000 coating exhibit average red rust less than 15%.	Strong-Drive TB and TF WOOD-TO-STEEL Screws
Double-Barrier Coating	The Simpson Strong-Tie double-barrier coating is a proprietary coating that provides a level of corrosion resistance that is equivalent to hot-dip galvanization (ASTM A153, Class D) in most non-marine environments and as described by ICC-ES, AC257 Exposures 1 and 3.	Strong-Drive SDS HEAVY-DUTY CONNECTOR Screw	
High/Severe	 ASTM A153, Class C	Hot-dip galvanized in accordance with ASTM A153, Class C. These hot-dip galvanized fasteners have a minimum average of 1.25 oz./ft.2 of zinc coating and are compliant with the 2018, 2021 and 2024 IRC (R317.3) and IBC.	Strong-Drive SDWH™ TIMBER-HEX HDG Screw
	Type 304 Stainless Steel	Type 304 stainless steel is a nickel-chromium austenitic grade of stainless steel. It is not hardened by heat treatment and is inherently nonmagnetic. It provides very good corrosion resistance and is suitable for use in many corrosive environments. Fasteners and anchors made from Type 304 stainless steels are compliant with the 2018, 2021 and 2024 IBC and IRC.	Stainless-Steel Titen HD Heavy-Duty Screw Anchor
	 Type 316 Stainless Steel	Type 316 stainless steel is a nickel-chromium austenitic grade of stainless steel with 2-3% molybdenum. It provides a level of corrosion protection suitable for severe environments, especially environments with chlorides. Type 316 stainless-steel fasteners are compliant with the 2018, 2021 and 2024 IRC and IBC.	Strong-Drive SCNR™ RING-SHANK CONNECTOR Nail Strong-Drive SDS HEAVY-DUTY CONNECTOR Screw Strong-Drive SD CONNECTOR SS Screw Stainless-Steel Titen HD Heavy-Duty Screw Anchor

Fastening Information


General Info



Round Holes

Purpose:
To fasten a connector.

Fill Requirements:
Always fill, unless noted otherwise.



Obround Holes

Purpose:
To make fastening a connector in a tight location easier.

Fill Requirements:
Always fill, unless noted otherwise.



Hexagonal Holes

Purpose:
To fasten a connector to concrete or masonry.


Fill Requirements:
Always fill when fastening a connector to concrete or masonry.



Triangular Holes

Purpose:
To increase a connector's strength or to achieve max. strength.


Fill Requirements:
When the designer specifies max. nailing.



Diamond Holes

Purpose:
To temporarily fasten a connector to make installing it easier.


Fill Requirements:
None.



Square Holes

Purpose:
To provide fastening option for unique custom designs

Fill Requirements:
Only when specified by designer.



Pilot Holes

Tooling holes for manufacturing purposes. No fasteners required.


To achieve the loads shown in this catalog, the designer must verify that the self-drilling screws used for connector installation have P_{nv}/Ω and P_{nts}/Ω values greater than or equal to the values tabulated in this table.

Hex head screws shown are required for connectors in this catalog. Where sheathing or finishes will be applied over the screws and low-profile heads are needed (such as with bracing connectors, hurricane ties and stud-plate ties), the designer is to ensure that the minimum screw head diameter complies with ASME B18.6.4.

Minimum ASD Loads for Screws (lb.)

Screw No. Designation	Nominal Diameter, d (in.)	Washer Diameter, d _w (in.)	Allowable Screw Shear Strength (P _{nv} /Ω)	Allowable Shear Connection Strength (P _{nv} /Ω, P _{nv} s/Ω)					Allowable Screw Tension Strength (P _{nts} /Ω)	Allowable Tensile Pull-Out Strength (P _{not} /Ω, P _{nts} /Ω)				
				Steel Thickness mil (ga.)						Steel Thickness mil (ga.)				
				33-33 (20-20)	43-43 (18-18)	54-54 (16-16)	68-68 (14-14)	97-97 (12-12)		33 (20)	43 (18)	54 (16)	68 (14)	97 (12)
#8	0.164	0.318	291	164	244	291	291	291	631	72	94	171	215	307
#10	0.190	0.375	554	177	263	535	554	554	759	84	109	198	249	356
#12	0.216	0.375	769	189	280	570	769	769	845	95	124	225	283	404
#14	0.242	0.500	956	200	296	603	852	956	1,219	107	139	252	318	453

1. Allowable loads are per AISI S-100 and are for use when utilizing the traditional Allowable Stress Design methodology. The tabulated loads may be multiplied by a Factor of Safety (Ω) of 3 to determine the screw nominal strength. The LRFD load may be determined by multiplying the nominal screw load by a Resistance Factor (φ) of 0.50.
2. Allowable loads may not be increased for wind or seismic load unless otherwise noted.
3. Allowable loads are based on cold-formed steel members with a minimum yield strength, F_y, of 33 ksi and tensile strength, F_u, of 45 ksi for 43 mil (18 ga.) and thinner, and a minimum yield strength of 50 ksi and tensile strength of 65 ksi for 54 mil (16 ga.) and thicker.
4. Allowable loads are based on design steel thickness for 33 mil = 0.0346", 43 mil = 0.0451", 54 mil = 0.0566", 68 mil = 0.0713", and 97 mil = 0.1017" per AISI S240, Table A5-1.
5. Self-drilling tapping screw fasteners for steel-to-steel connections used for connectors in this catalog shall be in compliance with ASTM C1513.
6. Minimum required screw length is the greater of ¾" and the minimum length required for the screw to extend through the steel connection a minimum of (3) exposed threads per AISI S240, Section C4.1 General Provisions Standard, Sect. D1.3.
7. Screw diameters per AISI S240, Table C-B1.5.1.1-1.
8. Size ¼"-diameter self-tapping screws may be substituted for #14 screws.



Shown Actual Size

See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.

Screw Suitability

Screw Point Type	Screw Size	Maximum Material Thickness ^{1,2}	
		(in.)	(mm)
#2	#6	0.100	2.54
	#8	0.100	2.54
	#10	0.100	2.54
#3	#7	0.125	3.18
	#8	0.140	3.56
	#10	0.175	4.45
	#12	0.210	5.33
#4	#14	0.220	5.59
	#12	0.250	6.35
#5	#14	0.250	6.35
	#12	0.500	12.70
	#14	0.500	12.70

1. Total thickness of all steel, including any spacing between layers.
2. Drill and tap capacities may vary.
3. Table is guideline only; see individual product for specific maximum material thickness.

CFS Framing Member

Mil	Gauge	Design Thickness		Minimum Thickness	
		(in.)	(mm)	(in.)	(mm)
18	25	0.0188	0.48	0.0179	0.45
27	22	0.0283	0.72	0.0269	0.68
30	20 (drywall)	0.0312	0.79	0.0296	0.75
33	20 (structural)	0.0346	0.88	0.0329	0.84
43	18	0.0451	1.14	0.0428	1.09
54	16	0.0566	1.44	0.0538	1.37
68	14	0.0713	1.81	0.0677	1.72
97	12	0.1017	2.58	0.0966	2.45

1. One "mil" is 1/1000 (0.001) of an inch. Mil thickness measures the uncoated base material.



CFS DESIGNER™

Software Solutions

Overview

Efficient, accurate, AISI-compliant design of cold-formed steel (CFS) structures is made possible by Simpson Strong-Tie CFS Designer software. Powerful tools automate the design of common CFS systems, complicated AISI provisions, complex loading scenarios and more. A modern development platform and intuitive user interface enable fast input and simplify file management, as multiple systems can be saved within a single job file. Output is generated in PDF files that can be saved separately, if needed.

Features

Wall Framing design tools for load-bearing framing and non-load-bearing curtain walls.

Modules include:

- Wall stud
- 1-span opening
- 2-span opening
- Kneewall
- Stacked wall
- Spandrel

Joist Framing design tools for floor that automate pattern loading, and rafter design that designs load combinations and pinched axial loads.

Modules include:

- Floor joist
- Rafters

General Framing design tools for general design.

Modules include:

- General interaction
- Beam input

X-Bracing design tools to design elements and components with simple and robust design for LFRS (lateral force resisting system) up to eight stories that incorporate AISI S240 and S400. Modules include:


- Simple
- LFRS

Shearwall design tools to design elements and components with simple and robust design for LFRS up to eight-story shearwall design that incorporate AISI S240 and S400 with the LFRS module.


Modules include:

- Simple
- LFRS

Wind Module design tools to design components and cladding loads for walls and roof. Wind module can be imported to wall, opening, spandrel and kneewall modules.



Wall Stud design tool allows up to three-span beam with overhangs on each end, as well as importing of wind loads, additional slopes, moment or point loads, and design connections.



Wall Opening design tool is a simple and intuitive layout that allows design flexibility in all framing components of the opening.

General Information and Notes

General Information and Notes for Curtain-Wall Framing Connectors

Slide-clip and fixed-clip curtain-wall framing connectors represent key components that comprise a continuous load path between curtain-wall steel-stud framing and primary building structure.

In light-frame cold-formed steel construction, primary building structures typically consist of structural steel or structural concrete base material. Hence, connectors for curtain-wall framing are designed to anchor to steel or concrete to resist tension and compression load, perpendicular to wall, due to wind pressure, shear load due to gravity weight of the CFS framing, and in-plane load, parallel to wall due to earthquake or high wind force.

General Notes

1. Allowable loads are for use when utilizing the traditional Allowable Stress Design methodology. Contact Simpson Strong-Tie for LRFD loads unless otherwise noted.
2. Allowable loads may not be increased for wind or earthquake load.
3. Allowable loads are based on cold-formed steel members with a minimum yield strength, F_y , of 33 ksi and tensile strength, F_u , of 45 ksi for 43 mils (18 ga.) and thinner, and a minimum yield strength of 50 ksi and tensile strength of 65 ksi for 54 mils (16 ga.) and thicker. (U.O.N.)
4. Clips do not replace lateral or stability bracing. Design of bracing is the responsibility of the designer.
5. It is the responsibility of the designer to verify the adequacy of the stud. Allowable loads are based on clips installed an adequate distance away from penetrations, notches, ends of studs and other conditions that may affect the clip performance.
6. It is the responsibility of the designer to check the adequacy of the supporting structure for loads imposed by connectors.
7. Industry studies show that hardened fasteners can experience performance problems in wet or corrosive environments. Accordingly, use these products in dry and non-corrosive environments only.

Anchorage to Structural Steel

Anchor to structural steel using self-drilling screws, powder-actuated fasteners, or welding are based on installation in a minimum $\frac{3}{16}$ " thick structural steel with $F_y = 36$ ksi. (U.O.N.)

1. Allowable loads for #12–24 self-drilling screws are based on a minimum nominal shear strength, P_{nvs} , of 2,307 lb. and nominal tension strength, P_{nts} , of 2,535 lb. It is the responsible of the designer to select the proper length fasteners based on installation need. Screw length must ensure fastener extends through the connection a minimum of three exposed threads.
2. Allowable loads for Simpson Strong-Tie® PDPAT-62KP powder-actuated "tophat" fasteners also apply to alternate fasteners with a minimum shank 0.157", a minimum head diameter of 0.300", a minimum allowable shear of 410 lb. and tension strength of 260 lb. for A36 steel, and a minimum allowable shear of 420 lb. and tension strength of 305 lb. for A572 or A992 steel per ESR-2138. "Tophat" fasteners are recommended to ensure adequate clamping force and consistent installations.
3. Welding shall be in accordance with American Welding Society AWS D1.1 or D1.3, as applicable. Allowable loads for welded connections require electrodes with minimum tensile strength of 70 ksi. Welding galvanized steel may produce harmful fumes; follow proper welding procedures and precautions. Unless otherwise noted, Simpson Strong-Tie connectors cannot be welded.

Post-Installed Anchorage to Structural Concrete

Anchors to concrete or masonry, such as Titen Turbo™ screws, Titen HD® screw anchors, Strong-Bolt® 2 wedge anchors, or SET-3G®, ET-3G™ or AT-3G™ adhesives, require installation in concrete with a minimum $f'_c = 2,500$ psi and a maximum $f'_c = 4,000$ psi. Reference the current *Anchoring, Fastening, Restoration and Strengthening Systems for Concrete and Masonry* catalog at strongtie.com for more information.

1. Titen Turbo is a screw anchor for use in uncracked concrete as well as uncracked masonry. Titen Turbo is available in $\frac{1}{4}$ " diameter.
2. Titen HD is a heavy-duty screw anchor for use in cracked and uncracked concrete as well as uncracked masonry. Titen HD is available in $\frac{1}{4}$ ", $\frac{3}{8}$ " and $\frac{1}{2}$ " diameters for anchorage used in curtain-wall framing.
3. Strong-Bolt 2 is a wedge-type expansion anchor designed for optimal performance in cracked and uncracked concrete as well as uncracked masonry. Strong-Bolt 2 is available in $\frac{1}{4}$ ", $\frac{3}{8}$ " and $\frac{1}{2}$ " diameters for anchorage common to CFS construction or in larger diameters for structural applications.

Anchorage to Cross-Laminated Timber (CLT)

Anchoring to Cross-Laminated Timber (CLT) requires the use of Simpson Strong-Tie wood fasteners such as the SDHR Combo-Head Screw, SDS Heavy-Duty Connector Screw, SD Connector Screw or SDWH™ Timber-Hex HDG Screw. Published anchoring values are applicable to CLT consisting of SPF or better, and are designated as being applicable for installation into the side grain or end grain of the lamina. Fastener spacing, and edge and end distances listed for attachment of cold-formed steel connectors and steel struts must be followed to achieve published load values. The allowable anchorage loads are also limited by the allowable connector loads. Use the minimum tabulated values from the connector and anchorage load tables as applicable. Reference the current *Fastening Systems* catalog on strongtie.com for additional fastener information.

Special Order Custom Clips and Connectors

Does your job require custom CFS connectors?

We can provide the solutions that you need with a fast turnaround time.


Simpson Strong-Tie can make a variety of flat and bent steel clips and connectors for cold-formed steel framing. Most custom clips can be punched with different holes and slots per your job specifications.

Material: 229 mil (3 ga.) maximum, 33 mil (20 ga.) minimum mill-certified steel (carbon and Type 316L stainless steel)

Finish: Galvanized (G90 or G185), Simpson Strong-Tie® gray paint. Contact Simpson Strong-Tie for availability.

To Obtain Quote:

- Supply a detailed drawing, in .dwg, .dxf or .pdf formats, complete with all dimensions, hole diameters and centerline locations, bend angles, steel strength (min. F_y and F_u), thickness (mil and/or ga.) and finish: (galvanized to G90, G185) or Simpson Strong-Tie gray paint (specify)
- Total shape and size up to a maximum of 48" x 96" (approx. $\frac{1}{16}$ " tolerance)
- Simpson Strong-Tie does not provide product engineering or load values for special-order custom clips and connectors
- Contact Simpson Strong-Tie for pricing and leadtime. Call **(800) 999-5099** to ask for your local CFS Specialist for assistance.
- For additional information, please refer to Important Information and General Notes on pp. 16–19 and 28.



State of the art laser cutting machinery is used to create high tolerance custom connectors for your project.

Custom Clip Request Example:

Quantity: XX pieces


Dimensions: Per the attached detailed drawing (.dwg, .pdf or .dxf format). Drawing must be fully dimensioned, including:

- Overall dimensions
- Leg dimensions
- Bend angles (if required)
- Hole/slot sizes and centerlines (if required)

Thickness: 54 mil (16 ga.)

Strength: Min. Yield Strength (F_y) = 33 ksi,
Min. Tensile Strength (F_u) = 45 ksi

Finish: Galvanized (G90)



Innovative Solutions for Curtain-Wall Framing

Simpson Strong-Tie has developed a line of connectors for use with curtain-wall steel stud framing. Curtain-wall projects require a variety of connectors that provide a load path from the curtain wall to the primary structure for wind loads, seismic loads and dead loads. Slide-clip connectors enable the structural building frame to deflect independently of the curtain-wall system. Fixed-clip connectors support the dead load of a curtain wall from the structural frame. Fixed clips have the added benefit of providing connector solutions for load-bearing walls and for roof systems utilizing steel trusses and rafters.

Our connectors for curtain-wall construction accommodate many different bypass framing applications in a variety of standoff conditions. We also offer connectors for head-of-wall and strut applications.


Tailored to Your Design

Our standard slide clips accommodate either $\frac{3}{4}$ " or 1" of both upward and downward movement, equivalent to an L/360 live-load deflection for a 30' span. Our standard clips also accommodate standoffs as large as 25". For deflections greater than 1", or job-specific conditions, Simpson Strong-Tie can provide custom clips to suit most framing needs (see p. 29).

Complete, Tested Solutions

Designers of curtain walls will often know the capacity of a connector, but since the capacity does not take into account the way in which the connector is anchored to the supporting structure, the designer must then manually calculate this important aspect of the connection design. These calculations are complicated by considerations of eccentric and prying forces that often exist but are difficult to predict. Through comprehensive testing Simpson Strong-Tie provides total, code-listed connector solutions. Our testing extends from the capacity of the connector and its attachment to the framing, to the anchorage of the connector to the primary structure. By providing complete data on the entire connection system, we save the designer time and ensure that all forces, including eccentric and prying forces, are adequately considered.

As with all Simpson Strong-Tie® products, our slide-clip and fixed-clip connectors for curtain-wall steel stud framing carry our promise of quality and performance, and are backed by prompt, knowledgeable service.



SCB™/MSCB™ Bypass Framing Slide-Clip Connectors



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The SCB/MSCB slide-clip connectors are high-performance connectors for bypass framing applications designed to reduce design time and overall installed cost. Various anchorage methods have been tested, and the resulting allowable loads eliminate the need to design connector anchorage. The SCB/MSCB can accommodate applications that typically require two parts with a single connector, reducing material and labor cost. These connectors are manufactured in five different lengths to accommodate a variety of standoff conditions and steel-stud sizes.

Features:

- Provides a full 1" of both upward and downward movement
- The precision-manufactured shouldered screws provided with the SCB/MSCB connector are designed to prevent overdriving and to ensure the clip functions properly
- Strategically placed stiffeners, embossments and anchor holes maximize connector performance
- Simpson Strong-Tie® No-Equal® stamps mark the center of the slots to help ensure correct shouldered-screw placement

Material: SCB — 54 mil (16 ga.); MSCB — 68 mil (14 ga.)

Finish: Galvanized (G90)

Installation:


- Use the specified type and number of anchors.
- Use the specified number of XLSH34B1414 #14 shouldered screws (included). Install shouldered screws in the slots adjacent to the No-Equal stamp.
- Use a maximum of one screw per slot.
- For installations to wood framing, see Simpson Strong-Tie engineering letter L-CF-DEFCLIPW at strongtie.com.

Codes: See p. 15 for Code Reference Key Chart


Order and Dimension Information:

Model No.	Ordering SKU	Length L (in.)	Thickness mil (ga.)	Package Quantity	
				Connectors	Shoulder Screws
SCB43.5	SCB43.5-KT	3.5	54 (16)	25	55
SCB45.5	SCB45.5-KT	5.5	54 (16)	25	83
MSCB45.5	MSCB45.5-KT	5.5	68 (14)	25	83
SCB47.5	SCB47.5-KT	7.5	54 (16)	25	83
MSCB47.5	MSCB47.5-KT	7.5	68 (14)	25	83
SCB49.5	SCB49.5-KT	9.5	54 (16)	25	83
SCB411.5	SCB411.5-KT	11.5	54 (16)	25	83


Replacement #14 shoulder screws for SCB/MSCB connectors are XLSH34B1414-RP83.




XLSH34B1414
#14 Shouldered Screw for Attachment to Stud Framing (included)




✓ **SCB43.5**




✓ **SCB45.5**
(MSCB45.5 similar)



✓ **SCB47.5**
(MSCB47.5 similar)




✓ **SCB49.5**



✓ **SCB411.5**

US Patent. See strongtie.com/patent.




✓ **SCB/MSCB**

*3/4" for SCB43.5

SCB™/MSCB™ Bypass Framing Slide-Clip Connectors

Deflection Connectors



Typical SCB/MSCB Installation

SCB/MSCB Installation at Steel Beam

Typical SCB/MSCB Installation with Stud Strut


SCB/MSCB Allowable Connector Loads (lb.)

Model No.	Connector Material Thickness mil (ga.)	L (in.)	No. of #14 Shouldered Screws ¹	Stud Thickness												Code Ref.
				33 mil (20 ga.)			43 mil (18 ga.)			54 mil (16 ga.)			68 mil (14 ga.)			
				F ₁ ^{3,4}	F ₂ ²	F ₃ ²	F ₁ ^{3,4}	F ₂ ²	F ₃ ²	F ₁ ^{3,4}	F ₂ ²	F ₃ ²	F ₁ ^{3,4}	F ₂ ²	F ₃ ²	
SCB43.5	54 (16)	3½	2	175	480	480	260	570	640	290	705	905	405	705	905	IBC, FL, LA
SCB45.5	54 (16)	5½	2	165	455	480	260	570	640	290	705	905	405	705	905	
			3	165	625	625	260	930	930	330	990	1,260	405	990	1,260	
MSCB45.5	68 (14)	5½	2	165	455	480	260	720	640	360	1,055	1,115	500	1,115	1,475	
			3	165	625	625	260	995	930	410	1,220	1,930	500	1,365	1,930	
SCB47.5	54 (16)	7½	2	165	455	480	260	570	640	285	705	875	375	705	875	
			3	165	625	625	260	930	930	285	990	1,260	375	990	1,260	
MSCB47.5	68 (14)	7½	2	165	455	480	260	720	640	330	1,055	1,115	460	1,115	1,475	
			3	165	625	625	260	995	930	330	1,220	1,930	460	1,365	1,930	
SCB49.5	54 (16)	9½	2	165	455	480	260	640	640	285	705	905	335	705	905	
			3	165	625	625	260	930	930	285	990	1,260	335	990	1,260	
SCB411.5	54 (16)	11½	2	165	455	480	260	640	640	285	990	905	335	990	905	
			3	165	625	625	260	860	930	285	990	1,260	335	990	1,260	


- When the SCB or MSCB connector is used with two shouldered screws, the screws may be installed in any two slots.
- Allowable loads are based on clips installed with (4) #12–14 screws in the anchor leg. For other anchorage installations, the capacity of the connection system will be the minimum of the tabulated value and the allowable load from the SCB/MSCB Allowable Anchorage Loads table on p. 33.
- Anchorage to the supporting structure using welds or a minimum of (2) fasteners is required.
- Tabulated F₁ loads are based on assembly tests with the load through the centerline of stud. Tested failure mode due to screw pullout; therefore compare F₁ against F_p calculated per ASCE 7-16 and ASCE 7-22 Chapter 13 with values for “Fasteners of the connecting system for exterior nonstructural wall elements and connections” as specified in Table 13.5-1.

SCB/MSCB Standoff Distances

Model No.	L (in.)	No. of #14 Shouldered Screws	Maximum Standoff (in.)
SCB43.5	3½	2	1
SCB45.5	5½	2	2¾
		3	1½
MSCB45.5	5½	2	2¾
		3	1½
SCB47.5	7½	2	4¾
		3	3½
MSCB47.5	7½	2	4¾
		3	3½
SCB49.5	9½	2	6¾
		3	5½
SCB411.5	11½	2	8¾
		3	7½



SCB™/MSCB™ Bypass Framing Slide-Clip Connectors





Deflection Connectors

SCB/MSCB Allowable Anchorage Loads (lb.)

Anchorage Type	Minimum Base Material	No. of Anchors	SCB		MSCB	
			F ₁	F ₂	F ₁	F ₂
Attached to Steel or Concrete						
#12–24 self-drilling screws Strong-Drive® X and XL Metal screws	A36 steel 3/16" thick	2	310	1,115	380	1,150
		3	460	1,645	565	1,725
		4	615	2,230	755	2,300
Simpson Strong-Tie® 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	A36 steel 3/16" thick	2	—	440	—	520
		3	—	585	—	780
		4	—	895	—	1,040
Simpson Strong-Tie 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	A572 or A992 steel 3/16" thick	2	—	585	—	610
		3	—	800	—	915
		4	—	1,170	—	1,220
Weld E70XX electrodes	A36 steel 3/16" thick	Hard side: 2"	1,205	1,740	1,485	3,350
		Free side: 1"				
Simpson Strong-Tie 1/4" x 1 3/4" Titen Turbo™ TNT25134H	Concrete f _c = 2,500 psi	2	—	330	—	330
		3	—	460	—	460
		4	—	595	—	595
Attached to CLT			F₁ (160)	F₂ (160)	F₁ (160)	F₂ (160)
# 10 x 2 1/2" Strong-Drive SD Connector Screw SD10212	3-ply min. (4 1/8") SPF CLT into side grain	4	595	705	595	705
	3-ply min. (4 1/8") SPF CLT into end grain	4	400	375	400	375

- For additional important information, see General Information and Notes on p. 28.
- Allowable anchorage loads are also limited by the SCB/MSCB Allowable Connector Load table on p. 32. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- Tabulated F₁ loads are based on assembly tests with the load through the centerline of stud. Tested failure mode due to screw pullout; therefore compare F₁ against F_p calculated per ASCE 7-16 and ASCE 7-22 Chapter 13 with values for "Fasteners of the connecting system for exterior nonstructural wall elements and connections" as specified in Table 13.5-1.
- F₃ is a compression load and is not a controlling factor for anchor design.
- SD10212 screw is designed to thread into SCB/MSCB anchor hole without enlargement of clip hole.
- Loads (160) have been increased for wind or earthquake loading, with no further increase allowed. Reduce where other loads govern.



SCS Hybrid Bypass Framing Connector

Deflection Connectors

The first product of its type to undergo full-scale cyclic research testing to determine its load capacities in real-world conditions, the SCS is a hybrid clip designed specifically to allow both slide-clip or fixed-clip applications in areas of high seismic activity. Everything about the SCS clip — from its heavy-duty 10- and 12-gauge steel manufacturing to its strategically placed darts to the location of its fastener slots and holes — has been engineered to provide exceptional resistance to in-plane seismic loads. Because slide-clip testing shows that attachment at the first slot is most critical to in-plane capacity, the SCS is designed to accommodate two large washer screws (included) at the first slot attached to the stud.

The SCS clip is the most versatile clip on the market making it the ideal clip in seismic and non-seismic areas. This clip has three prepunched oblong slots for slide applications and a pattern of round holes for fixed-clip applications to meet a range of load needs. In addition, the support leg features anchor holes for concrete supports using 1/4"- or 1/2"-diameter concrete screws or bolts, plus smaller holes for steel supports using powder-actuated fasteners such as Simpson Strong-Tie® PDPAT 0.157"-diameter pins or #12 self-drilling Strong-Drive® XL Large-Head Metal screws.

Features:

- 3 1/2", 6" and 8" lengths
- Slide slots used with shouldered washer screws (included) allow a full 1" of vertical deflection
- Precision-located stiffeners enhance strength while allowing ductility
- Simpson Strong-Tie No-Equal® stamps alongside slide slots indicate proper screw placement
- Dual-function clip with prepunched slots for slide application and small round holes for fixed application

Material: 14 ga. (68 mil), 12 ga. (97 mil) and 10 ga. (118 mil), 50 ksi

Finish: Galvanized (G90)

Installation:


- SCS32-5 permits 1" maximum standoff for fixed applications and 1 1/2" maximum for slide applications. SCS62-5 and SCS82-5 maximum standoff are 2 1/4" for fixed applications and 3" for slide applications.
- Use the specified type and number of anchors.
- Slide applications — Use the specified number of XLSH78B1414 #14 shouldered screws (included). Install the screws in the slots adjacent to the No-Equal stamps.
- Fixed applications — Use the specified number of #10 screws (not included) in the designated screw holes.

Codes: See p. 15 for Code Reference Key Chart.

Order and Dimension Information:

Model No.	Ordering SKU	Thickness mil (ga.)	L (in.)	A (in.)	B (in.)	Package Quantity	
						Connectors	Shoulder Screws
SCS32-5/97	SCS32-5/97-KT25	97 (12)	3 1/2	1 1/2	—	25	55
NEW SCS62-5/68	SCS62-5/68-KT25	68 (14)	6	1 1/2	1 1/2	25	83
SCS62-5/97	SCS62-5/97-KT25	97 (12)	6	1 1/2	1 1/2	25	83
SCS62-5/118	SCS62-5/118-KT25	118 (10)	6	1 1/2	1 1/2	25	83
SCS82-5/118	SCS82-5/118-KT25	118 (10)	8	1 1/2	1 1/2	25	83


Replacement #14 shoulder screws for SCS connectors are XLSH78B1414-R83



SCS32-5/97


Clip features designed to dramatically increase in-plane loading resistance. Load rated per ICC-ES AC261.

US Patent. See strongtie.com/patent.




SCS62-5/68, SCS62-5/97, SCS62-5/118

NEW



SCS82-5/118




XLSH78B1414
#14 Shouldered Screw
for Attachment to Stud Framing Slide Application (included)


SCS Hybrid Bypass Framing Connector

SCS Slide-Clip Allowable Connector Loads (lb.)


Model No.	Framing Members Thickness mil (ga.)	Fasteners to Framing Member		Max. Standoff Distance (in.)	Allowable Loads (lb.)		
		Fastener Pattern	No. of #14 Shouldered Screws		In-Plane Load F ₁	Tension Load F ₂	Comp. Load F ₃
SCS32-5/97	33 (20)	S1	2	1 1/2	190	395	395
SCS62-5/68		S1	3	1 1/2	95	395	445
		S2	3	3	95	395	445
SCS62-5/97		S1	3	1 1/2	190	590	705
	S2	3	3	190	590	705	
SCS62-5/118	33 (20)	S1	3	1 1/2	250	605	705
SCS62-5/118		S2	3	3	250	605	705
		S1	3	1 1/2	250	605	705
SCS82-5/118		S2	3	3	250	605	705
SCS32-5/97	43 (18)	S1	2	1 1/2	290	500	500
SCS62-5/68		S1	3	1 1/2	135	795	760
		S2	3	3	135	795	760
SCS62-5/97		S1	3	1 1/2	350	830	1,080
	S2	3	3	335	830	1,080	
SCS62-5/118	43 (18)	S1	3	1 1/2	435	875	1,080
SCS62-5/118		S2	3	3	435	875	1,080
		S1	3	1 1/2	435	875	1,080
SCS82-5/118		S2	3	3	435	875	1,080
SCS32-5/97	54 (16)	S1	2	1 1/2	535	890	890
SCS62-5/68		S1	3	1 1/2	255	975	1,685
		S2	3	3	255	975	1,685
SCS62-5/97		S1	3	1 1/2	655	1,520	1,880
	S2	3	3	620	1,520	1,600	
SCS62-5/118	54 (16)	S1	3	1 1/2	655	1,795	2,185
SCS62-5/118		S2	3	3	620	1,795	2,185
		S1	3	1 1/2	655	1,795	2,185
SCS82-5/118		S2	3	3	620	1,795	2,185
SCS32-5/97	68 (14)	S1	2	1 1/2	535	925	925
SCS62-5/68		S1	3	1 1/2	705	975	1,685
		S2	3	3	665	975	1,685
SCS62-5/97		S1	3	1 1/2	705	1,695	2,000
	S2	3	3	665	1,695	1,705	
SCS62-5/118	68 (14)	S1	3	1 1/2	705	2,065	2,325
SCS62-5/118		S2	3	3	665	2,065	2,325
		S1	3	1 1/2	705	2,065	2,325
SCS82-5/118		S2	3	3	665	2,065	2,325
SCS32-5/97	97 (12)	S1	2	1 1/2	650	925	925
SCS62-5/68		S1	3	1 1/2	705	975	1,685
		S2	3	3	670	975	1,685
SCS62-5/97		S1	3	1 1/2	975	1,695	2,000
	S2	3	3	925	1,695	1,705	
SCS62-5/118	97 (12)	S1	3	1 1/2	975	2,065	2,325
SCS62-5/118		S2	3	3	925	2,065	2,325
		S1	3	1 1/2	975	2,065	2,325
SCS82-5/118		S2	3	3	925	2,065	2,325




Typical SCS Slide-Clip Installation



Typical SCS Slide-Clip Installation with Stud Strut



SCS62-5
1 1/2" Maximum Standoff
(Pattern S1 — reference p. 37 for all fastener patterns)




SCS62-5
3" Maximum Standoff
(Pattern S2 — reference p. 37 for all fastener patterns)

- For additional important information, see General Information and Notes on p. 28.
- SCS Allowable Connector Loads are also limited by the SCS Anchorage Load tables on pp. 38–39. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- See illustrations on p. 37 for fastener placement to stud framing.
- Tabulated F₁ loads are based on assembly tests with the load through the centerline of the stud. Tests are governed by fastener connections.
- F₁ loads are based on maximum standoff distances of 1 1/2" or 3" as shown. SCS32-5/97 maximum 1 1/2" standoff.


SCS Hybrid Bypass Framing Connector

SCS Fixed-Clip Allowable Connector Loads (lb.)


Model No.	Framing Members Thickness mil (ga.)	Fasteners to Framing Member		Max. Standoff Distance (in.)	Allowable Loads (lb.)				
		Fastener Pattern	No. of #10 Self-Drilling Screws		In-Plane Load F_1	Tension Load F_2	Comp. Load F_3	Shear Load F_4	
SCS32-5/97	33 (20)	R1	4	1	160	705	705	705	
SCS62-5/68		R1	6	2¼	145	1,060	1,060	550	
SCS62-5/97		R2	8	1	175	1,095	1,095	935	
		R1	6	2¼	145	1,060	1,060	650	
SCS62-5/118	33 (20)	R2	8	1	175	1,415	1,415	995	
		R1	6	2¼	165	1,060	1,060	650	
		R2	8	1	175	1,415	1,415	995	
		R1	8	2¼	165	1,415	1,415	640	
SCS82-5/118	33 (20)	R2	10	1	175	1,765	1,765	975	
		R1	4	1	200	1,050	1,050	1,050	
		SCS32-5/97	R1	6	2¼	190	1,095	1,095	820
		SCS62-5/68	R2	8	1	225	1,095	1,095	1,390
R1	6		2¼	190	1,580	1,580	970		
SCS62-5/97	43 (18)	R2	8	1	225	2,105	2,105	1,480	
		R1	6	2¼	210	1,580	1,580	970	
		SCS62-5/118	R2	8	1	265	2,105	2,105	1,480
			R1	8	2¼	210	2,105	2,105	950
SCS82-5/118	43 (18)	R2	10	1	265	2,630	2,105	1,455	
		R1	4	1	395	2,135	2,135	1,405	
SCS32-5/97	54 (16)	R1	6	2¼	345	1,235	1,235	1,415	
SCS62-5/68		R2	8	1	410	1,235	1,235	1,885	
		R1	6	2¼	345	3,205	2,380	1,970	
SCS62-5/97		R2	8	1	410	4,275	3,275	3,005	
SCS62-5/118	54 (16)	R1	6	2¼	385	3,205	2,550	1,970	
		R2	8	1	480	4,275	3,510	3,005	
		SCS82-5/118	R1	8	2¼	385	4,275	2,550	1,935
			R2	10	1	480	4,540	3,510	2,950
SCS32-5/97	68 (14)	R1	4	1	430	2,160	2,160	1,405	
SCS62-5/68		R1	6	2¼	345	1,235	1,235	1,430	
		R2	8	1	410	1,235	1,235	1,905	
SCS62-5/97		R1	6	2¼	410	3,240	2,380	1,970	
	R2	8	1	435	4,320	3,275	3,005		
SCS62-5/118	68 (14)	R1	6	2¼	535	3,240	2,550	1,970	
		R2	8	1	540	4,320	3,510	3,005	
		SCS82-5/118	R1	8	2¼	535	4,320	3,120	1,935
			R2	10	1	675	4,720	4,290	2,950
SCS32-5/97	97 (12)	R1	4	1	615	2,160	2,160	1,405	
SCS62-5/68		R1	6	2¼	415	1,235	1,235	1,430	
		R2	8	1	415	1,235	1,235	1,905	
SCS62-5/97		R1	6	2¼	770	3,240	2,380	1,970	
	R2	8	1	770	4,320	3,275	3,005		
SCS62-5/118	97 (12)	R1	6	2¼	770	3,240	2,550	1,970	
		R2	8	1	770	4,320	3,510	3,005	
		SCS82-5/118	R1	8	2¼	770	4,320	3,120	1,935
			R2	10	1	770	4,720	4,290	2,950



Typical SCS Fixed-Clip Installation



SCS62-5
2¼" Maximum Standoff
(Pattern R1 — reference p. 37
for all fastener patterns)



SCS62-5
1" Maximum Standoff
(Pattern R2 — reference p. 37
for all fastener patterns)

- For additional important information, see General Information and Notes on p. 28.
- SCS Allowable Connector Loads are also limited by the SCS Anchorage Load tables on pp. 38–39. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- See illustrations on p. 37 for screw fastener placement to stud framing.
- Tabulated F_1 loads are based on assembly tests with the load through the centerline of the stud. Tests are governed by fastener connections.
- F_1 loads are based on maximum standoff distances of 1" or 2¼" as shown. SCS32-5/97 maximum 1" standoff.
- XLGH78B1414 #14 shouldered screw may be used to replace #10 screws in a fixed application.

SCS Hybrid Bypass Framing Connector

Fastener Patterns

Model No.	Slide Conditions		Fixed Conditions	
	Pattern S1	Pattern S2	Pattern R1	Pattern R2
SCS32-5/97				
SCS62-5/68 SCS62-5/97 SCS62-5/118				
SCS82-118				

Deflection Connectors




First of Its Kind — Full-Scale Cyclic Testing for Bypass Clips

The Re-Engineered Bypass Clip

The Innovation team at Simpson Strong-Tie helped to create the SCS hybrid bypass clip, all aspects of the clip were evaluated. One significant modification was the location of our screw holes and slots. Our tests showed that in-plane load is not evenly applied to all screws. In-plane load, or seismic shaking along the plane of the wall, applies predominantly to the first row of screws. Our SCS clip was designed to accommodate two shoulder screws at the first screw line, doubling the number of screws effectively resisting in-plane load.

Testing Results Explained

To determine the in-plane performance of our SCS clips, Simpson Strong-Tie conducted full-scale cyclic testing on our uniaxial shake table at our Tye Gilb Research Laboratory in Stockton, CA. The full-scale test results were used to develop a representative component test to determine various combinations of stud/clip in-plane capacities. This first-of-its-kind testing represents something that was sorely needed because of the lack of industry testing and design standards. Our tests also allowed us to re-engineer the bypass clip to significantly increase the in-plane capacities. Prior to our tested values, various unproven calculation techniques have been used to estimate in-plane loads. Our tested in-plane loads eliminate the guesswork and thus mitigate risk for engineers, contractors and building owners.






Test based on 16 ga. 50 ksi stud and 12 ga. generic clip with (3) #14 screws through slot with flat washer tested in same manner as Simpson Strong-Tie SCS 12 ga. 50 ksi clip in slide-clip application.



Observed screw failure in test

SCS Hybrid Bypass Framing Connector




Deflection Connectors



SCS Allowable Anchorage Loads (lb.)

Anchorage Type	Minimum Base Material	No. of Anchors	SCS62-5/68			SCS32-5/97, SCS62-5/97 SCS62-5/118, SCS82-5/118		
			F ₁	F ₂	F ₄	F ₁	F ₂ and F ₃	F ₄
Attached to Steel⁴								
#12-24 self-drilling screws Strong-Drive [®] X and XL Metal screws	A36 steel 3/16" thickness	3	580	1,890	1,430	730	1,910	1,475
		4	770	2,520	1,905	975	2,545	2,950
Simpson Strong-Tie [®] 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	A36 steel 3/16" thickness	3	—	780	—	—	780	—
		4	—	1,040	730	—	1,040	1,040
Simpson Strong-Tie 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	A572 or A992 steel 3/16" thickness	3	—	915	—	—	1,260	—
		4	—	1,220	1,200	—	1,710	1,710
Weld E70XX electrodes	A36 steel 3/16" thickness	(2) Hard side: 1.5"	1,430	4,635	2,715	2,040	4,720	3,865
		(2) Free side: 1.5"						
Attached to CLT⁴								
0.276" x 4" Strong-Drive [®] SDWH™ TIMBER-HEX HDG Screw (SDWH27400G)	5-ply min. (67/8") SPF CLT into side or end grain	2	560	1,110	1,295	560	1,260	1,295
1/4" x 3 1/2" Strong-Drive SDS Heavy-Duty Connector Screw (SDS25312)	3-ply min. (4 1/8") SPF CLT into side grain	2	595	825	965	595	825	965
	3-ply min. (4 1/8") SPF CLT into end grain	2	400	430	540	400	430	540

- For additional important information, see General Information and Notes on p. 28.
- Allowable anchorage loads are also limited by the SCS Allowable Connector Loads on p. 35 for slide applications and p. 36 for fixed applications. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- Allowable loads for self-drilling screws and PDPAT powder-actuated fasteners are based on installation in minimum 3/16"-thick structural steel with F_y = 36 ksi. PDPAT values are also provided for A572 steel. Values listed above maybe used where other thicknesses of steel are encountered provided that the fastener has equal or better tested values into thicker steel. It is the responsibility of the designer to select the proper length fasteners based on the steel thickness installation.
- F₃ is a compression load and is not a controlling factor for anchor design attached to steel. For attachment to CLT, F₃ (100) is limited to 3,315 lb.
- For screw fastener installation into steel backed by concrete, predrilling of both the steel and the concrete is suggested.
- For predrilling, use a maximum 3/16"-diameter drill bit. SDWH27400G and SDS25312 screw is designed to thread into SCS anchor hole without enlargement of clip hole.
- Loads (160) have been increased for wind or earthquake loading, with no further increase allowed. Reduce where other loads govern.
- F₁, F₂, F₃ and F₄ load directions are the same as SCS Allowable Connector Loads on p. 35 for slide applications and p. 36 for fixed applications.




SCS Hybrid Bypass Framing Connector

SCS Allowable Anchorage Loads to Concrete (lb.)

Anchorage Type	Anchor Bolt Quantity and Diameter	Nominal Embed. Depth, h_{nom} (in.)	Minimum Edge Distance (in.)	Minimum End Distance (in.)	Allowable Load (lb.)					
					$f'_c = 3,000$ psi			$f'_c = 4,000$ psi		
					F ₁	F ₂ and F ₃	F ₄	F ₁	F ₂ and F ₃	F ₄
Uncracked Concrete, Wind and Seismic in SDC A & B^{4,6}										
Titen HD®	(2) ¼"	1½	1½	2½	375	725	565	430	840	655
		2½			410	525	555	475	605	640
Strong-Bolt® 2	(2) ¼"	1¾	4	4	750	1,245	750	750	1,245	750
Titen HD	(1) ½"	3¼	2½	2½	525	1,105	665	605	1,245	770
		3¾			540	1,110	690	625	1,245	795
Strong-Bolt 2	(1) ½"	2¾	4	4	1,035	1,155	1,240	1,195	1,245	1,435
		3⅞			1,120	1,245	1,400	1,295	1,245	1,620
AT-3G™	(1) ½"	7	4	4	1,160	1,245	1,450	1,340	1,245	1,675
SET-3G®					1,160	1,245	1,450	1,340	1,245	1,675
Cracked Concrete, Wind and Seismic in SDC A & B^{4,6}										
Titen HD	(2) ¼"	1½	1½	2½	265	690	405	305	800	465
		2½			295	770	445	340	885	515
Titen HD	(1) ½"	3¼	2½	2½	375	790	475	430	910	550
		3¾			385	790	490	445	910	565
Strong-Bolt 2	(1) ½"	2¾	4	4	740	1,225	925	855	1,245	1,065
		3⅞			800	1,245	1,000	925	1,245	1,155
AT-3G	(1) ½"	7	4	4	830	1,245	1,035	955	1,245	1,195
SET-3G					830	1,245	1,035	955	1,245	1,195
Cracked Concrete, Seismic in SDC C-F^{5,6}										
Titen HD	(2) ¼"	1½	1½	2½	310	605	470	360	700	545
		2½			340	670	520	395	775	600
Titen HD	(1) ½"	3¼	2½	2½	435	690	555	505	800	640
		3¾			450	690	575	520	800	660
Strong-Bolt 2	(1) ½"	2¾	4	4	860	1,070	1,075	995	1,240	1,245
		3⅞			935	1,245	1,170	1,080	1,245	1,350
AT-3G	(1) ½"	7	4	4	965	1,245	1,210	1,115	1,245	1,395
SET-3G					965	1,245	1,210	1,115	1,245	1,395

- Allowable anchor capacities have been determined using ACI 318-19 Chapter 17 calculations with a minimum concrete compressive strength (f'_c) of 3,000 and 4,000 psi in normal-weight concrete. Tabulated values shall be multiplied by a factor (λ_a) of 0.51 for adhesive anchor and 0.68 for mechanical anchor for installation in sand light-weight concrete.
- Load values are for group anchors based on ACI 318, assuming supplementary edge reinforcement not present, load factors from ACI 318-19 Section 5.3, no supplement edge reinforcement, $\Psi_{c,v} = 1.0$ for cracked concrete and periodic special inspection.
- Allowable Stress Design (ASD) values were determined by multiplying calculated LRFD capacities by a conversion factor, Alpha (α), of 0.70 for seismic load and 0.6 for wind loads. ASD values for other combinations may be determined using alternate conversion factors.
- Tabulated allowable ASD loads for Wind and Seismic in SDC A & B are based on using wind conversion factors and may be increased by 1.17 for SDC A & B only.
- Design loads shall include the over-strength factor per ASCE7 Section 12.4.3. See Table 13.5-1 for fasteners in exterior wall connection systems.
- Tabulated allowable loads are based on anchorage only. The capacity of the connection system shall be the minimum of the allowable anchorage load and the SCS allowable connector loads on p. 35 for slide applications and p. 36 for fixed applications.
- Shaded values are limited by connector serviceability and strength in a single-fastener anchorage.
- For anchor subjected to both tension and shear loads, it shall be designed to satisfy the following:
 - For $N_a / N_{all} \leq 0.2$, the full allowable load in shear is permitted.
 - For $V_a / V_{all} \leq 0.2$, the full allowable load in tension is permitted.
 - For all other cases, $N_a / N_{all} + V_a / V_{all} \leq 1.2$, where
 - N_a = Applied ASD tension load.
 - N_{all} = Allowable F₂ or F₃ load column from SCS allowable anchorage loads to concrete table.
 - V_a = Applied ASD shear load.
 - V_{all} = Allowable F₄ or F₁ load column from the SCS allowable anchorage loads to concrete table.



SC Bypass Framing Slide-Clip Connector

Ideal for high-seismic areas, Simpson Strong-Tie® SC connectors are the optimal solution for slide-clip bypass framing. SC clips are often welded to the structure in high-seismic zones, but they also feature anchorage holes so that concrete screws or powder-actuated fasteners can be used to attach the clip to the structure. In addition to anchorage versatility, the SC clips include No-Equal® stamps at the center of the slots to ensure proper shouldered screw placement. SC connectors are manufactured using heavy-duty 10- and 12-gauge steel to provide exceptional resistance to in-plane seismic load.

Features:

- The clips come in lengths of 3½", 6" and 8" for use with 3⅝", 6" and 8" studs, respectively
- The maximum standoff distance is 1" for 3⅝" studs and 1½" for 6" and 8" studs
- Provides a full ¾" of both upward and downward deflection
- Embossments in the bend line provide increased strength and stiffness in the F₁ and F₂ load directions, but are positioned towards the center of the clip so that 1½" long welds can be applied at the top and bottom of the clip
- Prepunched large-diameter anchor holes accommodate ¼"-diameter concrete screws like the Simpson Strong-Tie Titen HD®
- Prepunched small-diameter anchor holes accommodate powder-actuated fasteners like the 0.157"-diameter Simpson Strong-Tie PDPAT or the #12 self-drilling Simpson Strong-Tie Strong-Drive® XL Large-Head Metal screw
- Precision-manufactured shouldered screws, provided with SC connectors, are designed to prevent overdriving and to ensure the clip functions properly

Material: 12 ga. (97 mil) and 10 ga. (118 mil), 50 ksi

Finish: Galvanized (G90)

Installation:





- Use the specified type and number of anchors.
- Use the specified number of XLSH78B1414 #14 shouldered screws (included). Install the screws in the slots adjacent to the No-Equal stamps.
- Use one shouldered screw per slot (maximum).

Codes: See p. 15 for Code Reference Key Chart

Order and Dimension Information:

Model No.	Ordering SKU	Thickness mil (ga.)	L (in.)	A (in.)	B (in.)	Package Quantity	
						Connectors	Shoulder Screws
SC32-5/97	SC32-5/97-KT25	97 (12)	3½	7⁄8	1¼	25	55
SC62-5/97	SC62-5/97-KT25	97 (12)	6	1½	1½	25	83
SC62-5/118	SC62-5/118-KT25	118 (10)	6	1½	1½	25	83
SC82-5/118	SC82-5/118-KT25	118 (10)	8	1½	1½	25	83


Replacement #14 shouldered screws for SC connectors are XLSH78B1414-RP83.




SC Bypass Framing Slide-Clip Connector

SC Allowable Connector Loads (lb.)

Model No.	Stud Thickness mil (ga.)	Fasteners to Stud No. of #14 Shouldered Screws	Allowable Load (lb.)				Code Ref.
			F ₁		F ₂	F ₃	
			1" Standoff	1½" Standoff			
SC32-5/97	33 (20)	2	170	—	585	715	
SC62-5/97		2	100	115	585	715	
SC62-5/118		3	115	130	880	1,070	
		2	100	115	585	710	
SC82-5/118		3	115	130	880	1,070	
		2	115	130	585	710	
SC32-5/97		4	115	130	1,170	1,425	
		2	220	—	765	930	
SC62-5/97	43 (18)	2	135	155	765	930	
		3	150	175	1,145	1,395	
SC62-5/118		2	135	155	765	930	
		3	150	175	1,145	1,395	
SC82-5/118		2	150	175	765	930	
		4	150	175	1,525	2,125	
SC32-5/97		54 (16)	2	300	—	1,145	1,645
SC62-5/97			2	255	295	1,145	1,645
	3		265	305	2,120	2,345	
SC62-5/118	2		255	295	1,405	1,685	
	3		265	305	2,110	2,530	
SC82-5/118	2		260	300	1,405	1,685	
	4		260	300	2,810	3,370	
SC32-5/97	68 (14)		2	375	—	1,695	1,645
SC62-5/97		2	320	370	1,695	1,645	
		3	335	385	2,540	2,345	
SC62-5/118		2	330	380	2,165	2,040	
		3	345	395	3,250	3,060	
SC82-5/118		2	325	375	2,165	2,085	
		4	325	375	4,330	4,165	
SC32-5/97		97 (12)	2	540	—	1,695	1,645
SC62-5/97	2		555	555	1,695	1,645	
	3		555	555	2,540	2,345	
SC62-5/118	2		555	555	2,165	2,040	
	3		635	635	3,250	3,060	
SC82-5/118	2		465	465	2,165	2,085	
	4		465	465	4,330	4,165	



Typical SC Installation

SC62 with Two Screws
(SC82 similar)

- For additional important information, see General Information and Notes on p. 28.
- SC Allowable Connector Loads are also limited by the SC Anchorage Load tables on pp. 42 and 43. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- See illustration for fastener placement when using only two shouldered screws to the stud.
- Tabulated F₁ loads are based on assembly tests with the load through the centerline of stud. Tested failure mode due to screw pullout; therefore compare F₁ against F_p calculated per ASCE 7-16 and ASCE 7-22 Chapter 13 with values for "Fasteners of the connecting system for exterior nonstructural wall elements and connections" as specified in Table 13.5-1.
- F₁ loads are based on maximum standoff distances of 1" or 1½" as shown. Other loads are applicable to a 1" standoff for SC32 and 1" or 1½" standoff for SC62 and SC82.
- At the bend line, the gross allowable plastic moment in the F₁ load direction for 97 mil (12 ga.) and 118 mil (10 ga.) SC connectors are 395 in.-lb. and 675 in.-lb., respectively.
- At a vertical slot, the net allowable plastic moment in the F₁ load direction for 97 mil (12 ga.) and 118 mil (10 ga.) SC connectors are 260 in.-lb. and 440 in.-lb., respectively.



SC Bypass Framing Slide-Clip Connector

Deflection Connectors


SC Allowable Anchorage Loads to Steel (lb.)

Anchorage Type	Minimum Base Material	No. of Anchors	Allowable Load (lb.)	
			F ₁	F ₂
#12–24 self-drilling screws Strong-Drive® X and XL Metal screws	A36 steel 3/16" thick	3	730	1,910
		4	975	2,545
Simpson Strong-Tie® 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	A36 steel 3/16" thick	3	—	780
		4	—	1,040
Simpson Strong-Tie 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	A572 or A992 steel 3/16" thick	3	—	1,260
		4	—	1,710
Weld E70XX electrodes	A36 steel 3/16" thick	(2) Hard side: 1.5"	2,040	4,720
		(2) Free side: 1.5"		

- For additional important information, see General Information and Notes on p. 28.
- Allowable anchorage loads are also limited by the SC Connector Load Table on p. 41. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- F₃ is a compression load and is not a controlling factor for anchor design.
- Allowable loads for #12–24 self-drilling screws and PDPAT powder-actuated fasteners are based on installation in minimum 3/16" thick structural steel with F_y = 36 ksi. PDPAT values are also provided for A572 steel. Values listed above may be used where other thicknesses of steel are encountered or other manufacturers are used, provided that the fastener has equal or better tested values (see p. 28). It is the responsibility of the designer to select the proper length fasteners based on the steel thickness installation.
- For screw fastener installation into steel backed by concrete, predrilling of both the steel and the concrete is suggested. For predrilling, use a maximum 3/16"-diameter drill bit.



3 PAF Anchor Placement
(3 screws similar)



4 PAF Anchor Placement
(4 screws similar)


SC Anchor Layout

SC Bypass Framing Slide-Clip Connector

SC Allowable Anchorage Loads to Concrete with Titen HD® (lb.)

Anchorage Type	Anchor Quantity and Size	Nominal Embedment (in.)	f _c (psi)	Load Direction	Wind and SDC A & B		SDC C-F
					Uncracked Concrete	Cracked Concrete	Cracked Concrete ⁶
Simpson Strong-Tie® Titen HD screw anchor THDB25178H	(2) ¼" x 1 7⁄8"	1 5⁄8"	3,000	F ₁	335	240	280
				F ₂	660	630	550
			4,000	F ₁	390	280	325
				F ₂	760	725	635
Simpson Strong-Tie Titen HD screw anchor THDB25234H	(2) ¼" x 2 3⁄4"	2 1⁄2"	3,000	F ₁	370	265	310
				F ₂	475	695	610
			4,000	F ₁	430	305	360
				F ₂	550	805	705

1. Allowable anchor capacities have been determined using ACI 318-19 Chapter 17 calculations with a minimum concrete compressive strength (f_c) of 3,000 and 4,000 psi in normal-weight concrete. Tabulated values shall be multiplied by a factor (λ_a) of 0.68 for sand light-weight concrete.
2. Edge distance is assumed to be 1 ½", and end distance is 2 5⁄8".
3. Load values are for group anchors based on ACI 318, assuming supplementary edge reinforcement not present, load factors from ACI 318-19 Section 5.3, no supplement edge reinforcement, ψ_{c,v} = 1.0 for cracked concrete and periodic special inspection.
4. Allowable Stress Design (ASD) values were determined by multiplying calculated LRFD capacities by a conversion factor, Alpha (α), of 0.70 for seismic load and 0.6 for wind loads. ASD values for other combinations may be determined using alternate conversion factors.
5. Tabulated allowable ASD loads for Wind and Seismic in SDC A & B are based on using wind conversion factors and may be increased by 1.17 for SDC A & B only.
6. Design loads shall include the over-strength factor per ASCE7 Section 12.4.3. See Table 13.5-1 for fasteners in exterior wall connection systems.
7. Allowable loads for F₁ are based on the governing loading direction which is toward the end of slab.
8. F₃ is a compression load and is not a controlling factor for anchor design.
9. For anchor subjected to both tension and shear loads, it shall be designed to satisfy the following:
 - For N_a / N_{all} ≤ 0.2, the full allowable load in shear is permitted.
 - For V_a / V_{all} ≤ 0.2, the full allowable load in tension is permitted.
 - For all other cases: N_a / N_{all} + V_a / V_{all} ≤ 1.2 where:
 - N_a = Applied ASD tension load
 - N_{all} = Allowable F₂ and F₃ load from the SC Allowable Anchorage Loads into Concrete table
 - V_a = Applied ASD shear load
 - V_{all} = Allowable F₁ load from the SC Allowable Anchorage Loads into Concrete table
10. Tabulated allowable loads are based on anchorage only. The capacity of the connection system shall be the minimum of the allowable anchorage load and the SC Allowable Connector Loads.



SSB Bypass Framing Slide-Clip Strut Connector

The SSB connector is a versatile strut connector that is commonly used at the bottom of a steel beam to accommodate large standoff conditions. It accommodates 1" of upward and 1" of downward movement.

Material: 54 mil (16 ga.)

Finish: Galvanized (G90)

Installation:



- Use the specified type and number of anchors.
- Use the specified number of XLSH34B1414 #14 shouldered screws (included). Install shouldered screws in the slots adjacent to the No-Equal® stamp.
- Use a maximum of one screw per slot.
- If the SSB intrudes on interior space, it can be trimmed. The trimmed part shall allow an edge distance from the center of the nearest anchor to the end of the trimmed part of ½" or greater.
- For installations to wood framing, see Simpson Strong-Tie® engineering letter L-CF-DEFCLIPW at strongtie.com.

Codes: See p. 15 for Code Reference Key Chart

Ordering Information:

Model No.	Ordering SKU	Package Quantity	
		Connectors	Shoulder Screws
SSB3.518	SSB3.518-KT	25	83

Replacement #14 shoulder screws for SSB are XLSH34B1414-RP83.




XLSH34B1414
#14 Shouldered Screw
for Attachment to Stud Framing
(included)


SSB Allowable Connector Loads (lb.)

Model No.	Connector Material Thickness mil (ga.)	No. of #14 Shouldered Screws	Stud Thickness						Code Ref.
			33 mil (20 ga.)		43 mil (18 ga.)		54 mil (16 ga.)		
			F ₂	F ₃	F ₂	F ₃	F ₂	F ₃	
SSB3.518	54 (16)	2 ¹	480	480	640	640	890	890	IBC, FL, LA
		3	755	755	955	1,000	1,235	1,370	

1. When the SSB connector is used with two shouldered screws, the screws may be installed in any two slots.
2. Allowable loads are based on clips installed with (3) #12–24 screws in the anchor leg. For other anchorage installations, the capacity of the connection system will be the minimum of the tabulated value and the allowable load from the SSB Allowable Anchorage Loads table on p. 45.
3. The maximum standoff for SSB with (2) screws and (3) screws is 12¼" and 11", respectively.



SSB Installation with Two Shouldered Screws






SSB Installation with Three Shouldered Screws

SSB Bypass Framing Slide-Clip Strut Connector


SSB Allowable Anchorage Loads (lb.)

Anchorage Type	No. of Anchors	Allowable Load F ₂ and F ₃
#12-24 self-drilling screws	2	1,250
	3	1,875
Simpson Strong-Tie® 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	2	820
	3	1,225
Weld E70XX electrodes	Hard side: 2" Free side: 1"	2,455


- For additional important information, see General Information and Notes on p. 28.
- Allowable loads are for clip anchorage only. The capacity of the connection system will be the minimum of the tabulated value and the allowable load from the SSB Allowable Connector Loads table on p. 44.



SSB Anchor Layout



Typical SSB Installation with Stud Strut



Typical SSB3.518 Installation

HYS Hybrid Strut

Deflection Connectors

The HYS hybrid strut is the only CFS strut on the market designed and tested for use as either a slide or a rigid clip. Commonly used at the bottom of a steel beam to accommodate large standoff conditions, the HYS strut attaches to the structure with screws, powder-actuated fasteners or welds.

For installation as a slide connection, attach the HYS using shouldered screws through the slotted holes. Precision-manufactured shouldered screws provided with the HYS are designed to prevent over-driving and to ensure that the clip functions properly in the slide application. For installation as a rigid connection to support gravity and lateral loading, attach the clip using the small predrilled holes with #10 screws.

The HYS has undergone comprehensive component, assembly and anchor testing. Tabulated loads were developed from these tests and include capacities based on strength and deflection to assist in mitigating design risk. You can count on the HYS dual-application strut for its versatility and test-verified performance.

Features:

- Available in lengths of 12", 15", 24" and 30" (for 18" lengths, use SSB and FSB struts)
- Slots are positioned to minimize eccentric load and maximize capacity
- Slide application allows up to 1" of vertical moment in each direction when shouldered screws are used through the center of the slot
- Simpson Strong-Tie® No-Equal® stamps mark the center of the slots to help ensure correct placement of shouldered screws
- Supports gravity and lateral loads when using #10 screws through small predrilled holes

Material: HYS12/68, HYS15/68, HYS24/68 — 68 mil (14 ga.), 50 ksi
HYS30/97 — 97 mil (12 ga.), 40 ksi


Finish: Galvanized (G90)

Codes: See p. 15 for Code Reference Key Chart


Order and Dimension Information:

Model No.	Ordering SKU	Length, L (in.)	Package Quantity	
			Connectors	Shoulder Screws
HYS12/68	HYS12/68-KT25	12	25	83
HYS15/68	HYS15/68-KT25	15	25	83
HYS24/68	HYS24/68-KT15	24	15	55
HYS30/97	HYS30/97-KT10	30	10	55


1. Replacement #14 shoulder screws for HYS are XLSH78B1414-RP83.
2. 18" lengths (if needed) are provided by the SSB for slide clips and FSB for fixed clips.



XLSH78B1414
#14 Shouldered Screw for Attachment to Stud Framing Slide Application
(included)




HYS12/68
(HYS15/68, HYS24/68 and HYS30/97 similar)




HYS12/68



HYS15/68



HYS24/68




HYS30/97

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.



HYS Hybrid Strut

HYS Slide-Clip Allowable Loads (lb.)

Model No.	Stud Thickness mil (ga.)	No. of #14 Shoulder Screws (Pattern)	Allowable Load (lb.)			Code Ref.	
			In-Plane Load F_1	Tension Load F_2	Comp. Load F_3		
HYS12/68	33 (20)	2 (S1)	95	480	480		
		3 (S2)	95	755	755		
HYS15/68		2 (S1)	95	480	480		
		3 (S2)	95	755	755		
HYS24/68		2 (S1)	95	480	420		
		3 (S2)	95	755	635		
HYS30/97	43 (18)	2 (S1)	105	480	490		
		3 (S2)	105	755	735		
HYS12/68		2 (S1)	150	755	575		
		3 (S2)	155	1,135	1,160		
HYS15/68		2 (S1)	150	755	575		
		3 (S2)	155	1,135	1,160		
HYS24/68	54 (16)	2 (S1)	150	755	870		
		3 (S2)	155	1,135	1,310		
HYS30/97		2 (S1)	150	755	870		
		3 (S2)	155	1,135	1,310		
HYS12/68		68 (14)	2 (S1)	240	960	915	
			3 (S2)	265	1,460	1,420	
HYS15/68	2 (S1)		240	960	915		
	3 (S2)		265	1,460	1,430		
HYS24/68	2 (S1)		240	960	1,075		
	3 (S2)		265	1,460	1,615		
HYS30/97	84 (12)	2 (S1)	240	960	1,250		
		3 (S2)	265	1,460	1,860		
HYS12/68		98 (10)	2 (S1)	385	1,330	915	
			3 (S2)	385	1,995	1,420	
HYS15/68			2 (S1)	385	1,330	915	
			3 (S2)	385	1,995	1,430	
HYS24/68	2 (S1)		385	1,330	1,075		
	3 (S2)		385	1,995	1,615		
HYS30/97	112 (8)	2 (S1)	240	1,410	1,410		
		3 (S2)	265	2,100	2,100		



Typical HYS Slide-Clip Application

Slide Screw Pattern S1
(no screws required in small round holes in slide application)Slide Screw Pattern S2
(no screws required in small round holes in slide application)


- For additional important information, see General Information and Notes on p. 28.
- HYS Allowable Connector Loads are also limited by the HYS Anchorage Load table on p. 49. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- See illustrations on the side for fastener placement to stud framing.
- Tabulated F_1 loads are based on assembly tests with the load through the centerline of the stud. Tests are governed by fastener connections.

HYS Hybrid Strut


Deflection Connectors

HYS Fixed-Clip Allowable Loads (lb.)


Model No.	Stud Thickness mil (ga.)	No. of #10 Screws (Pattern)	Allowable Load (lb.)				Code Ref.		
			In-Plane Load F ₁	Tension Load F ₂	Comp. Load F ₃	Shear Load F ₄			
HYS12/68	33 (20)	4 (R1)	100	705	705	335			
		6 (R2)	110	1,060	1,060	335			
HYS15/68		4 (R1)	100	705	705	305			
		6 (R2)	110	1,060	1,060	305			
HYS24/68		4 (R1)	75	705	705	150			
		6 (R2)	75	1,060	1,060	150			
HYS30/97		4 (R1)	75	705	705	125			
		6 (R2)	75	1,060	1,060	125			
HYS12/68		43 (18)	4 (R1)	155	1,050	1,050		510	
			6 (R2)	180	1,580	1,580		510	
HYS15/68			4 (R1)	100	1,050	1,050		400	
			6 (R2)	100	1,580	1,580		400	
HYS24/68	4 (R1)		100	1,050	1,050	205			
	6 (R2)		100	1,580	1,580	290			
HYS30/97	4 (R1)		100	1,050	1,050	185			
	6 (R2)		100	1,580	1,580	185			
HYS12/68	54 (16)		4 (R1)	260	1,940	1,885	560		
			6 (R2)	330	2,835	1,885	710		
HYS15/68			4 (R1)	150	1,940	2,135	560		
			6 (R2)	280	2,835	2,735	560		
HYS24/68		4 (R1)	150	1,940	2,135	225			
		6 (R2)	280	2,835	2,400	290			
HYS30/97		4 (R1)	115	1,975	2,135	220			
		6 (R2)	115	2,960	3,205	220			
HYS12/68		68 (14)	4 (R1)	330	1,940	1,885	560		
			6 (R2)	415	2,835	1,885	710		
HYS15/68			4 (R1)	250	1,940	2,215	560		
			6 (R2)	415	2,835	2,735	560		
HYS24/68	4 (R1)		250	1,940	2,215	225			
	6 (R2)		425	2,835	2,400	290			
HYS30/97	4 (R1)		145	1,975	2,215	220			
	6 (R2)		145	2,960	3,325	220			



Typical HYS Fixed-Clip Application



Fixed Screw Pattern R1
(no screws required in slot in fixed application)



Fixed Screw Pattern R2
(no screws required in slot in fixed application)

1. For additional important information, see General Information and Notes on p. 28.
2. HYS Allowable Connector Loads are also limited by the HYS Anchorage Load table on p. 49. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
3. See illustrations on the side for screw fastener placement to stud framing.
4. Tabulated F₁ loads are based on assembly tests with the load through the centerline of the stud. Tests are governed by fastener connections.
5. XLSH78B1414 #14 shouldered screw may be used to replace #10 screws in a fixed application.
6. Minimum stud width for fixed application is 6".

HYS Hybrid Strut

HYS Allowable Anchorage Loads (lb.)





Anchorage Type	No. of Anchors	Allowable Load (lb.)	
		F ₂ and F ₃	F ₄
#12-24 self-drilling screws	2	1,595	565
	3	2,395	845
	4	3,190	1,125
Simpson Strong-Tie® 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	2	820	—
	3	1,230	520
	4	1,640	780
Weld E70XX electrodes	Hard side: 2" Free side: 1"	2,455	1,125
	Hard side: 4" Free side: 1"	3,190	1,125

- For additional important information, see General Information and Notes on p. 28.
- Allowable loads are for the clip anchorage only. The capacity of the connection system will be the minimum of the tabulated value and the allowable load from the HYS Allowable Connector Loads on p. 47 for slide applications and p. 48 for fixed applications.

HYS Maximum Standoff Distances (in.)

Model No.	Pattern	No. of Anchors	
		2 or 3	4
HYS12/68	S1	7	6¼
	S2	5¾	5
	R1 or R2	5½	4¾
HYS15/68	S1	10	9¼
	S2	8¾	8
	R1 or R2	8½	7¾
HYS24/68	S1	19	18¼
	S2	17¾	17
	R1 or R2	17½	16¾
HYS30/97	S1	25	24¼
	S2	23¾	23
	R1 or R2	23½	22¾

For drawing showing standoff, see p. 47 for slide applications (S1,S2) and p. 48 for fixed applications (R1 or R2).



SCW Head-of-Wall Slide-Clip Connector

The SCW connectors offer 1" of upward and 1" of downward movement. They are primarily used in head-of-wall applications that require vertical movement relative to the structure. SCW connectors are often used to strengthen window and door jambs for projects that utilize slip or slotted track.

Material: 54 mil (16 ga.)

Finish: Galvanized (G90)

Installation:



- Use the specified type and number of anchors.
- Use the specified number of #14 shouldered screws (included). Install shouldered screws in the slots adjacent to the No-Equal® stamp.
- Use a maximum of one screw per slot.
- For installations to wood framing, see Simpson Strong-Tie® engineering letter L-CF-DEFCLIPW at strongtie.com.

Codes: See p. 15 for Code Reference Key Chart

Ordering Information:

Model No.	Ordering SKU	Package Quantity	
		Connectors	Shoulder Screws
SCW3.25	SCW3.25-KT	25	55
SCW5.5	SCW5.5-KT	25	83

Replacement #14 shoulder screws for SCW are XLSH34B1414-RP83.




XLSH34B1414
#14 Shouldered Screw for Attachment to Stud Framing
(included)


SCW Allowable Connector Loads (lb.)

Model No.	W (in.)	No. of #14 Shouldered Screws	Stud Thickness			Code Ref.
			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	
			F ₄	F ₄	F ₄	
SCW3.25	3 1/4	2	425	590	695	IBC, FL, LA
SCW5.5	5 1/2	2 ¹	425	590	920	
		3	425	590	1,130 ³	


1. When the SCW5.5 connector is used with two shouldered screws, install screws in the outermost slots.
2. Allowable loads are based on clips installed with all holes in the anchor leg filled with #12–14 screws. For other anchorage installations, the capacity of the connection system will be the minimum of the tabulated value and the allowable load from the SCW Allowable Anchorage Loads table on p. 51.
3. Tabulated loads are applicable for the following framing widths:
 SCW3.25 — 3 1/2", 3 3/8", 4" and 5 1/2"
 SCW5.5 — 6", 8" (18 ga. min.), 10" and 12" (16 ga. min.)



Typical SCW Installation with Stud Strut



SCW5.5 Installation with Two Shouldered Screws
(three shouldered screws and SCW3.25 similar)





Typical SCW Installation at Stud

SCW Head-of-Wall Slide-Clip Connector

SCW Allowable Anchorage Loads (lb.)

Anchorage Type	Minimum Base Material	Allowable Loads (lb.)			
		SCW3.25		SCW5.5	
		No. of Anchors	F ₄	No. of Anchors	F ₄
#12–24 self-drilling screws	A36 steel 3/16" thick	2	715	2	775
		3	1,075	4	1,550
Simpson Strong-Tie® 0.157" x 5/16" powder-actuated fasteners PDPAT-62KP	A36 steel 3/16" thick	2	715	2	745
		3	1,075	4	1,490
Simpson Strong-Tie 1/4" x 1 3/4" Titen Turbo™ ³	Concrete f _c = 2,500 psi	2	285	2	285
		3	350	4	775

1. For additional important information, see General Information and Notes on p. 28.
2. Allowable loads are for clip anchorage only. The capacity of the connection system will be the minimum of the tabulated value and the allowable load from the SCW Allowable Connector Loads table on p. 50.
3. Tabulated values require a minimum 1 1/2" edge distance for Titen Turbo (TNT) masonry screws in concrete.
4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



HWSC® Head-of-Wall Slide-Clip Connector



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The HWSC head-of-wall slide-clip connector is specifically designed for simplifying the panelization of 3½" and 6" framing formed on automated cold-formed steel (CFS) stud fabrication machines (e.g., FrameCAD, Arkitech, Howick, Pinnacle and Scottsdale). The HWSC is designed to replace slotted track with a typical printed track at head-of-wall conditions. To facilitate installation, a cone-shaped funnel in the clip helps the dimple in the track align properly with the clip's corresponding dimple to hold it in place while a screw is placed in each flange from the track to the clip. The stud is then slid into position, and the clip is attached to the stud with shoulder screws driven through the center of the fastener slots. As an option, fasten the clip through the diamond-shaped hole to stud using a single screw to lock the deflection gap in place temporarily during transport and installation. The optional screw is then removed after installation is complete. The HWSC has been assembly tested to provide optimal strength and performance.

Features:

- An edge stiffener has been rolled into the web and flange of the clip for added strength and for ease of fastening of the screws into the clip flange during installation
- The clip has a unique cone-shaped dimple that guides the track dimple into alignment with the clip, locking the connection in-place while a screw is installed into each flange
- Replaces slotted track that is difficult to panelize with typical printed track
- Provides a full 1" of both upward and downward deflection

Caution:

- The HWSC connector is specifically designed for use with printed studs and tracks such as FrameCAD, Arkitech, Howick, Pinnacle and Scottsdale
- Not intended for use with typical manufactured studs and tracks

Material: 54 mil (16 ga.), 50 ksi

Finish: Galvanized (G90)

Installation:


- Use (2) XLSH78B1414 #14 shoulder screws (included). Install screws into the center of the slot at No-Equal® logo.
- Use an optional #10 screw to lock deflection gap during panel construction. Remove after installation is complete.

Codes: Testing performed in accordance with ICC-ES AC261. Visit strongtie.com for the latest load values and testing information.

Ordering Information:


Model No.	Ordering SKU	Package Quantity	
		Connectors	Shoulder Screws
HWSC362	HWSC362-KT	50	110
HWSC6	HWSC6-KT	50	110

Replacement #14 shoulder screws for HWSC are XLSH78B1414-RP83.




XLSH78B1414

#14 Shouldered Screw for Attachment to Stud Framing Slide Application
(included)



HWSC6




HWSC362

HWSC® Head-of-Wall Slide-Clip Connector


HWSC Allowable Connector Loads, F_4 (lb.)

Model No.	Track		Stud Thickness mil (ga.), F_y					
	Thickness Mil (ga.)	F_y (ksi)	27 (22)	30 (20-D)	33 (20)	43 (18)	54 (16)	
			33 ksi	33 ksi	33 ksi	33 ksi	33 ksi	50 ksi
HWSC362	27 (22)	33 ksi	145	145	160	160	160	160
	30 (20-D)	33 ksi	145	145	160	160	160	160
	33 (20)	33 ksi	180	180	295	295	295	295
	43 (18)	33 ksi	275	275	320	320	320	320
HWSC6	33 (20)	33 ksi	—	—	170	195	195	210
	43 (18)	33 ksi	—	—	325	345	345	345
	54 (16)	33 ksi	—	—	325	345	345	345
		50 ksi	—	—	325	480	480	495
	68 (14)	33 ksi	—	—	325	345	345	345
		50 ksi	—	—	325	480	480	655

1. The HWSC362 and HWSC6 have an out-to-out dimension of 3½" and 5¾", respectively. They are designed to fit inside a printed track and attached to the swaged end of the printed stud. Listed capacities are based on tracks with ½" lips and a maximum lip cutout of 2⅞" at stud location.
2. Allowable loads are based on the clip installed with (1) #10-16 screw into each track flange and (2) shoulder screws into the stud. Shoulder screws are included with the clip.
3. Tabulated capacities are based on a 1" deflection gap. End of stud to top of track to provide gap equal to the deflection gap required (up to 1" deflection). Top track leg length to be a minimum of two times the deflection gap plus a ¼".
4. Thickness 30 (20-D) refers to 30 mil (20 ga. drywall). 33 (20) refers to 33 mil (20 ga. structural).
5. Anchorage to structure designed by others.



Typical HWSC Installation to Steel



Typical HWSC Installation to Concrete

DTC Head-of-Wall Slide-Clip

DTC clips are a cost-effective solution for light-duty, head-of-wall slide clip applications. The 1 5/8" slot will allow 3/4" movement in each direction.

Material: 43 mil (18 ga.)


Finish: Galvanized (G90)

Installation:

- Use specified type and number of anchors per the installation drawing below
- Install (2) #8 screws centered in the vertical slots
- Once tightened, back-out screws 1/2 turn to ensure slip

Codes: See p. 15 for Code Reference Key Chart


Ordering Information: DTC available in single pieces or box of 100.



DTC


DTC Allowable Loads (lb.)

Model No.	Fasteners	Anchorage	Stud Thickness mil (ga.)	Stud Steel Strength F _y (ksi)	Allowable Load F ₄	Code Ref.
DTC	(2) #8 self-drilling screws ⁴	(2) 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP or (2) #12 self-drilling screws ⁴	15 (25 EQ)	50	60	IBC, FL, LA
			18 (25)	33	70	
			19 (20 EQ)	65	80	
			20 (20 EQ)	57	80	
			30 (20 DW)	33	165	
			33 (20 STR)	33	170	
			43 (18)	33	215	




Typical DTC Screw Installation

1. Allowable loads may not be increased for wind or seismic load.
2. Clips do not replace stud lateral or stability bracing. Design of bracing is the responsibility of the designer.
3. It is the responsibility of the designer to verify the adequacy of the stud. Allowable loads are based on clips installed an adequate distance away from penetrations, notches, ends of studs and other conditions that may affect the clip performance.
4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.
5. EQ = Equivalent, DW = Drywall, STR = Structural.



Typical DTC Installation at Stud



DTC Anchor Layout

SCHA Slide-Clip Connectors for Horizontal Anchorage

SCHA Allowable Loads (lb.)

Primary Structure Base Material	Anchorage		Fasteners to Stud Self-Drilling Screws		Stud Thickness mil (ga.)	Maximum Standoff Distance (in.)	Allowable Load (lb.)			Code Ref.
	Qty./Type/Size	Condition	Min./Max.	No. #12-14			F ₁ ⁷	F ₂	F ₃	
Structural steel A36 3/16" thick minimum	(4) 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP or (2) welds – 2" length	Front condition	Min.	4	33 (20)	2	150	645	490	—
					43 (18)		195	860	610	
			54 (16)	235	990		880			
			68 (14)	235	990		880			
		Max.	6	54 (16)	350	1,300	1,045			
				68 (14)	350	1,495	1,045			
	End condition	Min.	4	4	33 (20)	4 3/4	105	625	470	
					43 (18)		110	830	570	
					54 (16)		165	830	720	
					68 (14)		165	830	720	
		Max.	6	4	54 (16)	350	1,060	775		
					68 (14)	350	1,060	775		
Concrete	(4) 1/4"-diameter concrete screw anchors ³	4 anchors	Min.	4	33 (20)	2	105	625	470	
					43 (18)		110	830	570	
					54 (16)		165	830	720	
					68 (14)		165	830	720	
		Max.	6	54 (16)	350	1,060	775			
				68 (14)	350	1,060	775			
	(2) 1/4"-diameter concrete screw anchors ³	2 anchors	Min.	4	4	4 3/4	105	625	470	
							43 (18)	105	830	570
							54 (16)	165	830	720
							68 (14)	165	830	720
		Max.	6	4	54 (16)	350	860	745		
					68 (14)	350	860	745		

1. For additional important information, see General Information and Notes on p. 28.

2. Allowable loads are based on connectors installed with tabulated anchorage type, quantity and size into structural steel. For anchorage installations into concrete, the capacity of the connection system will be the minimum of the tabulated value and the allowable load using concrete screws indicated on the table on p. 57. Note that if the designer chooses to calculate concrete anchorage with alternate 1/4"-diameter anchors, then the maximum load shall not exceed the tabulated values in this table. Refer to the figures on p. 55 for anchorage conditions.

3. Please refer to the table on p. 57 for Simpson Strong-Tie® Titen HD® anchorage loads.





4. Min. fasteners quantity and tabulated values — fill round holes; max. fasteners quantity and tabulated values — fill round and triangular holes.

5. The standoff is the distance from the interior flange of the stud to the face of the supporting structure. Note that the interior flange of the stud is assumed to align with the inside vertical edge of the connector as indicated in the illustrations on p. 57.

6. Tabulated values are based on 3/16" studs. Web crippling checks for deeper members are the responsibility of the designer.

7. Tabulated F₁ loads are based on assembly tests with the load through the centerline of stud. Tested failure mode due to screw pullout; therefore compare F₁ against F_P calculated per ASCE 7-16 and ASCE 7-22 Chapter 13 with values for "Fasteners of the connecting system for exterior nonstructural wall elements and connections" as specified in Table 13.5-1.

SCHA Slide-Clip Connectors for Horizontal Anchorage

Typical SCHA Installation
at Floor SlabTypical SCHA Installation
at Floor Slab
(inverted)Typical SCHA Installation at
Beam FlangeTypical SCHA Installation
for Built-Up Studs at Floor Slab
(SCHA10.75L near side and
SCHA10.75 far side)

SCHA Allowable Anchorage Loads to Concrete for Titen HD® (lb.)

Anchorage Type	Nominal Embedment (in.)	Anchors Quantity and Size	f'_c (psi)	Allowable Anchor Load (lb.) F_2 and F_3			
				Wind and Seismic in SDC A & B		Seismic in SDC C-F	
				Uncracked Concrete	Cracked Concrete	Cracked Concrete ($\Omega = 1.0$)	Cracked Concrete ⁷ ($\Omega = 2.5$)
Simpson Strong-Tie® Titen HD screw anchor THDB25178H	1½"	(4) ¼" x 1 7/8"	2,500	1,025	730	855	350
	1"	(2) ¼" x 1 7/8"	2,500	510	365	425	175

1. Allowable anchor capacities have been determined using ACI 318-19 Chapter 17 calculations with a minimum concrete compressive strength (f'_c) of 2,500 psi and 5" slab thickness in normal-weight concrete. Tabulated values can be multiplied by a factor (λ_a) of 0.68 for sand-lightweight concrete.
2. Nominal Embedment Depth/Effective Embedment Depth relationship is $1.75" (h_{nom}) / 1.30" (h_{ef})$.
3. Edge distance is assumed to be 2", and end distance is 7 1/8".
4. Load values are for group anchors based on ACI 318-19, assuming supplementary reinforcement not present, load factors from ACI 318-19 Section 5.3, no supplemental edge reinforcement, $\Psi_{c,v} = 1.0$ for cracked concrete and periodic special inspection.
5. Allowable Stress Design (ASD) values were determined by multiplying calculated LRFD capacities by a conversion factor, Alpha (α), of 0.70 for seismic load and 0.6 for wind loads. ASD values for other combinations may be determined using alternate conversion factors.
6. Tabulated allowable ASD loads for Wind and Seismic in SDC A & B are based on using wind conversion factors and may be increased by 1.17 for SDC A & B only.
7. Allowable loads have been divided by an Omega (Ω) seismic factor of 2.5 for brittle failure as required by ACI 318-19 Chapter 17.
8. Allowable F_2 and F_3 loads are based on the governing loading direction, which is toward the edge of slab.
9. Tabulated capacities are based on maximum allowable anchorage loads only. The capacity of the connection system shall be the minimum of the tabulated value and the SCHA allowable loads for concrete shown on previous page, in the "Primary Structure Base Material" column.

IDCB Drift-Clip Bypass Framing Connector

The IDCB drift-clip connector is used to secure bypass stud framing to the edge of a slab. The connector will accommodate 1" of lateral drift in each direction and 1" of upward and downward vertical deflection. Tested load values are provided for anchorage to a steel-edge angle using #12 x 1 1/4" Strong-Drive® XL Large-Head Metal screws.

Features:

- Horizontal embossments and corner gussets optimize performance in the F_2 load direction
- Precision-manufactured shouldered screws provided with the IDCB connector are designed to prevent overdriving and to ensure that the clip functions properly
- Simpson Strong-Tie® No-Equal® stamps mark the center of the slots to help ensure correct shouldered screw and anchor placement

Material: 97 mil (12 ga.), 50 ksi

Coating: Galvanized (G90)






Installation:

- Use the specified type and number of fasteners and anchors.
- In the vertical slots, use the specified number of #14 shouldered screws (included) for attachment to the stud. Install screws to align with the No-Equal stamp.
- For attachment to a minimum 3/16"- and maximum 1/2"-thick steel edge angle, use Simpson Strong-Tie Strong-Drive XL Large-Head Metal screws (XLQ114B1224). Use one screw centered in each horizontal slot. Install screws to align with the No-Equal stamp and back out 1/2 turn.
- For fastener installation into steel backed by concrete, predrilling of both the steel and the concrete may be required. For predrilling, use a maximum 3/16"-diameter drill bit.

Codes: See p. 15 for Code Reference Key Chart

Ordering Information:

Model No.	Ordering SKU	Package Quantity	
		Connectors	Shoulder Screws
IDCB45.5	IDCB45.5-KT25	25	83



Standoff Distance

IDCB45.5 Connector Loads (lb.)

Model No.	No. of #14 Shouldered Screws ¹	No. of #12 XLQ Screw Anchors ²	Load Direction	Stud Thickness mil (ga.)	Strength ³ (lb.)		Service Limit ³ (lb.)		Code Ref.
					ASD	LRFD	1/8" Deformation	3/16" Deformation	
IDCB45.5	3	2	F_2 and F_3	33 mil (20 ga.)	600	900	410	650	—
				43 mil (18 ga.)	680	1,060	455	695	
				54 mil (16 ga.)	760	1,220	500	745	

1. #14 x 7/8" shouldered screw (model no. "XLSH78B1414") provided with the clips are ASTM C1513 compliant.

2. For additional information on the #12 XL screw (model no. "XLQ114B1224") refer to strongtie.com.

3. The capacity of the connection will be the minimum of Strength Load and applicable Service Limit Load as determined by the designer.

4. For additional important information, see General Information and Notes on p. 26.

DSSCB Bypass Framing Drift Strut Connector



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The solution to accommodate building drift, the DSSCB, is used to support cold-formed steel bypass framing to the edge of a floor slab. The DSSCB also simplifies installation by allowing installers for panelized construction to install finished panels while working off the top of the slab without the need to predrill or preinstall anchors for each clip. It also eliminates the coordination difficulties associated with preanchorage of standard bypass clips. With prepunched slots and round holes, the DSSCB is a dual-function connector that can be used for slide-clip and fixed-clip applications.

Features:

- The clips come in lengths of 3½", 6" and 8".
- Prepunched slots provide a full 1" of both upward and downward deflection.
- Precision-manufactured shouldered screws, provided with DSSCB connectors, are designed to prevent overdriving and to ensure the clip functions properly.
- Works with 7⁄8" and 1½" strut channels as given in the accompanying figures. Common manufactured brands are Unistrut, PHD and B-Line, among others. Struts manufactured that meet the strut requirements shown on p. 69 for attachment to steel or CLT, or on p. 67 for concrete embedment are acceptable.
- The maximum slide-clip standoff distance is 3½" for 7⁄8" struts, 3¾" for 1½" struts and 2¼" for concrete inserts.
- Depending on the application and the designer's specifications, struts can be either mechanically anchored, welded or cast in place.
- Pre-engineered design solutions are provided for channel strut anchorage.
- Tabulated design values are based on assembly testing to mitigate risk for designers, engineers and architects.
- Optional precast concrete inserts for flush mounting.
- Optional drift stopper, DSHS, for clip alignment flexibility (where drift not required).

Material: DSSCB — 97 mil (12 ga.), 50 ksi;

DSHS — 97 mil (12 ga.), 33 ksi


Finish: Galvanized (G90)

Codes: See p. 15 for Code Reference Key Chart.

Ordering Information:

Model No.	Ordering SKU	Package Quantity	
		Connectors	Shoulder Screws
DSSCB43.5	DSSCB43.5-KT25	25	55
DSSCB46	DSSCB46-KT25	25	83
DSSCB48	DSSCB48-KT25	25	110
DSHS	DSHS-R100	100	—


Replacement #14 shoulder screws for DSSCB are XLSH78B1414-RP83.




✓ DSSCB43.5

✓ DSSCB46

US Patent. See strongtie.com/patent.



✓ DSSCB48



XLSH78B1414
#14 Shouldered Screw for
Attachment to Stud Framing
(included)

DSSCB Bypass Framing Drift Strut Connector



Squaring flange
helps the clip stay square with the strut

Unique formed insert
works with standard $\frac{7}{8}$ " and $1\frac{1}{8}$ "-deep, 12-gauge strut, minimizes friction, and allows an easy twist-in installation


Stiffened edges and heavy 12-gauge construction
provide jobsite durability and superior tabulated loads

Dual-function clips
can be used for either deflection or fixed conditions


No-Equal® stamp
marks the center of the slots to help ensure correct shouldered-screw placement



The Simpson Strong-Tie® DSSCB works with 12-gauge standard strut channels (not sold by Simpson Strong-Tie). See p. 69 for strut requirements and p. 67 for concrete insert requirements. See p. 65 for model numbers and capacities.




DSSCB Dimensions



DSHS used to prevent horizontal sliding when needed (sold separately)

DSSCB Bypass Framing Drift Strut Connector



Typical DSSCB Installation
Slide-Clip Application

DSSCB Screw Patterns (Slide-Clip Applications)

Model	Pattern A		
DSSCB43.5			
Model	Pattern B	Pattern C	Pattern D
DSSCB46			
Model	Pattern E	Pattern F	Pattern G
DSSCB48			

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.


DSSCB Bypass Framing Drift Strut Connector

DSSCB Allowable Slide-Clip Connector Loads (lb.)

Model No.	Stud Thickness mil (ga.)	Fasteners to Stud		Allowable Load (lb.)			Code Ref.
		Screw Pattern	No. of #14 Shouldered Screws	F ₁	F ₂	F ₃	
DSSCB43.5	33 (20)	A	2	115	515	570	IBC, FL, LA
DSSCB46		B	3	115	765	850	
		C, D	2	105	515	570	
DSSCB48		E	4	115	765	1,135	
	F, G	3	105	765	850		
DSSCB43.5	43 (18)	A	2	170	785	875	
DSSCB46		B	3	170	1,175	1,310	
		C, D	2	155	785	875	
DSSCB48		E	4	170	1,175	1,745	
	F, G	3	155	1,175	1,310		
DSSCB43.5	54 (16)	A	2	245	1,075	1,250	
DSSCB46		B	3	245	1,475	1,875	
		C, D	2	225	1,075	1,190	
DSSCB48		E	4	245	1,475	2,385	
	F, G	3	225	1,475	1,820		
DSSCB43.5	68 (14) and 97 (12)	A	2	300	1,075	1,640	
DSSCB46		B	3	300	1,475	2,675	
		C, D	2	300	1,075	1,560	
DSSCB48		E	4	300	1,475	2,675	
	F, G	3	300	1,475	2,600		

1. For additional important information, see General Information and Notes on p. 28.
2. DSSCB Allowable Slide-Clip Connector Loads are also limited by the Strut Channel Allowable Anchorage Loads to Steel table on p. 65, or Concrete Insert Allowable Anchorage Loads table on p. 66 or Strut Channel Allowable Anchorage Loads to CLT table on p. 70. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
3. See illustrations on p. 61 for shouldered screw fastener pattern placement to stud framing.
4. Tabulated F₁ loads are based on assembly tests with the load through the centerline of the stud. F₁ loads require DSHS connector with (1) #10 screw to strut.
5. For attachment with clip on each side of stud, the allowable loads (F₂,F₃) can be multiplied by a factor of two. The allowable load (F₁) is limited to a maximum of two times capacity or 455 lb. whichever is less.

DSSCB Bypass Framing Drift Strut Connector



Typical DSSCB Installation
Fixed-Clip Application

DSSCB Screw Patterns (Fixed-Clip Applications)

Model	Pattern H	Pattern I	Pattern J
DSSCB43.5			
Model	Pattern K	Pattern L	Pattern M
DSSCB46			
Model	Pattern N	Pattern O	Pattern P
DSSCB48			

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.


DSSCB Bypass Framing Drift Strut Connector

Drift Connectors


DSSCB Allowable Fixed-Clip Connector Loads (lb.)

Model No.	Stud Thickness mil (ga.)	Screw Pattern	No. of #10 Screws	Allowable Load (lb.)				Code Ref.		
				F ₁	F ₂	F ₃	F ₄			
DSSCB43.5	33 (20)	H	4	220	705	705	345	IBC, FL, LA		
		I, J	2	185	355	355	175			
DSSCB46		K	6	220	1,060	1,060	355			
		L, M	4	185	705	705	350			
DSSCB48		N	8	220	1,060	1,060	545			
		O, P	4	185	705	705	505			
DSSCB43.5		43 (18)	H	4	265	1,050	1,050		450	IBC, FL, LA
			I, J	2	240	525	525		230	
DSSCB46			K	6	285	1,125	1,580		460	
			L, M	4	240	1,050	1,050		455	
DSSCB48	N		8	285	1,145	1,580	710			
	O, P		4	240	1,050	1,050	660			
DSSCB43.5	54 (16)		H	4	330	1,410	2,070	1,025	IBC, FL, LA	
			I, J	2	300	1,070	1,035	515		
DSSCB46			K	6	360	1,410	3,105	1,050		
			L, M	4	300	1,410	2,135	1,040		
DSSCB48		N	8	360	1,440	3,105	1,145			
		O, P	4	300	1,420	2,135	1,070			
DSSCB43.5		68 (14) and 97 (12)	H	4	395	1,410	2,160	1,025		IBC, FL, LA
			I, J	2	300	1,080	1,080	515		
DSSCB46			K	6	395	1,410	3,105	1,050		
			L, M	4	300	1,410	2,160	1,040		
DSSCB48	N		8	395	1,440	3,240	1,145			
	O, P		4	300	1,420	2,160	1,070			


- For additional important information, see General Information and Notes on p. 28.
- DSSCB Allowable Fixed-Clip Connector Loads are also limited by the Strut Channel Allowable Anchorage Loads to Steel table on p. 65, or Concrete Insert Allowable Anchorage Loads table on p. 66, or Strut Channel Allowable Anchorage Loads to CLT table on p. 70. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- See illustrations on p. 63 for screw fastener pattern placement to stud framing.
- Tabulated F₁ loads are based on assembly tests with the load through the centerline of the stud. F₁ loads require DSHS connector with (1) #10 screw to strut.
- For attachment with clip on each side of stud, the allowable loads (F₂, F₃, F₄) can be multiplied by a factor of two. The allowable load (F₁) is limited to a maximum of two times capacity or 455 lb., whichever is less.
- In-plane capacities (F₁) for DSSCB attached to 54 mil (16 ga.) stud can be increased to 455 lb. with the addition of a shoulder screw at first slot from bend line for screw pattern K and L and at middle slot for pattern M (reference patterns shown to the right). Failure mode for this condition is member, not fastener.



Screw Pattern K
With Added Shoulder
Screw per Note 6



Screw Pattern L
With Added Shoulder
Screw per Note 6



Screw Pattern M
With Added Shoulder
Screw per Note 6

DSSCB Bypass Framing Drift Strut Connector

Drift Connectors


Strut Channel Allowable Anchorage Loads to Steel (lb.)

Strut Size (in.)	Models	Anchorage Spacing (in.)	Welded Anchorage Each Flange				#12-24 Screw Anchorage				PDPAT-62KP Pin Anchorage				Code Ref.
			F ₁ (lb.)	F ₂ (lb.)	F ₃ (lb.)	F ₄ (lb.)	F ₁ (lb.)	F ₂ (lb.)	F ₃ (lb.)	F ₄ (lb.)	F ₁ (lb.)	F ₂ (lb.)	F ₃ (lb.)	F ₄ (lb.)	
7/8"	Unistrut P3300; P3300HS; P3300T; P3300K0	4	775	1,800	2,710	3,200	755	1,530	2,710	1,650	755	1,040	2,710	1,640	Weld and Screw Anchor IBC, FL, LA
		6	775	1,200	2,710	2,135	755	1,040	2,710	1,155	755	695	2,710	1,095	
	PHD 1201; 1202; 1211; 1212; 1221; 1222; 1241; 1242	8	775	900	2,710	1,600	755	800	2,710	865	755	520	2,710	820	
		10	775	720	2,710	1,280	—	—	—	—	—	—	—	—	
	B-Line B52; B52H1 7/8; B52SH; B52K06	12	775	600	2,710	1,065	—	—	—	—	—	—	—	—	
		16	775	450	2,710	800	—	—	—	—	—	—	—	—	
1 1/8"	Unistrut P1000; P1000HS; P1000T; P1000K0.	4	775	4,310	3,925	1,745	755	1,530	3,925	1,315	755	1,040	3,925	1,315	PDPAT Anchorage per AC261
		6	775	2,875	3,925	1,720	755	1,040	3,925	1,155	755	695	3,925	1,095	
	PHD 1001; 1002; 1011; 1012; 1021; 1022; 1041; 1042	8	775	2,155	3,925	1,690	755	800	3,925	865	755	520	3,925	820	
		10	775	1,725	3,925	1,350	—	—	—	—	—	—	—	—	
	B-Line B22; B22H1 7/8; B22SH; B22K06	12	775	1,435	3,925	1,125	—	—	—	—	—	—	—	—	
		16	775	1,080	3,925	845	—	—	—	—	—	—	—	—	

- For additional important information, see General Information and Notes on p. 28.
- Allowable anchorage loads are also limited by the DSSCB Connector Load tables on pp. 62 and 64. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- Allowable loads are based on 97 mil (12 ga.) thickness strut channel members with a minimum yield strength, F_y , of 33 ksi, tensile strength, F_u , of 45 ksi.
- Allowable loads for self-drilling screws are based on installation in minimum 3/16"-thick structural steel with $F_y = 36$ ksi. Values listed above may be used where other thicknesses of steel are encountered provided that the fastener has equal or better tested values into thicker steel. It is the responsibility of the designer to select the proper length fasteners based on the steel thickness installation.
- For screw fastener installation into steel backed by concrete, predrilling of both the steel and the concrete is suggested. For predrilling, use a maximum 3/16"-diameter drill bit. Screw to be installed through steel portion of channel strut (1.5 x screw diameter from punch-out) and centered vertically in web.
- For any connector occurring within 2" of channel strut splice, load not to exceed:
 - 7. Maximum allowable load of strut can be increased at high concentrated loads by welding each flange 1" from the strut channel to support directly at clip location:
 - For 7/8" strut size — $F_1 = 775$ lb., $F_2 = 1,800$ lb., $F_3 = 2,710$ lb., $F_4 = 3,200$ lb.
 - For 1 1/8" strut size — $F_1 = 775$ lb., $F_2 = 4,310$ lb., $F_3 = 3,925$ lb., $F_4 = 1,745$ lb.
 - 8. Required weld length is on each flange at spacing indicated.
 - 9. Anchorage spacing cannot be greater than framing spacing.
 - 10. Connector load to be located a minimum of 2" from end of strut channel.
 - 11. 1 1/8" x 3/16" strut may be used in lieu of a 1 1/8" x 7/8" strut provided the F_2 load does not exceed 1,615 lbs. If the strut is pierced and weld-attached to the structure, apply the following F_2 reduction factors:
 - For 3/16" hole at 1 1/8" o.c., multiply by 0.9;
 - For 7/8" hole at 6" o.c., multiply by 0.9;
 - For slotted hole (1 1/8" x 3/16") at 2" o.c., multiply by 0.85.
- Listed channels under models are not an inclusive list. Channels that meets the dimensional, gauge and ksi requirements shown on p. 69 are acceptable.
- The allowable pin anchorage loads (F_2 and F_4) are limited by calculation in accordance with ICC-ES ESR-2138. Allowable loads for Simpson Strong-Tie® PDPAT-62KP powder-actuated "top-hat" fasteners also apply to alternate fasteners with a minimum shank 0.157", a minimum head diameter of 0.300", a minimum allowable shear of 410 lb. and allowable tension of 260 lb. for A36 steel, and a minimum allowable shear of 420 lb. and allowable tension of 305 lb. for A572 or A992 steel per ESR-2138. "Tophat" fasteners are recommended to ensure adequate clamping force and consistent installations.
- For conditions that require drift with a 7/8" strut, it is recommended to weld to the steel support (no screws or pins) due to the possible clip interference with screw or pin. Alternately, use a 1 1/8" strut.

Strut size	Attachment at Splice	Splice Detail	F ₂ (lb.)		F ₄ (lb.)	
			# of Connectors to Stud @ Splice			
			1	2	1	2
7/8" or 1 1/8"	Screws or Pins (no weld @ splice)	—	865		785	
	(4) 1" welds strut to structure & (1) 7/8" weld top flange at splice	1	1,100	1,730	875	2,080
	(4) 1" welds strut to structure	2	865	1,730	875	1,380

F₄ allowable load with (2) connectors for splice detail 1 may be increased by 15% if one connector occurs on each side of splice, in lieu of both on one side of splice.




DSSCB Bypass Framing Drift Strut Connector

Concrete Insert Allowable Anchorage Loads (lb.)


Strut Size 1 $\frac{1}{8}$ " Wide x Depth (in.)	Minimum Edge Distance		Load Direction	Allowable Load (lb.)			
	Top of Slab (in.)	Bottom of Slab (in.)		Uncracked Concrete		Cracked Concrete	
				SDC A & B	SDC C-F	SDC A & B	SDC C-F
$\frac{7}{8}$ to 1 $\frac{1}{8}$	2	2	In-plane (F_1)	2,955	2,590	2,070	1,815
$\frac{7}{8}$	2	2	Tension (F_2)	1,715	1,250	1,200	1,050
1 $\frac{1}{8}$	2	2	Tension (F_2)	2,100	1,570	1,470	1,290
$\frac{7}{8}$ to 1 $\frac{1}{8}$	2	2	Compression (F_3)	2,710	2,710	2,710	2,710
$\frac{7}{8}$ to 1 $\frac{1}{8}$	2	6	Shear (F_4)	1,640	1,440	1,150	1,005
$\frac{7}{8}$ to 1 $\frac{1}{8}$	2	3	Shear (F_4)	485	425	340	300

- For additional DSSCB connector requirements and important technical information, visit strongtie.com.
- The designer is responsible for concrete slab design. The minimum tested concrete slab thickness is 8". Minimum end distance and edge distances for concrete insert struts are shown in the illustrations.
- Tabulated values are for concrete compressive strength $f'_c = 4,000$ psi minimum. For 3,000 psi or 3,500 psi, apply a load adjustment factor of 0.87 or 0.94, respectively.
- Allowable anchorage loads with concrete insert are also limited by the DSSCB Connector Load tables on pp. 62 and 64. Use the minimum tabulated values from the connector and strut anchorage load table above as applicable.
- Allowable loads are based on 97 mil (12 ga.) thickness strut channel members with a minimum yield strength, F_y , of 33 ksi, tensile strength, F_u , of 45 ksi. Strut size and dimensions are illustrated on p. 69. Other strut manufacturers with equivalent performance and dimensions may be used as approved by the designer.
- Tabulated values are for connector load spacing at 16" minimum. Reduce load linearly for connector spacing less than 16". For example, shear connector load (F_4), with 2" edge distance from the top of slab at 12" spacing is 1,440 lb. * $(12"/16") = 1,080$ lb.
- Tabulated values are for clips installed 6" minimum from the end of strut and concrete. Reduce load linearly for end distance less than 6" (up to a minimum of 3"). Reduced Load = Load * End Distance/6. For example, shear connector load (F_4), SDC C-F with 3" end distance from end of strut and concrete is 1,440 lb. * $(3"/6") = 720$ lb.
- The load direction of shear (F_4) is toward the bottom of the slab for the tabulated capacities.
- Shear load (F_4) may be linearly interpolated for center of strut embedded between 2" from the top to 3" from the bottom of the concrete slab as follows:
 - For an 8" concrete slab, shear load (F_4) may be linearly interpolated for center of strut embedded between 2" from the top and 3" from the bottom of the slab.
 - For slabs thicker than 8", linear interpolate based on bottom concrete edge distance.
- Allowable loads are based on testing in accordance with AC308 in the Simpson Strong-Tie's IAS-accredited test lab.
- For a 1 $\frac{1}{8}$ " wide x 1 $\frac{1}{8}$ " depth strut, the allowable load is determined by multiplying the $\frac{7}{8}$ " depth strut allowable load by 0.92 for tension and 1.0 for all other load directions.




DSSCB Bypass Framing Drift Strut Connector


Concrete Insert Anchorages




Slide Application



Fixed Application



Fixed Application
(Panelized)




Screw (1) #10 screw
to lip of channel
for F₁ support



Detail A
(F₁ support required)

This detail meets or exceeds
the published F₁ loads for this
connector when installed with
the DSHS drift stopper clip.


For horizontal drift connections
where F₁ support is not required,
do not fasten connector to strut.



12 ga. 33 ksi Concrete Insert
(by others)



Typical Unistrut Concrete Insert




Typical B-Line and PHD Concrete Insert

DSSCB Bypass Framing Drift Strut Connector


Drift Connectors

DSSCB Standoff Distances


Model No.	Application	Screw Pattern	No. of Screws	7/8" Struts		1 1/8" Struts		Concrete Inserts	
				Min. Standoff (in.)	Max. Standoff (in.)	Min. Standoff (in.)	Max. Standoff (in.)	Min. Standoff (in.)	Max. Standoff (in.)
DSSCB43.5	Slide Clip	A	2	1	2 3/8	1 13/16	3 1/8	3/16	1 1/2
DSSCB46		B	3		2 3/8		3 1/8		1 1/2
		C	2		2 3/8		3 1/8		1 1/2
		D	2		3 1/8		3 7/8		2 1/4
DSSCB48		E	4		2 3/8		3 1/8		1 1/2
		F	3		2 3/8		3 1/8		1 1/2
		G	3		3 1/8		3 7/8		2 1/4
DSSCB43.5	Fixed Clip	H	4	1	2 3/4	1 13/16	3 1/2	3/16	1 7/8
DSSCB46		I	2		2 3/4		3 1/2		1 7/8
		J	2		3 1/2		4 1/4		2 5/8
		K	6		2 3/4		3 1/2		1 7/8
DSSCB48		L	4		2 3/4		3 1/2		1 7/8
		M	4		3 1/2		4 1/4		2 5/8
		N	8		2 3/4		3 1/2		1 7/8
		O	4		2 3/4		3 1/2		1 7/8
		P	4	3 1/2	4 1/4	2 5/8			




DSSCB Standoff Distance with 1 1/8" Strut (7/8" Strut Similar) and Minimum Fastener Edge Distance for Slide-Clip Application



DSSCB Standoff Distance with Concrete Insert and Minimum Fastener Edge Distance for Slide-Clip Application



DSSCB Standoff Distance with 7/8" Strut and Minimum Fastener Edge Distance for Fixed-Clip Application










DSSCB Standoff Distance with Concrete Insert and Minimum Fastener Edge Distance for Fixed-Clip Application


DSSCB Bypass Framing Drift Strut Connector

Strut Requirements

Struts must meet the strut channel dimensions, gauge, yield strength, and punch patterns shown in these requirements.



Typical Strut Channel Anchorage with Welds



Typical Strut Channel Anchorage with Screws or Pins




DSSCB Bypass Framing Drift Strut Connector

CLT Applications


Strut Channel Allowable Anchorage Loads to CLT (lb.)

Strut Size 1 5/8" Wide x Depth (in.)	SDHR31400 Screw Spacing (in.)	Allowable Load (lb.)			
		In-Plane F ₁ (160)	Tension F ₂ (160)	Compression F ₃ (160)	Shear F ₄ (100)
7/8"	3 3/4"	2,200	1,675	2,710	2,200
1 1/8"					1,215
7/8"	5 5/8"	1,320	1,150	2,710	1,320
1 1/8"					1,215


- For additional DSSCB connector requirements and important technical information, visit strongtie.com.
- The designer is responsible for CLT system design. Tabulated values are based on minimum 3-ply (4 1/8") SPF CLT into side or end grain.
- Tabulated values are based on Strong-Drive® SDHR31400 Combo-Head screw 0.472" diameter x 4" length. Minimum end distance, and edge distances for wood screws are shown in the illustrations.
- Allowable anchorage loads in CLT are also limited by the DSSCB Connector Load tables on pp. 62 and 64. Use the minimum tabulated values from the connector and strut anchorage load table above as applicable.
- Allowable loads are based on 97 mil (12 ga.) thickness strut channel members with a minimum yield strength, F_y, of 33 ksi, tensile strength, F_u, of 45 ksi. Strut size and dimensions are illustrated below. Other strut manufacturers with DSSCB equivalent performance and dimensions may be used as approved by the designer.
- Tabulated values are for connector spacing at 8" minimum. Reduce load linearly for DSSCB connector spacing less than 8". For example, shear connector allowable load (F₄) for 7/8" depth strut, with 3 3/4" screw spacing, at 6" DSSCB connector spacing is 2,200 lb. * (6"/8") = 1,650 lb.
- Tabulated values are for clips installed 6" minimum from the end of CLT.
- Strut size 1 1/8" width x 7/8" depth is limited to a horizontal fixed application due to DSSCB clip interference with SDHR screw head. Coordination of screw location is recommended for proper installation. Alternately, use a 1 1/8" depth strut for drift applications.
- Loads (160) have been increased for wind or earthquake loading, with no further increase allowed. Reduce where other loads govern.
- Tabulated loads for 7/8" strut may be used for 1 1/8" strut, except F₂ load capacity reduced to 1,550 lb. and 1,035 lb. at 3 3/4" and 5 5/8" spacing, respectively.




Unistrut: P3300HS, P1000HS
PHD: 1221-1222
Blind: B22H17/8
Other manufacturers that meet dimensions and thickness



Typical DSSCB Fixed Clip Installation




Minimum CLT Edge and End Distance



Typical DSSCB Slide Clip Installation

DSHS Connector. (Sold separately and optional if required by designer. Clip shown blue for clarity only.) Use to prevent horizontal movement when needed. Fasten to top of strut channel with (1) #10-16.



Strut Channel Routed into CLT

HWDC Head-of-Wall Drift-Clip Connector



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The head-of-wall drift-clip connector (HWDC) is used to secure the head of a wall to the bottom of a slab or beam. The unique design allows anchor screws to be installed closer to the bend, providing a stronger and stiffer connection while also allowing horizontal and vertical movement during seismic and high-wind events. HWDC5.25 provides anchorage location options with a third slot providing a solution for clips overhanging beam flanges.

HWDC connectors are an optimal solution for adding strength to window or door jambs at head-of-wall connections. Tested load values are provided for anchorage to steel and concrete.

Features:

- Accommodates 1" of lateral drift in each direction, and 1" of upward and downward vertical deflection
- Unique design and placement of slot on anchorage leg allows for closer attachment of anchorage to the clip bend, providing increased load capacity
- The HWDC5.25 clip has three slots located at the anchorage leg allowing for attachment at the outer slots (anchorage pattern — centered) for maximum capacity or anchorage to the adjacent slots (anchorage pattern — off center) for walls that overhang the edge-angle or beam-edge
- Stiffening ribs are placed in between anchorage slots through the bend to provide additional strength and stiffness
- Simpson Strong-Tie® No-Equal® stamps mark the center of the slots to help ensure proper shouldered screw and anchor placement

Material: 97 mil (12 ga.), 50 ksi

Finish: Galvanized (G90)

Installation:


- Use the specified type and number of fasteners and anchors.
- In the vertical slots, use the specified number of #14 shoulder screws (included) for attachment to the stud. Install screws to align with No-Equal stamp.
- For attachment to steel support, use Simpson Strong-Tie Strong-Drive® XL Large-Head Metal Screws (XLQ114B1224). Use two screws centered in horizontal slot. Install screws to align with the No-Equal stamp and then back out one half-turn.
- For attachment to concrete support, use a Titen Turbo™ screw anchor.

Codes: See p. 15 for Code Reference Key Chart

Ordering Information:

Model No.	Ordering SKU	Package Quantity	
		Connectors	Shoulder Screws
HWDC3.37	HWDC3.37-KT25	25	55
HWDC5.25	HWDC5.25-KT25	25	55


Replacement #14 shoulder screws for HWDC are XLSH78B1414-RP83.



HWDC5.25 Installation with Two Shouldered Screws
(HWDC3.37 similar, only one shoulder screw required)




Drift Connectors




HWDC3.37

US Patent Pending


HWDC5.25



XLSH78B1414
#14 Shouldered Screw for Attachment to Stud Framing
(included)



XLQ114B1224
Screw for Anchorage to Steel Support
(sold separately)



TNT25134H
Screw Anchor for Anchorage to Concrete
(sold separately)

FCB/MFCB Bypass Framing Fixed-Clip Connector



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The FCB/MFCB clip is an economical, high-performance fixed-clip connector that can be used for a variety of framing applications. It is rated for tension, compression, shear and in-plane loads and offers the designer the flexibility of specifying different screw and anchorage patterns that conform to desired load levels.

Features:

- Rated for tension, compression, shear and in-plane loads
- Provides design flexibility with varying screw and anchorage patterns that achieve different load levels
- Strategically placed stiffeners, embossments and anchor holes maximize connector performance

Material: FCB — 54 mil (16 ga.); MFCB — 68 mil (14 ga.)

Finish: Galvanized (G90)

Installation:


- Use the specified type and number of anchors.
- Use the specified number of #12 self-drilling screws to CFS framing. Note that #10 self-drilling screws can be used per the load tables given on strongtie.com.
- For installations to wood framing, see Simpson Strong-Tie® engineering letter L-CF-FIXCLIPW at strongtie.com.

Codes: See p. 15 for Code Reference Key Chart


Order and Dimension Information:

Model No.	Ordering SKU	Length, L (in.)	Thickness mil (ga.)	Package Quantity
FCB43.5	FCB43.5-KT	3.5	54 (16)	25
MFCB43.5	MFCB43.5-KT	3.5	68 (14)	25
FCB45.5	FCB45.5-KT	5.5	54 (16)	25
MFCB45.5	MFCB45.5-KT	5.5	68 (14)	25
FCB47.5	FCB47.5-KT	7.5	54 (16)	25
MFCB47.5	MFCB47.5-KT	7.5	68 (14)	25
FCB49.5	FCB49.5-KT	9.5	54 (16)	25
FCB411.5	FCB411.5-KT	11.5	54 (16)	25


✓ **FCB43.5**
(MFCB43.5 similar)



✓ **FCB45.5**
(MFCB45.5 similar)




✓ **FCB47.5**
(MFCB47.5 similar)





US Patent. See strongtie.com/patent.

✓ **FCB49.5**




✓ **FCB411.5**




Typical FCB/MFCB Installation at the Base of a 6" Jamb Stud

Typical FCB/MFCB Installation at Bypass Framing



Typical FCB/MFCB Installation for Roof Rafters



Typical FCB/MFCB Installation at Spandrel Studs and Kickers

FCB/MFCB Bypass Framing Fixed-Clip Connector


FCB/MFCB Allowable Connector Loads (lb.)

Model No.	Connector Material Thickness mil (ga.)	Length L (in.)	Min./Max.	No. of #12-14 Self-Drilling Screws	Stud Thickness												Code Ref.
					33 mil (20 ga.)				43 mil (18 ga.)				54 mil (16 ga.)				
					F ₁ ^{3,4}	F ₂	F ₃	F ₄	F ₁ ^{3,4}	F ₂	F ₃	F ₄	F ₁ ^{3,4}	F ₂	F ₃	F ₄	
FCB43.5	54 (16)	3½	Min.	4	140	755	755	755	175	1,105	905	1,055	330	1,250	905	1,235	IBC, FL, LA
			Max.	6	205	1,100	1,130	1,075	450	1,105	1,260	1,350	615	1,250	2,245	1,770	
MFCB43.5	68 (14)	3½	Min.	4	200	755	755	755	255	1,105	1,105	1,055	410	1,530	2,280	1,595	
			Max.	6	425	1,130	1,130	1,075	555	1,265	1,265	1,545	755	1,530	2,630	1,770	
FCB45.5	54 (16)	5½	Min.	4	120	755	755	700	150	1,105	905	875	330	1,105	905	1,100	
			Max.	9	205	1,100	1,260	1,095	425	1,105	1,260	1,380	545	1,105	2,245	1,785	
MFCB45.5	68 (14)	5½	Min.	4	170	755	755	700	220	1,105	1,105	1,030	405	1,530	2,280	1,595	
			Max.	9	330	1,265	1,265	1,695	425	1,265	1,265	2,315	670	1,605	3,205	2,315	
FCB47.5	54 (16)	7½	Min.	4	120	755	755	220	150	1,105	875	330	330	1,105	875	815	
			Max.	12	205	1,100	1,260	705	295	1,105	1,260	1,050	535	1,105	2,245	1,345	
MFCB47.5	68 (14)	7½	Min.	4	170	755	755	415	220	1,105	1,105	540	405	1,580	2,280	1,025	
			Max.	12	245	1,265	1,265	1,345	315	1,265	1,405	1,530	575	1,605	3,350	2,700	
FCB49.5	54 (16)	9½	Min.	4	120	755	755	170	150	1,105	905	255	330	1,105	905	340	
			Max.	12	205	1,100	1,260	750	295	1,105	1,260	1,115	535	1,105	2,245	1,200	
FCB411.5	54 (16)	11½	Min.	4	120	755	755	140	150	1,105	935	205	330	1,105	935	340	
			Max.	12	205	1,100	1,260	795	270	1,105	1,260	860	490	1,105	2,245	860	


1. Min. fastener quantity and load values — fill all round holes; max. fastener quantity and load values — fill all round and triangular holes.
2. Allowable loads are based on clip capacity only and do not consider anchorage. The capacity of the connection system will be the minimum of the tabulated value and the allowable load from the FCB/MFCB Allowable Anchorage Loads table on p. 75.
3. Anchorage to the supporting structure using welds or a minimum of (2) #12-24 self-drilling screws is required.
4. Tabulated F₁ loads are based on assembly tests with the load through the centerline of stud. Tested failure mode due to screw pullout; therefore compare F₁ against F_p calculated per ASCE 7-16 and ASCE 7-22 Chapter 13 with values for "Fasteners of the connecting system for exterior nonstructural wall elements and connections" as specified in Table 13.5-1.
5. Tabulated values for 54 mil (16 ga.) CFS framing may be used for 68 mil (14 ga.) and greater steel thickness.

FCB/MFCB Standoff Distances


Model No.	L (in.)	Min./Max.	No. of #12-14 Self-Drilling Screws	Maximum Standoff (in.)
FCB43.5	3½	Min.	4	1
		Max.	6	1
MFCB43.5	3½	Min.	4	1
		Max.	6	1
FCB45.5	5½	Min.	4	1½
		Max.	9	1½
MFCB45.5	5½	Min.	4	1½
		Max.	9	1½
FCB47.5	7½	Min.	4	3½
		Max.	12	1
MFCB47.5	7½	Min.	4	3½
		Max.	12	1
FCB49.5	9½	Min.	4	5½
		Max.	12	1
FCB411.5	11½	Min.	4	7½
		Max.	12	1



Variable	Dimensions (in.)				
	FCB/MFCB				
	43.5	45.5	47.5	49.5	411.5
X ₁	¾	1	1	1	1
X ₂	1¼	1¼	1¼	1¼	1¼
X ₃	—	1¼	1¼	1¼	1¼
X ₄	—	—	1½	1½	1½
L	3½	5½	7½	9½	11½



FCB/MFCB Installation with Min. Fasteners



FCB/MFCB Installation with Max. Fasteners

FCB/MFCB Bypass Framing Fixed-Clip Connector

FCB, MFCB Allowable Anchorage Loads (lb.)

Anchorage Type	Minimum Base Material	No. of Anchors	FCB											MFCB						
			F ₁	F ₂	F ₄								F ₁	F ₂	F ₄					
					FCB43.5		FCB45.5		FCB47.5		FCB49.5				FCB411.5		MFCB43.5		MFCB45.5	
Min./Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min./Max.	Min.	Max.	Min.	Max.			
#12–24 self-drilling screws Strong-Drive® X and XL Metal screws	A36 steel 3/16" thick	2	395	795	635	590	945	555	1,075	535	1,015	370	1,015	395	1045	800	765	1,180	695	1,350
		3	590	1,120	950	880	1,420	830	1,610	570	1,520	370	1,520	590	1,725	1,195	1,150	1,770	1,045	2,025
		4	785	1,590	1,265	1,175	1,890	1,105	2,145	590	2,025	370	2,025	785	2,090	1,595	1,530	2,360	1,390	2,700
Simpson Strong-Tie® 0.157" x 5/8" power-actuated fasteners (PDPAT-62KP)	A36, A572 or A992 steel 3/16" thick	2	395	390	590	590	820	555	820	535	820	370	820	395	390	765	765	820	555	820
		3	590	715	880	880	1,230	725	1,230	570	1,230	370	1,230	590	715	1,150	1,150	1,230	725	1,230
		4	785	970	1,175	1,175	1,640	830	1,640	590	1,640	370	1,640	785	970	1,530	1,530	1,640	830	1,640
Weld E70XX electrodes	A36 steel 3/16" thick	Hard side: 2"	1,205	1,740	1,770	1,840	1,105	2,650	450	1,200	450	880	1,485	4,570	1,770	2,315	1,390	3,335		
		Free side: 1"																		
Simpson Strong-Tie 1/4" x 1 3/4" Titen Turbo™ (TNT25134H)	Concrete f'c = 2,500 psi	2	—	380	415	315	195	315	140	205	140	150	—	380	415	315	195	315		
		3	—	525	470	470	290	470	210	305	210	225	—	525	470	470	290	470		
		4	—	675	645	630	390	630	280	410	280	300	—	675	645	630	390	630		
Attached to CLT ⁴		F ₁ (160)	F ₂ (160)	F ₄ (100)								F ₁ (160)	F ₂ (160)	F ₄ (100)						
				FCB43.5				FCB45.5						MFCB43.5		MFCB45.5				
				Min./Max.				Min./Max.						Min./Max.		Min./Max.				
# 10 x 2 1/2" Strong-Drive® SD Connector Screw SD10212	3-ply min. (4 1/8") SPF CLT into side grain	4	595	705	1,080				1,080				595	705	1,080		1,080			
	3-ply min. (4 1/8") SPF CLT into end grain	4	400	375	600				600				400	375	600		600			

1. For additional important information, see General Information and Notes on p. 28.

2. Min. fastener quantity and load values — fill all round holes; Max. fastener quantity and load values — fill all round and triangular holes.

3. Allowable anchorage loads are also limited by the FCB Allowable Connector Load table on p. 74. Use the minimum tabulated values from the connector and anchorage load tables as applicable.

4. F₃ is a compression load and is not a controlling factor for anchor design attached to steel or concrete. For attachment to CLT, F₃ (100) is limited to 1,970 lb.

5. Allowable loads for #12–24 self-drilling screws and PDPAT powder-actuated fasteners are based on installation in minimum 3/16"-thick structural steel with F_y = 36 ksi. PDPAT values are also provided for A572 steel. Values listed above maybe used where other thicknesses of steel are encountered or other manufacturers are used, provided that the fastener has equal or better tested values (see p. 28). It is the responsibility of the designer to select the proper length fasteners based on the steel thickness installation.


6. F₂ allowable loads listed in table are for attachment with 0.157" x 5/8" PDPAT-62KP to 3/16" min. A36 steel. For attachment to 3/16" min. A572 or A992 steel, F₂ allowable loads can be increased to 585 lb., 800 lb., and 1,170 lb. for 2, 3, and 4 fasteners respectively.

7. For screw fastener installation into steel backed by concrete, predrilling of both the steel and the concrete is suggested. For predrilling use a maximum 3/16"-diameter drill bit. SD10212 screw is designed to thread into FCB/MFCB anchor hole without enlargement of clip hole.


8. Loads (160) have been increased for wind or earthquake loading, with no further increase allowed. Reduce where other loads govern.

FCB/MFCB Bypass Framing Fixed-Clip Connector


Rigid Connectors




Two Anchors




Three Anchors




Four Anchors



FCB/MFCB Anchor Layout to Steel
(Concrete sim. except where noted)



FCB/MFCB Installation with SD10212 Screws (3-ply min. CLT)
(minimum edge and end distance)



























FCB/MFCB Installation with SD10212 Screws (3-ply min. CLT)
(minimum edge and end distance)

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

FCB/MFCB Bypass Framing Fixed-Clip Connector

The following FCB/MFCB supplemental information is given to help designers with value-engineered solutions for our FCB/MFCB connectors. Loads are given on our website for fastener patterns other than our standard “min.” (fill all round holes) and “max.” (fill all round and triangle holes). In addition, the tables on the website give LRFD loads and loads for #10 screws as well as #12 screws. Please visit strongtie.com/cfs and reference FCB/MFCB clip.

Table 1: FCB/MFCB Screw Patterns

FCB43.5 MFCB43.5	Pattern “Min.”	Pattern “Max.”	For load capacities for patterns 1 through 10, refer to FCB/MFCB clip on strongtie.com .			
						
FCB45.5 MFCB45.5	Pattern “Min.”	Pattern 1	Pattern 2	Pattern “Max.”		
						
	Pattern “Min.”	Pattern 3	Pattern 4	Pattern 5	Pattern 6	Pattern “Max.”
						
FCB49.5	Pattern “Min.”	Pattern 7		Pattern 8		
						
	Pattern 9	Pattern 10		Pattern “Max.”		
						
FCB411.5	Pattern “Min.”	Pattern 11		Pattern 12		
						
	Pattern 13	Pattern 14		Pattern “Max.”		
						

FC Bypass Framing Fixed-Clip Connector

Ideal for high-seismic areas, Simpson Strong-Tie® FC connectors are the optimal solution for fixed-clip bypass framing. FC clips are often welded to the structure in high-seismic zones, but they also feature anchorage holes so that concrete screws or powder-actuated fasteners can be used to attach the clip to the structure. In addition to its anchorage versatility, the FC clip features prepunched screw holes for the framing attachment, eliminating the need for predrilling holes or worrying that fastener placement doesn't match the designer specifications. FC connectors are manufactured using heavy-duty 10- and 12-gauge steel to provide exceptional resistance to in-plane seismic load.

Features:

- The clips are available in lengths of 3½", 6" and 8", and are intended to be used with 3½", 6" and 8" studs, respectively
- The maximum standoff distance is 1" for 3½" studs and 1½" for 6" and 8" studs
- Embossments in the bend line provide increased strength and stiffness in the F_1 and F_2 load directions, but are positioned towards the center of the clip so that 1½"-long welds can be applied at the top and bottom of the clip
- Prepunched large-diameter anchor holes accommodate ¼"-diameter concrete screws like the Simpson Strong-Tie Titen HD® screw anchor
- Prepunched small-diameter anchor holes accommodate powder-actuated fasteners like the 0.157"-diameter Simpson Strong-Tie PDPAT or #12 self-drilling Simpson Strong-Tie Strong-Drive® XL Large-Head Metal screw

Material: 50 ksi

Finish: Galvanized (G90)

Installation:

- Use the specified type and number of fasteners and anchors


Codes: See p. 15 for Code Reference Key Chart

Order and Dimension Information:


Model No.	Ordering SKU	Thickness mil (ga.)	L (in.)	A (in.)	B (in.)	Package Quantity
FC32-5/97	FC32-5/97-R25	97 (12)	3½	½	½	25
FC62-5/97	FC62-5/97-R25	97 (12)	6	1	1	25
FC62-5/118	FC62-5/118-R25	118 (10)	6	1	1	25
FC82-5/118	FC82-5/118-R25	118 (10)	8	1	1	25

WANT MORE OPTIONS IN YOUR CLIP?


Try our SCS hybrid clip which supports slip and fixed conditions all in one clip. The SCS comes with a wide range of versatile options for attaching to structures. Attach with weld, screws, powder-actuated fasteners to steel, or attach to concrete with a single ½"- diameter or (2) ¼"- diameter anchors. Reference p. 36 for the SCS fixed-clip load chart.



FC82-5/118



FC62-5/97
(FC62-5 /118 similar)




FC32-5/97


FC Bypass Framing Fixed-Clip Connector

FC Allowable Connector Loads (lb.)

Model No.	Stud Thickness mil (ga.)	Fasteners to Stud		Allowable Load (lb.)					Code Ref.
		Allowable Pullout per Single #10 Screw	No. of #10 Self-Drilling Screws	F ₁		F ₂	F ₃	F ₄	
				1" Standoff	1 1/2" Standoff				
FC32-5/97	33 (20)	85	4	165	—	705	1,130	705	
			6	225	—	1,060	1,355	1,060	
FC62-5/97			4	115	130	705	1,130	705	
			6	140	160	1,060	1,355	1,060	
FC62-5/118			4	115	130	705	1,130	705	
			6	140	160	1,060	1,355	1,060	
FC82-5/118	4	105	120	705	1,130	705			
	6	135	155	1,060	1,355	1,060			
FC32-5/97	43 (18)	110	4	215	—	1,050	1,470	1,050	
			6	290	—	1,580	1,765	1,580	
FC62-5/97			4	150	175	1,050	1,470	1,050	
			6	185	215	1,580	1,765	1,580	
FC62-5/118			4	150	175	1,050	1,470	1,050	
			6	185	215	1,580	1,765	1,580	
FC82-5/118	4	140	160	1,050	1,470	1,050			
	6	175	200	1,580	1,765	1,580			
FC32-5/97	54 (16)	200	4	395	—	2,135	2,885	2,045	
			6	530	—	2,690	2,885	2,195	
FC62-5/97			4	325	375	2,135	2,885	2,045	
			6	405	465	2,690	2,885	2,195	
FC62-5/118			4	345	395	2,135	2,885	2,045	
			6	370	425	3,205	2,885	2,195	
FC82-5/118	4	325	375	2,135	2,885	2,045			
	6	440	505	3,205	2,885	2,195			
FC32-5/97	68 (14)	250	4	495	—	2,160	2,885	2,045	
			6	670	—	2,690	2,885	2,195	
FC62-5/97			4	435	500	2,160	2,885	2,045	
			6	465	535	2,690	2,885	2,195	
FC62-5/118			4	435	500	2,160	2,885	2,045	
			6	465	535	3,240	3,780	2,195	
FC82-5/118	4	410	470	2,160	2,885	2,045			
	6	555	640	3,240	3,780	2,195			
FC32-5/97	97 (12)	355	4	710	—	2,160	2,885	2,045	
			6	955	—	2,690	2,885	2,195	
FC62-5/97			4	775	775	2,160	2,885	2,045	
			6	1295	1295	2,690	2,885	2,195	
FC62-5/118			4	775	775	2,160	2,885	2,045	
			6	1150	1150	3,240	3,780	2,195	
FC82-5/118	4	585	585	2,160	2,885	2,045			
	6	790	790	3,240	3,780	2,195			



Typical FC Installation at Bypass Framing



FC62 with Four Screws

1. For additional important information, see General Information and Notes on p. 28.
2. FC Allowable Connector Loads are also limited by the FC Anchorage Load tables on pp. 80 and 81. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
3. See illustrations on p. 80 for screw fastener placement to stud framing.
4. Tabulated F₁ loads are based on assembly tests with the load through the centerline of stud. Tested failure mode due to screw pullout; therefore compare F₁ against F_D calculated per ASCE 7-16 and ASCE 7-22 Chapter 13 with values for "Fasteners of the connecting system for exterior nonstructural wall elements and connections" as specified in Table 13.5-1
5. F₁ loads are based on maximum standoff distances of 1" or 1 1/2" as shown. Other loads are applicable to a 1" standoff for FC32 and 1" or 1 1/2" standoff for FC62 and FC82.
6. The allowable plastic moment at the bend line in the F₁ load direction for 97 mil (12 ga.) and 118 mil (10 ga.) FC connectors are 395 in.-lb. and 675 in.-lb., respectively.

FC Bypass Framing Fixed-Clip Connector


FC Screw Patterns

Screw Pattern	Models		
	FC32-5/97	FC62-5/97 and FC62-5/118	FC82-5/118
4 screws			
6 screws			


FC Allowable Anchorage Loads to Steel (lb.)

Anchorage Type	Minimum Base Material	No. of Anchors	Allowable Load (lb.)		
			F ₁	F ₂	F ₄
#12–24 self-drilling screws Simpson Strong-Tie® X and XL Metal screws	A36 steel 3/16" thick	3	730	1,910	1,590
		4	975	2,545	3,180
Simpson Strong-Tie 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	A36 steel 3/16" thick	3	—	780	—
		4	—	1,040	1,040
Simpson Strong-Tie 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	A572 or A992 steel 3/16" thick	3	—	1,260	—
		4	—	1,710	1,710
Weld E70XX electrodes	A36 steel 3/16" thick	(2) Hard side: 1 1/2"	2,040	4,720	3,865
		(2) Free side: 1 1/2"			


- For additional important information, see General Information and Notes on p. 28.
- Allowable anchorage loads are also limited by the FC Connector Load table on p. 79. Use the minimum tabulated values from the connector and anchorage load tables as applicable.
- F₃ is a compression load and is not a controlling factor for anchor design.
- Allowable loads for #12–24 self-drilling screws and PDPAT powder-actuated fasteners are based on installation in minimum 3/16" thick structural steel with F_y = 36 ksi. PDPAT values are also provided for A572 steel. Values listed above maybe used where other thicknesses of steel are encountered or other manufacturers are used, provided that the fastener has equal or better tested values (see p. 28). It is the responsibility of the designer to select the proper length fasteners based on the steel thickness installation.
- For screw fastener installation into steel backed by concrete, predrilling of both the steel and the concrete is suggested. For predrilling, use a maximum 3/16"-diameter drill bit.



Weld



3 PAF Anchor Placement
(3 screws similar)



4 PAF Anchor Placement
(4 screws similar)


FC Anchor Layout

FC Bypass Framing Fixed-Clip Connector

FC Allowable Anchorage Loads to Concrete with Titen HD® (lb.)

Anchorage Type	Anchor Quantity and Size	Nominal Embedment (in.)	f'_c (psi)	Load Direction	Wind and SDC A & B		SDC C-F
					Uncracked Concrete	Cracked Concrete	Cracked Concrete ⁶
Simpson Strong-Tie® Titen HD screw anchor THDB25178H	(2) ¼" x 17⁄8"	1½"	3,000	F ₁	335	240	280
				F ₂	660	630	550
				F ₄	565	405	470
			4,000	F ₁	390	280	325
				F ₂	760	725	635
				F ₄	655	465	545
Simpson Strong-Tie Titen HD screw anchor THDB25234H	(2) ¼" x 2¾"	2½"	3,000	F ₁	370	265	310
				F ₂	475	695	610
				F ₄	515	445	520
			4,000	F ₁	430	305	360
				F ₂	550	805	705
				F ₄	590	515	600

1. Allowable anchor capacities have been determined using ACI 318-19 Chapter 17 calculations with a minimum concrete compressive strength (f'_c) of 3,000 and 4,000 psi in normal-weight concrete. Tabulated values shall be multiplied by a factor (λ_a) of 0.68 for sand light-weight concrete.
2. Edge distance is assumed to be 1½", and end distance is 2½".
3. Load values are for group anchors based on ACI 318, assuming supplementary reinforcement not present, load factors from ACI 318-19 Section 5.3, no supplement edge reinforcement, $\psi_{c,v} = 1.0$ for cracked concrete and periodic special inspection.
4. Allowable Stress Design (ASD) values were determined by multiplying calculated LRFD capacities by a conversion factor, Alpha (α), of 0.70 for seismic load and 0.6 for wind loads. ASD values for other combinations may be determined using alternate conversion factors.
5. Tabulated allowable ASD loads for Wind and Seismic in SDC A & B are based on using wind conversion factors and may be increased by 1.17 for SDC A & B only.
6. Design loads shall include the over-strength factor per ASCE7 Section 12.4.3. See Table 13.5-1 for fasteners in exterior wall connection systems.
7. Allowable loads for F₄ are based on the governing loading direction which is toward the edge of slab.
8. Allowable loads for F₁ are based on the governing loading direction which is toward the end of slab.
9. F₃ is a compression load and is not a controlling factor for anchor design.
10. For anchor subjected to both tension and shear loads, it shall be designed to satisfy the following:
 - For $N_a / N_{all} \leq 0.2$, the full allowable load in shear is permitted.
 - For $V_a / V_{all} \leq 0.2$, the full allowable load in tension is permitted.
 - For all other cases: $N_a / N_{all} + V_a / V_{all} \leq 1.2$ where:
 - N_a = Applied ASD tension load
 - N_{all} = Allowable F₂ or F₃ load from the FC Allowable Anchorage Loads for Concrete table
 - V_a = Applied ASD shear load
 - V_{all} = Allowable F₄ or F₁ load from the FC Allowable Anchorage Loads for Concrete table
11. Tabulated allowable loads are based on anchorage only. The capacity of the connection system shall be the minimum of the allowable anchorage load and the FC Allowable Connector Loads.



Titen HD Anchorage

For single-bolt fixed-clip connection to concrete, try the SCS hybrid clip; see p. 34.

FSB Bypass Framing Fixed-Clip Strut Connector

The FSB connector is the fixed-clip version of our popular SSB slide-clip strut connector. The FSB is commonly used at the bottom flange of a steel beam to accommodate large standoff distances for bypass curtain-wall studs.

Material: 54 mil (16 ga.)

Finish: Galvanized (G90)

Installation:



- Use the specified type and number of anchors.
- Use the specified type and number of screw fasteners to the stud.
- If the FSB intrudes on interior space, it can be trimmed. The trimmed part shall allow an edge distance of 1/2" or greater from the center of the nearest anchor to the end of the trimmed part.

Codes: See p. 15 for Code Reference Key Chart


Ordering Information:

Model No.	Ordering SKU	Package Quantity
FSB3.518	FSB3.518-R25	25

NEED SHORTER OR LONGER STRUT LENGTHS?
Try the HYS hybrid strut. HYS strut comes in 12", 15", 24" and 30" lengths. Reference p. 46 for HYS fixed-clip load chart.



Typical FSB3.518 Installation



FSB Installation with the Min. Number of Fasteners

FSB Bypass Framing Fixed-Clip Strut Connector

FSB Allowable Connector Loads (lb.)


Model No.	Connector Material Thickness mil (ga.)	Min./Max.	No. of #10-16 Screws	Stud Thickness												Code Ref.
				33 mil (20 ga.)				43 mil (18 ga.)				54 mil (16 ga.)				
				F ₁ ⁴	F ₂	F ₃	F ₄ ⁵	F ₁ ⁴	F ₂	F ₃	F ₄ ⁵	F ₁ ⁴	F ₂	F ₃	F ₄ ⁵	
FSB3.518	54 (16)	Min.	4	75	705	705	210	150	1,050	1,050	210	135	1,670	1,615	210	—
		Max.	9	105	1,590	1,340	210	205	2,365	2,185	210	200	2,475	2,285	260	

- For additional important information, see General Information and Notes on p. 28.
- FSB Allowable Connector Loads are also limited by the FSB Allowable Anchorage Loads table. Use the minimum value from the connector and anchorage load tables as applicable.
- Min. fasteners quantity and tabulated values — fill round holes; max. fasteners quantity and tabulated values — fill round and triangle holes.
- Tabulated F₁ loads are based on assembly tests with the load through the centerline of stud. Tested failure mode due to screw pullout; therefore compare F₁ against F_p calculated per ASCE 7-16 and ASCE 7-22 Chapter 13 with values for "Fasteners of the connecting system for exterior nonstructural wall elements and connections" as specified in Table 13.5-1.
- Tabulated F₄ values are controlled by 1/8" deformation limit. The connector strength load in the F₄ direction is 550 lb.
- Maximum standoff for FSB is 11" with two anchors to primary structure and 10" with four anchors to primary structure.

FSB Allowable Anchorage Loads (lb.)

Anchorage Type	No. of Anchors	F ₁	F ₂ and F ₃	F ₄
#12-24 self-drilling screws	2	270	1,250	550
	4	270	2,500	550
Simpson Strong-Tie® 0.157" x 5/8" powder-actuated fasteners PDPAT-62KP	2	—	820	—
	4	270	1,640	550
Weld	Hard side: 2"	270	2,455	550
	Free side: 1"			

- Allowable loads for #12-24 self-drilling screws and PDPAT powder-actuated fasteners are based on installation in minimum 3/8" thick structural steel with F_y = 36 ksi. It is the responsibility of the designer to select the proper length fasteners.
- Allowable loads for welded connections require E70XX electrodes with a minimum throat size equal to the clip thickness. Welding shall comply with AWS D1.3. Welding galvanized steel may produce harmful fumes; follow proper welding procedures and precautions.
- Allowable loads are for anchorage only. It is the responsibility of the designer to verify the strength and stability of the structure for loads imposed by the cold-formed steel framing connections.



FSB Anchor Layout

DoD-Compliant Blast Design

Does your project require DoD-compliant blast design?

Although Allowable Strength Design (ASD) is widely used by designers of Cold-Formed Steel (CFS) construction, some projects require additional connector limit states beyond the typical ASD values that are normally tabulated in our load tables. For example, many Department of Defense (DoD) projects require blast design of exterior wall framing and connections. Such projects may require the LRFD strength or nominal strength for the blast calculations. **These limit states required for blast design are located on strongtie.com. Search for the particular product required for blast design on our website to find these capacities.**

Not finding what you need? Please contact Simpson Strong-Tie.



Rigid Connectors

SIMPSON Strong-Tie Search... Products Solutions & Projects Resource Center Training & E

Table 2: FCB Bypass Framing Fixed-Clip Connectors (FCB43.5, FCB45 Service Load Limits and Strengths (lb.)

Model No.	No. of #12 Screws	Screw Pattern	Load Direction	Service Load Limit	Stud Thickness and Yield Strength						
					33 mil (20 ga.) – 33 ksi			43 mil (18 ga.) – 33 ksi			
					ASD	LRFD	Nominal	ASD	LRFD	Nominal	
FCB43.5	4	Min.	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,180	975	1,565	2,180	9.4
			F ₄	2,170	755	1,130	1,980	1,120	1,680	2,590	1.4
	6	Max.	F ₂	1,100	1,100	1,690	3,245	1,105	2,425	3,720	1.7
			F ₃	1,260	1,130	1,690	3,245	1,260	2,425	3,720	1.7
			F ₄	2,435	1,130	1,690	2,635	1,455	2,330	3,315	1.8
FCB45.5	4	Min.	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,180	975	1,565	2,180	9.4
			F ₄	1,225	755	1,130	1,720	945	1,515	2,150	1.2
	6	1	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,180	975	1,565	2,180	9.4
			F ₄	1,225	755	1,130	1,720	945	1,515	2,150	1.2
	6	2	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,180	975	1,565	2,180	9.4
			F ₄	1,225	755	1,130	1,720	945	1,515	2,150	1.2
	9	Max.	F ₂	1,100	1,100	2,025	2,880	1,105	2,425	3,720	1.7
			F ₃	1,260	1,260	2,285	3,245	1,260	2,425	3,720	1.7
			F ₄	2,570	1,180	1,890	2,685	1,485	2,375	3,380	1.8
FCB47.5	4	Min.	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,115	945	1,515	2,115	9.4
			F ₄	380	200	330	660	330	495	830	3.4
	6	3	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,115	945	1,515	2,115	9.4
			F ₄	380	260	390	775	380	575	1,060	3.4
	6	4	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,115	945	1,515	2,115	9.4
			F ₄	380	275	410	820	380	585	1,060	3.4
	6	5	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	785	1,275	2,550	945	1,515	2,550	9.4
			F ₄	465	385	580	1,155	575	860	1,720	9.4
	9	6	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,195	2,390	945	1,515	2,390	9.4
			F ₄	465	530	800	1,595	790	1,185	2,370	9.4
	12	Max.	F ₂	1,100	1,100	2,025	2,880	1,105	2,425	3,720	1.7
			F ₃	1,260	1,380	2,285	3,245	1,260	2,425	3,720	1.7
			F ₄	1,675	705	1,060	2,120	1,080	1,575	3,155	1.4

See footnotes below.

Table 3: FCB Bypass Framing Fixed-Clip Connectors (FCB49.5, FCB41 Load Limits and Strengths (lb.)

Model No.	No. of #12 Screws	Screw Pattern	Load Direction	Service Load Limit	Stud Thickness and Yield Strength						
					33 mil (20 ga.) – 33 ksi			43 mil (18 ga.) – 33 ksi			
					ASD	LRFD	Nominal	ASD	LRFD	Nominal	
FCB49.5	4	Min.	F ₂	1,500	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,180	945	1,565	2,180	9.4
			F ₄	380	170	255	510	255	380	760	3.4
	6	7	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,180	945	1,565	2,180	9.4
			F ₄	380	195	295	590	265	410	760	3.4
	6	8	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,130	2,180	945	1,565	2,180	9.4
			F ₄	380	210	315	630	265	410	760	3.4
	6	9	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	785	1,275	2,550	945	1,565	2,550	9.4
			F ₄	465	390	585	1,170	580	870	1,735	9.4
	9	10	F ₂	1,100	755	1,130	2,255	1,105	1,680	3,360	1.7
			F ₃	1,185	755	1,195	2,390	945	1,565	2,390	9.4

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.











Raise Your Expectations, Lower Your Installed Costs!

Utility Clip Connectors

The SSC steel stud connector, the SJC steel joist connector and the SFC steel framing connector, are designed so that a minimum number of clips can be stocked to accommodate a wide array of applications. Prepunched holes and intuitive fastener hole patterns ensure that the structural needs of the designer and the efficient installation goals of the contractor are both satisfied.

Testing You Can Trust

Simpson Strong-Tie® utility clip connectors have undergone industry-first testing to provide maximum benefit to both the installer and the designer. By testing these connectors as part of a complete system in the applications for which they are intended, rather than only testing the physical capabilities of the connector, Simpson Strong-Tie is able to provide comprehensive allowable loads for real-world conditions. This system-based approach eliminates the need for designers to manually calculate connector performance and anchorage, and provides confidence that designs based on these values have been thoroughly evaluated by the industry leader in structural connector research and development.

		Product Category		
		SSC	SJC	SFC
Tested Application				
Steel-to-Steel		✓	✓	✓
Bypass Framing		✓		
Headers		✓		✓
Base of Jamb		✓		
Rafter		✓		
Kneewall		✓		
U-Channel Bridging		✓		✓
Kicker			✓	
Soffit Hanger		✓	✓	


Innovative Design Lets You Work Smarter — Not Harder!

Simpson Strong-Tie® utility clip connectors have been designed with both the contractor and designer in mind. Connector dimensions and fastener/anchor locations have been developed to maximize design flexibility and installation efficiency.

Intelligent Connector Dimensions


SSC Steel Stud Connectors

Designed to accommodate open-side connections with flanges up to 3" wide and stiffener lips up to 3/4"*




SJC Steel Joist Connectors

Designed to accommodate open-side connections with flanges up to 3 1/2" wide and stiffener lips up to 3/4"



SFC Steel Framing Connectors

Designed to accommodate open-side connections with stiffener lips up to 3/4" long**




*SSC2.25 clips will accommodate 2" wide flange and 5/8" stiffener lips.

**SFC2.25 clips will accommodate 5/8" long stiffener lips.

For detailed product dimensions, refer to p. 92 for SSC, p. 100 for SJC and p. 103 for SFC.


Intuitive Fastener Patterns




SSC and SJC connectors include prepunched holes for 3/8"-diameter anchors that enable easy anchorage to concrete.

SSC and SJC anchorage leg also includes prepunched holes for #10 self-drilling screws.


SSC and SJC clips include round and triangle holes for minimum and maximum tabulated load values. Square holes are also provided, and can be combined with round and triangle holes for custom screw patterns per installation needs.



SSC and SJC 3/8" bolt-hole locations ensure tool clearance.



SJC 3/8" bolt-hole locations match-up with standard metal deck.



SSC and SFC hole locations accommodate u-channel.

SSC Steel-Stud Connector



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

SSC connectors are versatile utility clips ideal for a variety of stud-to-stud and stud-to-structure applications in cold-formed steel construction. The clips have been designed to enable easy installation on the open side of studs or joists with flanges up to 3" long and return lips up to 3/4". A wide pattern of strategic fastener locations allows the SSC to accommodate a variety of traditional and custom designs.

Features:

- Prepunched holes reduce installation cost by eliminating predrilling
- Intuitive fastener hole positions ensure accurate clip installation in accordance with design, support a wide range of design and application requirements and provide installation flexibility
- Angle lengths accommodate either hard-side or soft-side attachment for studs and joists with return lips up to 3/4"
- 4" leg length enables soft-side connections for studs and joists with flanges up to 3"
- Also suitable for u-channel bridging

Material: LSSC — 54 mil (50 ksi); SSC — 68 mil (50 ksi); MSSC — 97 mil (50 ksi)

Finish: Galvanized (G90)


Installation: Use all specified fasteners/anchors

Codes: See p. 15 for Code Reference Key Chart


Ordering Information:

Model No.	Ordering SKU	Package Quantity
SSC2.25	SSC2.25-R125	Bucket of 125
MSSC2.25	MSSC2.25-R90	Bucket of 90
LSSC4.25	LSSC4.25-R50	Bucket of 50
SSC4.25	SSC4.25-R50	
MSSC4.25	MSSC4.25-R50	
LSSC6.25	LSSC6.25-R30	Bucket of 30
SSC6.25	SSC6.25-R30	
MSSC6.25	MSSC6.25-R30	


For detailed product dimensions, refer to p. 92.



✓
SSC6.25
(LSSC6.25, MSSC6.25 similar)




✓
SSC4.25
(LSSC4.25, MSSC4.25 similar)




✓
SSC2.25
(MSSC2.25 similar)

(US Patent Pending)




Load-Bearing Headers


Curtain-Wall Headers




Base of Jamb



Bypass Framing



Bypass Framing with Stud Strut



Stud Blocking with CS Coiled Strap

*SSC2.25 clips will accommodate attachment to the inside web of 3 5/8" studs.


SSC Steel-Stud Connector

SSC Connectors — CFS to CFS Allowable Loads (lb.)


Rigid Connectors

Model No.	Connector Material Thickness mil (ga.)	Clip Length (in.)	Framing Member Depth (in.)	Fasteners			Allowable F ₄ Load (lb.)				Code Ref.
				Pattern ¹	Carried Member	Carrying Member	Minimum Member Thickness			Maximum Connector Load ³	
							33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)		
SSC2.25	68 (14)	2 1/4	3 3/8	Min.	(3) #10	(2) #10	165	225	345	635	IBC, FL, LA
MSSC2.25	97 (12)	2 1/4	3 3/8	Min.	(3) #10	(2) #10	165	225	345	635	
LSSC4.25	54 (16)	4 1/4	6	Min.	(2) #10	(2) #10	215	440	675	1,490	
				Max.	(5) #10	(4) #10	215	440	795		
				Outer	(4) #10	(4) #10	200	310	545		
SSC4.25	68 (14)	4 1/4	6	Min.	(2) #10	(2) #10	355	525	890	1,490	
				Max.	(5) #10	(4) #10	365	600	1,005		
				Outer	(4) #10	(4) #10	235	345	650		
MSSC4.25	97 (12)	4 1/4	6	Min.	(2) #10	(2) #10	355	525	890	1,490	
				Max.	(5) #10	(4) #10	365	600	1,005		
				Outer	(4) #10	(4) #10	235	345	650		
LSSC6.25	54 (16)	6 1/4	8	Min.	(4) #10	(4) #10	265	545	1,190	2,395	
				Max.	(7) #10	(6) #10	265	545	1,190		
				Outer	(6) #10	(4) #10	270	375	765		
SSC6.25	68 (14)	6 1/4	8	Min.	(4) #10	(4) #10	385	720	1,190	2,395	
				Max.	(7) #10	(6) #10	385	720	1,190		
				Outer	(6) #10	(4) #10	270	460	725		
MSSC6.25	97 (12)	6 1/4	8	Min.	(4) #10	(4) #10	385	720	1,190	2,395	
				Max.	(7) #10	(6) #10	385	720	1,365		
				Outer	(6) #10	(4) #10	270	460	725		


1. Min. fastener quantity and load values — fill all round holes; Max. fastener quantity and load values — fill all round and triangular holes; Outer fastener quantity and load values — see illustrations for fastener placement.
2. Allowable loads are based on bracing of the members located within 12" of the connection.
3. Maximum allowable load for connector that may not be exceeded when designing custom installations. designer is responsible for member and fastener design.
4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.
5. Reference pp. 93-95 for supplemental information and alternate screw patterns.
6. For 50 ksi studs, 68 mil (14 ga.) and thicker, use tabulated values for 54 mil (16 ga.) — 50 ksi studs.




SSC4.25 — Outer Fastener Pattern
(LSSC4.25 and MSSC4.25 similar)




SSC6.25 — Outer Fastener Pattern
(LSSC6.25 and MSSC6.25 similar)



Typical SSC4.25 Installation with Min. Quantity



SSC Installation with Carried Member Fasteners in Outer Row




SSC6.25 Installation with Min. Quantity

SSC Steel-Stud Connector


SSC Connectors — Bypass Framing Allowable Loads (lb.)

Model No.	Connector Material Thickness mil (ga.)	Clip Length (in.)	Fasteners ^{1,4}		Stud Thickness												Code Ref.
					33 mil (20 ga.)				43 mil (18 ga.)				54 mil (16 ga.)				
			Anchorage ²	Stud	F ₁ ³	F ₂	F ₃	F ₄	F ₁ ³	F ₂	F ₃	F ₄	F ₁ ³	F ₂	F ₃	F ₄	
SSC4.25	68 (14)	2¼	(3) #10	(4) #10	20	120	675	190	20	120	675	285	20	120	675	565	
			(3) PDPAT-62K	(4) #10	20	120	675	190	20	120	675	285	20	120	675	565	
MSSC4.25	97 (12)	4¼	(3) #10	(4) #10	45	240	705	190	45	240	1,050	285	45	240	1,170	565	
			(3) PDPAT-62K	(4) #10	45	240	705	190	45	240	1,050	285	45	240	1,170	565	
SSC4.25	68 (14)	4¼	(3) #10	(4) #10	40	705	705	700	40	870	1,050	850	40	935	1,265	850	
			(3) PDPAT-62KP	(4) #10	40	705	705	700	40	780	1,050	850	40	780	1,265	850	
MSSC4.25	97 (12)	4¼	(3) #10	(4) #10	105	705	705	705	105	1,050	1,050	850	105	1,265	1,265	850	
			(3) PDPAT-62KP	(4) #10	105	705	705	705	105	780	1,050	850	105	780	1,265	850	

- See illustration for fastener placement.
- Allowable loads are based on anchors installed in minimum 3/8"-thick structural steel with F_y = 36 ksi.
- Allowable loads based on in-plane loads applied at the centroid of the fasteners to the stud, with no rotational restraint of stud.
- See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



SSC Bypass Installation




SSC Head-of-Wall Installation


SSC Connectors — CFS Header to CFS Jamb Allowable Loads (lb.)

Model No.	Connector Material Thickness mil (ga.)	Clip Length (in.)	Jamb Stud Depth (in.)	Fasteners ⁴			Jamb and Header Thickness mil (ga.)	Allowable F ₃ Load (lb.)		Allowable F ₄ Load (lb.)	Code Ref.
				Pattern	Jamb	Header		Nested Stud and Track Header ³	Back-to-Back Header ²		
LSSC4.25	54 (16)	4¼	6	Max.	(5) #10	(4) #10	33 (20)	140	455	215	IBC, FL, LA
							43 (18)	220	660	440	
SSC4.25	68 (14)	4¼	6	Max.	(5) #10	(4) #10	54 (16)	375	1,055	1,005	IBC, FL, LA
							68 (14)	570	1,055	1,005	
LSSC6.25	54 (16)	6¼	8	Max.	(7) #10	(6) #10	33 (20)	160	455	265	IBC, FL, LA
							43 (18)	250	730	660	
SSC6.25	68 (14)	6¼	8	Max.	(7) #10	(6) #10	54 (16)	410	1,110	1,190	IBC, FL, LA
							68 (14)	640	1,110	1,190	


- Max. fastener quantity and load values — fill all round and triangular holes.
- Designer is responsible for checking web crippling of the header and reducing allowable loads accordingly.
- Also applies to box header per illustration below.
- See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



Nested Stud and Track



Box Header



Back-to-Back Header


SSC Steel-Stud Connector

Rigid Connectors


SSC Connectors — Base of CFS Jamb Allowable Loads (lb.)

Model No.	Connector Material Thickness mil (ga.)	Clip Length (in.)	Stud Member Depth (in.)	Fasteners		Stud Thickness mil (ga.)	Allowable Load F ₄ (lb.)	Code Ref.
				Anchor Diameter	Stud Fasteners ³			
SSC2.25	68 (14)	2¼	3½	¾	(3) #10	33 (20)	430	IBC, FL, LA
						43 (18)	605	
						54 (16)	940	
SSC4.25	68 (14)	4¼	6	¾	(5) #10	33 (20)	460	
						43 (18)	755	
						54 (16)	1190	
SSC6.25	68 (14)	6¼	8	¾	(7) #10	33 (20)	515	
						43 (18)	790	
						54 (16)	1,220	


1. Allowable loads are based on minimum 33 mil (20 ga.) track for 33 mil (20 ga.) and 43 mil (18 ga.) studs, and minimum 43 mil (18 ga.) track for 54 mil (16 ga.) studs, with one #10 screw into each stud flange.
2. Allowable loads assume adequate torsional bracing is provided. Bracing design is the responsibility of the designer.
3. See illustrations for fastener placement.
4. Designer is responsible for anchorage design.
5. For anchorage capacity options, see p. 91.
6. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.




SSC2.25 Fastener Pattern



SSC4.25 Fastener Pattern



SSC6.25 Fastener Pattern



Typical SSC Installation
(Note: This figure references the table on the following page.)



Titen HD®
Screw Anchor



AT-3G™
Adhesive

For anchor capacities for SSC clip, reference p. 91. For more information on anchors, see *Anchoring, Fastening and Restoration Systems for Concrete and Masonry* catalog at strongtie.com.

SSC Steel-Stud Connector

Base of CFS Jamb Allowable Anchorage Loads (lb.)

Uncracked Concrete, Wind and SDC A & B ⁸						
Model No.	Minimum Concrete Thickness (h_{min}) (in.)	$\frac{3}{8}$ " Diameter Simpson Strong-Tie® Anchor Type	Nominal Embedment Depth (h_{nom}) (in.)	Allowable Anchor Load, F_4 (lb.)		
				3,000 psi SLWC	3,000 psi NWC	4,000 psi NWC
SSC2.25	4	Titen HD®	2½	275	455	530
		Titen HD	¾	290	485	560
	6	SET-3G®	4	345	510	590
		AT-3G™	4	345	510	590
SSC4.25	4	Titen HD	2½	550	920	975
		Titen HD	¾	620	975	975
	6	SET-3G	4	735	880	880
		AT-3G	4	735	880	880
SSC6.25	4	Titen HD	2½	735	1,020	1,020
		Titen HD	¾	960	1,020	1,020
	6	SET-3G	4	880	880	880
		AT-3G	4	880	880	880

Cracked Concrete, Wind and SDC A & B ⁸						
Model No.	Minimum Concrete Thickness (h_{min}) (in.)	$\frac{3}{8}$ " Diameter Simpson Strong-Tie® Anchor Type	Nominal Embedment Depth (h_{nom}) (in.)	Allowable Anchor Load, F_4 (lb.)		
				3,000 psi SLWC	3,000 psi NWC	4,000 psi NWC
SSC2.25	4	Titen HD	2½	195	325	375
		Titen HD	¾	210	345	400
	6	SET-3G	4	245	360	420
		AT-3G	4	245	360	420
SSC4.25	4	Titen HD	2½	395	655	760
		Titen HD	¾	445	740	855
	6	SET-3G	4	525	775	880
		AT-3G	4	525	775	880
SSC6.25	4	Titen HD	2½	525	875	1,010
		Titen HD	¾	685	1,020	1,020
	6	SET-3G	4	810	880	880
		AT-3G	4	810	880	880


Cracked Concrete, SDC C-F ⁹						
Model No.	Minimum Concrete Thickness (h_{min}) (in.)	$\frac{3}{8}$ " Diameter Simpson Strong-Tie® Anchor Type	Nominal Embedment Depth (h_{nom}) (in.)	Allowable Anchor Load, F_4 (lb.)		
				3,000 psi SLWC	3,000 psi NWC	4,000 psi NWC
SSC2.25	4	Titen HD	2½	90	150	175
		Titen HD	¾	95	160	185
	6	SET-3G	4	115	170	195
		AT-3G	4	115	170	195
SSC4.25	4	Titen HD	2½	185	305	355
		Titen HD	¾	205	345	400
	6	SET-3G	4	245	355	355
		AT-3G	4	245	350	350
SSC6.25	4	Titen HD	2½	245	410	470
		Titen HD	¾	320	480	480
	6	SET-3G	4	355	355	355
		AT-3G	4	350	350	350

- Allowable anchor capacities have been determined using ACI 318-19 Chapter 17 calculations with the minimum concrete compressive strength, f'_c and slab thickness listed. Sand-lightweight concrete is abbreviated as "SLWC" while normal-weight concrete is abbreviated as "NWC".
- Nominal Embedment Depth/Effective Embedment Depth relationships:
 - $\frac{3}{8}$ " Titen HD in 4" Slab: $2.50" (h_{nom}) / 1.77" (h_{ef})$
 - $\frac{3}{8}$ " Titen HD in 6" Slab or thicker: $3.25" (h_{nom}) / 2.40" (h_{ef})$
 - SET-3G or AT-3G Adhesive with $\frac{3}{8}$ " F1554 Gr. 36 All-Thread Rod in 6" Slab or thicker: $4.0" (h_{nom}) = 4" (h_{ef})$
- Edge distances are assumed to be 1.81", 3.0" and 4.0" ($\frac{1}{2}$ of stud width) as determined for 3", 6" and 8" studs, respectively.
- End distances are assumed as 1.5 x min. edge distance in one direction and 'N/A' in the other direction. See figure on p. 90.
- Load values are for a single anchor based on ACI 318-19, assuming supplementary edge reinforcement not present, load factors from ACI 318-19 Section 5.3, no supplemental edge reinforcement, $\Psi_{c,v} = 1.0$ for cracked concrete and periodic special inspection. Reference ICC-ES or IAPMO-UES evaluation reports for further information.
- Load values are based on a short-term temperature range of 160°F and 180°F for SET-3G and AT-3G Long-term temperature range is assumed to be 110°F for both SET-3G and AT-3G. Dry hole conditions are assumed. Other conditions may be evaluated using Anchor Designer™ Software for ACI 318, ETAG and CSA. See strongtie.com/software.
- Allowable Stress Design (ASD) values were determined by multiplying calculated LRFD capacities by a conversion factor, Alpha (α), of 0.7 for seismic loads and 0.6 for wind loads. ASD values for other load combinations may be determined using alternate conversion factors.
- Tabulated allowable ASD loads for Wind and Seismic in SDC A & B are based on using wind conversion factors and may be increased by 1.17 for SDC A & B only.
- Allowable loads have been divided by an Omega (Ω) seismic factor of 2.5 for brittle failure as required by ACI 318-19 Chapter 17.
- Allowable F_4 load based on loading direction towards the edge of slab.
- Tabulated capacities are based on maximum allowable anchorage loads only. The capacity of the connection system shall be the minimum of the tabulated value and the allowable load value from the SSC Connectors: Base of CFS Jamb Allowable Load Tables.

SSC Steel-Stud Connector

SSC Connectors — CFS Rafter Allowable Loads (lb.)




Model No.	Connector Material Thickness mil (ga.)	Clip Length (in.)	Fasteners ^{1,4}		Allowable Load (lb.)			Code Ref.
			Anchorage to Steel ²	Supported Member	43 mil (18 ga.)			
					F ₂	F ₃	F ₄	
SSC4.25	68 (14)	4¼	(2) #12–24	(5) #10	710	1,075	595	IBC, FL, LA
			(4) 0.157" PDPAT	(5) #10	1,020	1,075	630	
MSSC4.25	97 (12)	4¼	(2) #12–24	(5) #10	710	1,335	595	
			(4) 0.157" PDPAT	(5) #10	1,025	1,335	815	



Typical SSC Installation

1. See illustrations for fastener placement.
2. Allowable loads are based on anchors installed in minimum 3/16"-thick structural steel with F_y = 36 ksi.
3. Allowable loads are based on a 6"-deep member. For deeper members, designer must consider web crippling of the member and reduce loads accordingly.
4. Table based on 18 ga. 33ksi CFS Rafter. CFS rafters of heavier gauge thickness can conservatively use allowable loads listed.
5. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.

SSC Utility Clip Dimensions



SSC Supplemental Information

The following SSC supplemental information is given to help designers with value-engineered solutions for our SSC connectors. Loads are given for fastener patterns other than our standard “min.” (fill all round holes) and “max.” (fill all round and triangle holes). The tables give ASD Loads. LRFD and nominal loads can be found at strongtie.com.


Table 1: SSC Screw Patterns

SSC2.25 MSC2.25	Pattern “Min.”	Pattern A	Pattern B	
	Pattern C	Pattern D	Pattern E	
	Pattern “Min.”	Pattern “Max.”	Pattern “Outer”	
	Pattern F	Pattern G	Pattern H	Pattern I
	Pattern “Min.”	Pattern “Max.”	Pattern “Outer”	
	Pattern J	Pattern K	Pattern L	
LSSC4.25 SSC4.25 MSC4.25	Pattern “Min.”	Pattern “Max.”	Pattern “Outer”	
	Pattern M	Pattern N	Pattern O	
	Pattern “Min.”	Pattern “Max.”	Pattern “Outer”	
	Pattern J	Pattern K	Pattern L	
LSSC6.25 SSC6.25 MSC6.25	Pattern “Min.”	Pattern “Max.”	Pattern “Outer”	
	Pattern M	Pattern N	Pattern O	
	Pattern “Min.”	Pattern “Max.”	Pattern “Outer”	
	Pattern J	Pattern K	Pattern L	
	Pattern “Min.”	Pattern “Max.”	Pattern “Outer”	
	Pattern M	Pattern N	Pattern O	


SSC Supplemental Information

Notes for Table 2 (see p. 95)

1. Calculated values are per AISI RP18-4, AISI S-100, or generally accepted industry standards. Blue-shaded values for F_4 are derived from test data. Whenever possible, unshaded F_4 values are based on the maximum calculated value and applicable tested value.
2. The tabulated values do not account for anchorage to the support. Anchor strength must be calculated separately and may reduce the capacity of the connection when compared to the tabulated values.
3. Tabulated values do not include shear, web crippling, buckling, or other local effects in the member. The designer must check member limit states separately.
4. For load combinations that include F_4 and/or F_2 and/or F_3 , use an appropriate interaction equation.
5. #10–16 screws shall have $P_{NVS} \geq 1,620$ lb. Calculated values are per AISI S-100. Screws must be installed with three (min.) exposed threads.
6. The number of screws is for one clip leg that is attached to the supported stud.
7. For the minimum screw pattern, fill all round holes. For the maximum screw pattern, fill all round and triangle holes. Reference p. 93.
8. In addition to calculations of net and gross section tension, and screw shear of the clip leg attached to the stud, F_2 values are also calculated for weak-axis bending of the anchored clip leg with the line of bending at the smaller anchor holes. The designer is responsible for calculating pullover, pullout, and tension strength of the anchors, and this may reduce F_2 strength compared to the tabulated values.
9. F_3 values are computed using the plate buckling provisions of AISI RP18-4.
10. For the F_4 calculated values, it's assumed that the connection eccentricity is taken by screws in the supported stud.
11. Service load limits for F_2 and F_3 are not given since there are no generally accepted industry methods available to compute these values. F_4 service load limits are based on AISI Research Report RP18-4 for $\frac{1}{8}$ " deflection or applicable test data.
12. For 50 ksi studs, 68 mil (14 ga.) and thicker, use tabulated values for 54 mil (16 ga.) — 50 ksi studs.



Installation Example #1 —
 SSC4.25 Typical
 Bypass Framing Installation



Installation Example #2 —
 SSC6.25 Typical
 Joist-to-Girder Installation

SSC Supplemental Information

Table 2: SSC Steel Stud Connectors — Allowable Loads (lb.)

Model No.	No. of #10 Screws	Screw Pattern	Stud Thickness and Yield Strength								
			33 mil (20 ga.) – 33 ksi			43 mil (18 ga.) – 33 ksi			54 mil (16 ga.) – 50 ksi		
			F ₂	F ₃	F ₄	F ₂	F ₃	F ₄	F ₂	F ₃	F ₄
SSC2.25	3	Min.	235	525	165	235	610	225	235	610	345
	2	A		350	65		475	100		475	205
	2	B		350	105		530	160		635	325
	3	C		525	165		795	225		820	345
	4	D		635	190		635	285		635	580
	6	E		820	245		820	375		820	750
MSSC2.25	3	Min.	475	525	165	475	795	225	475	1,055	345
	2	A	350	350	65		530	100		820	205
	2	B		350	105		530	160		1,070	325
	3	C	475	525	165		795	225		1,420	345
	4	D		700	190		1,060	285		1,105	580
	6	E		1,050	245		1,420	375		1,420	750
LSSC4.25	2	Min.		435	350	215	435	350	440	435	350
5	Max.	845	215		845	440		845	725		
4	Outer	575	200		575	310		575	520		
4	F	350	320		350	485		350	980		
8	G	695	530		695	805		695	1,495		
11	H	845	590		845	895		845	1,495		
14	I	845	730		845	1,105		845	1,495		
SSC4.25	2	Min.	660	350	355	660	485	525	660	485	890
	5	Max.		875	365		1,175	600		1,175	1,005
	4	Outer		700	235		795	330		795	625
	4	F		485	320		485	485		485	980
	8	G		970	530		970	805		970	1,625
	11	H		1,175	590		1,175	895		1,175	1,805
	14	I		1,175	730		1,175	1,105		1,175	1,860
MSSC4.25	2	Min.	1,340	350	355	1,340	530	525	1,340	840	890
	5	Max.		875	365		1,325	600		2,040	1,005
	4	Outer		700	235		1,060	330		1,380	625
	4	F		700	320		1,060	485		840	980
	8	G		1,400	530		1,680	805		1,680	1,625
	11	H		1,925	590		1,340	895		2,040	1,805
LSSC6.25	4	Min.	640	700	265	640	705	660	640	705	1,190
	7	Max.		1,225	265		1,230	660		1,230	1,190
	6	Outer		870	270		870	375		870	695
	4	J		350	435		350	660		350	1,330
	8	K		705	785		705	1,190		705	2,210
	12	L		1,055	1,050		1,055	1,590		1,055	2,205
	16	M			1,230			1,860			
	19	N		1,255	1,305		1,255	1,975		1,255	2,250
SSC6.25	4	Min.	975	700	385	975	980	720	975	980	1,190
	7	Max.		975	385		1,710	720		1,710	1,190
	6	Outer		975	270		1,210	460		1,210	725
	4	J		700	435		490	660		490	1,330
	8	K		980	785		980	1,190		980	2,405
	12	L		1,465	1,050		1,465	1,590		1,465	2,750
	16	M			1,230		1,745	1,860		1,745	2,845
	19	N		1,745	1,305		1,745	1,975		1,745	2,845
MSSC6.25	4	Min.	1,970	700	385	1,970	1,060	720	1,970	1,695	1,190
	7	Max.		1,225	385		1,855	720		2,965	1,365
	6	Outer		1,050	270		1,590	460		2,100	725
	4	J		700	435		1,060	660		845	1,330
	8	K		1,400	785		1,695	1,190		1,695	2,405
	12	L			1,050			1,590		2,540	3,210
	16	M			1,230			1,860			3,755
	19	N			1,305			1,975			3,985
22	O		1,455		2,200		4,305				

See notes on p. 94.

SJC Steel-Joist Connector



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

SJC connectors have been specifically designed for various CFS joist, rafter and underside of metal deck applications. The unique clip dimensions enable easy installation on the open side of joists and rafters with up to 3 1/2" flanges and return lips up to 3/4". For metal deck applications, the prepunched 3/8" holes easily accommodate 6", 8", 10" and 12" on-center metal deck flutes.

Features:

- Prepunched holes reduce installation cost by eliminating predrilling
- Intuitive fastener hole positions ensure accurate clip installation in accordance with design, support a wide range of design and application requirements and provide installation flexibility
- Angle lengths accommodate either hard-side or soft-side attachment for joists with return lips up to 3/4"
- 4 1/2" leg length enables soft-side connections for joists with flanges up to 3 1/2"
- Also accommodates kicker-to-metal deck applications

Material: SJC — 68 mil (50 ksi); MSJC — 97 mil (50 ksi)

Finish: Galvanized (G90)

Installation:


- Use all specified fasteners/anchors

Codes: See p. 15 for Code Reference Key Chart

Ordering Information:


Model No.	Ordering SKU	Package Quantity
SJC8.25	SJC8.25-R15	15
MSJC8.25	MSJC8.25-R15	
SJC10.25	SJC10.25-R15	15
MSJC10.25	MSJC10.25-R15	

For detailed product dimensions, refer to p. 100.




SJC10.25
(MSJC10.25 similar)

Full dimensions shown on p. 100.




SJC8.25
(MSJC8.25 similar)


US Patent.
See strongtie.com/patent.




Header to Jamb



Kickers to Underside of Deck



Joists to I-Beam



Joist to Girder


Note: For 6" and 8" joists: SSC connectors are recommended.

SJC Steel-Joist Connector


SJC Connectors — CFS to CFS Allowable Loads (lb.)

Model No.	Connector Material Thickness mil (ga.)	Clip Length (in.)	Framing Member Depth ⁴ (in.)	Fasteners ⁵			Allowable F4 Load (lb.) ²		Code Ref.	
				Pattern ¹	Carried Member	Carrying Member	Minimum Member Thickness			Maximum Connector Load ³
							54 mil (16 ga.)	68 mil (14 ga.)		
SJC8.25	68 (14)	8¼	10	Min.	(4) #10	(4) #10	980	980	2,715	IBC, FL, LA
				Max.	(9) #10	(7) #10	1,060	1,490		
				Inner	(5) #10	(4) #10	1,345	2,005		
MSJC8.25	97 (12)	8¼	10	Min.	(4) #10	(4) #10	1,055	1,710	2,715	
				Max.	(9) #10	(7) #10	1,250	1,765		
				Inner	(5) #10	(4) #10	1,535	2,160		
SJC10.25	68 (14)	11½" short leg 10¼" long leg	12	Min.	(6) #10	(4) #10	1,285	1,785	3,640	
				Max.	(11) #10	(7) #10	1,285	1,785		
				Inner	(7) #10	(5) #10	1,620	2,385		
MSJC10.25	97 (12)	11½" short leg 10¼" long leg	12	Min.	(6) #10	(4) #10	1,200	2,045	3,640	
				Max.	(11) #10	(7) #10	1,285	2,045		
				Inner	(7) #10	(5) #10	1,730	2,635		


1. Min. fastener quantity and load values — fill all round holes; Max. fastener quantity and load values — see illustrations for fastener placement.
2. Allowable loads are based on bracing of the members located within 12" of the connection.
3. Maximum allowable load for connector that may not be exceeded when designing custom installations. Designer is responsible for member and fastener design.
4. For 6" and 8" joists, SSC connectors are recommended.
5. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.




SJC10.25 — Inner Fastener Pattern
(MSJC10.25 similar)



SJC8.25 — Inner Fastener Pattern
(MSJC8.25 similar)



SJC Installation with Carried Member
Fasteners in Inner Row




SJC Installation with Carried Member
Fasteners in Min. Pattern
(fill circle holes min. quantity, circle and triangle holes max. quantity)

SJC Steel-Joist Connector

SJC Connectors — Kicker Allowable Loads (lb.)

Model No.	Connector Material Thickness mil (ga.)	Clip Length (in.)	Fasteners to Kicker	Kicker Angle ²	Max. Allowable Kicker Load for 33 mil (20 ga.) Min. Kicker (lb.)	Anchor Tension at Max. Allowable Kicker Load (lb.)	Code Ref.
SJC8.25	68 (14)	8¼	(6) #10	30°	490	345	IBC, FL, LA
				45°	535	570	
SJC10.25	68 (14)	10¼" short leg 11⅞" long leg	(6) #10	30°	625	475	
				45°	530	440	
MSJC10.25	97 (12)	10¼" short leg 11⅞" long leg	(6) #10	30°	950	675	
				45°	780	680	

1. Loads apply to connectors installed perpendicular or parallel to metal deck flutes, with minimum 33 mil (20 ga.) kicker. No increase allowed for kicker with heavier thickness.
2. Kicker angle is the acute angle measured relative to the horizontal plane of the metal deck.
3. The tabulated value for anchor tension is per anchor. Anchors must be designed for combined shear and tension. Simpson Strong-Tie® anchorage solutions are tabulated on p. 99. Alternate anchors may be utilized if designed by others.
4. Maximum kicker load and anchorage tension at maximum load determined based on tests.
5. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



Design Example

Determine maximum allowable kicker load and tension load on anchor for MSJC10.25.

Given:

- Kicker load = 400 lb.
- Kicker angle = 35° from horizontal

Calculations:

- Interpolate max. allowed kicker load for MSCJ10.25 at 35°:

$$\text{Max. allowed kicker load for MSCJ10.25} = 950 - (950 - 780) * (\cos 35^\circ - \cos 30^\circ) / (\cos 45^\circ - \cos 30^\circ) = 899 \text{ lb.}$$
 Kicker Load = 400 lb. < 899 lb. **OK**
- Interpolate anchor tension at max. allowable kicker load for MSCJ10.25 at 35°:

$$\text{Anchor tension at maximum load} = 675 - (675 - 680) * (\cos 35^\circ - \cos 30^\circ) / (\cos 45^\circ - \cos 30^\circ) = 676 \text{ lb.}$$
- Determine tension load on anchor:

$$\text{Tension load on anchor} = 676 * 400 / 899 = 301 \text{ lb.}$$

SJC Steel-Joist Connector

SJC and MSJC Kicker Allowable Anchorage Loads (lb.)

Uncracked Concrete, Wind and SDC A & B				
Minimum 2.5" Slab (3,000 psi concrete min.) Over Metal Deck				
Model No.	Kicker Angle	3/8"-Diameter Simpson Strong-Tie® Anchor Type	Nominal Embedment Depth, h_{nom} (in.)	Maximum Allowable Kicker Load (lb.)
SJC8.25	30°	Strong-Bolt 2	2½	490
		Titen HD	2¼	490
	45°	Strong-Bolt 2	2½	535
		Titen HD	2½	535
SJC10.25	30°	Strong-Bolt 2	2½	625
		Titen HD	2¼	625
	45°	Strong-Bolt 2	2½	530
		Titen HD	2¼	530


Cracked Concrete, Wind and SDC A & B				
Minimum 2.5" Slab (3,000 psi concrete min.) Over Metal Deck				
Model No.	Kicker Angle	3/8"-Diameter Simpson Strong-Tie Anchor Type	Nominal Embedment Depth, h_{nom} (in.)	Maximum Allowable Kicker Load (lb.)
SJC8.25	30°	Strong-Bolt 2	2¾	490
		Titen HD	2½	455
	45°	Strong-Bolt 2	2¾	535
		Titen HD	2½	320
SJC10.25	30°	Strong-Bolt 2	2¾	625
		Titen HD	2½	435
	45°	Strong-Bolt 2	2¾	530
		Titen HD	2½	410

Cracked Concrete, SDC C-F					
Minimum 2.5" Slab (3,000 psi concrete min.) Over Metal Deck					
Model No.	Kicker Angle	3/8"-Diameter Simpson Strong-Tie Anchor Type	Nominal Embedment Depth, h_{nom} (in.)	Maximum Allowable Kicker Load (lb.)	
				$\Omega = 1.5$	$\Omega = 2.5$
SJC8.25	30°	Strong-Bolt 2	3¾	490	435
		Titen HD	2½	255	155
	45°	Strong-Bolt 2	3¾	535	330
		Titen HD	2½	185	110
SJC10.25	30°	Strong-Bolt 2	3¾	625	420
		Titen HD	2½	245	145
	45°	Strong-Bolt 2	3¾	530	410
		Titen HD	2½	235	140




- The allowable maximum kicker load is the minimum of anchor allowable loads or connector allowable loads per p. 98. The anchor allowable loads include checks for anchor shear and tension interaction including the effects of eccentric loading.
- Allowable loads have been determined using ACI 318-19 Chapter 17 anchorage calculations with the minimum concrete compressive strength, f'_c and slab thickness listed.
- Strong-Bolt 2 and Titen HD are 3/8"-diameter carbon steel anchor.
- Concrete over metal deck may be Normal-Weight or Sand-Lightweight with f'_c of 3,000 psi minimum and 2.5" minimum slab height above upper flute.
- Minimum deck flute height is 1½" (distance from top flute to bottom flute). All other anchor installation requirements shall follow ICC-ES ESR-3037 and ICC-ES ESR-2713.
- Minimum Spacing and Edge distances for bottom of metal deck assemblies shall comply with those required in ICC-ES ESR-3037 for Strong-Bolt 2 anchors and ICC-ES ESR-2713 for Titen HD anchors.
- Load values are based on ACI 318-19, assuming supplementary edge reinforcement not present, load factors from ACI 318-19 Section 5.3, no supplemental edge reinforcement for uncracked concrete, $\Psi_{c,v} = 1.0$ for cracked concrete, and periodic special inspection. Reference ICC-ES ESR-3037 and ICC-ES ESR-2713 for further information.
- Allowable Stress Design (ASD) values have been determined by multiplying Load Resistance Factor Design (LRFD) values by a conversion factor, Alpha (α), of 0.7 for seismic loads and 0.6 for wind loads. ASD values for other types or load combinations may be determined using alternate conversion factors.
- Minimum end distance to edge of panel is two times anchor embedment depth.

SJC Utility Clip Dimensions



SJC8.25
(MSJC8.25 similar)




SJC10.25
(MSJC10.25 similar)

SJC Steel-Joist Connector


SJC and SSC Connectors — Soffit Stud Hanger Allowable Loads (lb.)

Model No.	Connector Thickness mil (ga.)	Clip Length (in.)	Anchors	Fasteners to Stud 33 mil (20 ga.) Min.	Allowable Tension Load (lb.)	
					No Bearing Plate	BP ¹ / ₂ -3 Bearing Plate
SJC8.25	68 (14)	8¼	(2) ¾"	(4) #10	465	930
SJC10.25	68 (14)	10¼	(2) ¾"	(4) #10	465	930
SSC4.25	68 (14)	4¼	(1) ¾"	(4) #10	220	585

1. Loads apply to connectors installed perpendicular or parallel to metal deck flutes.
2. Stud member design per designer. Tabulated loads for stud fasteners are based on a minimum stud thickness of 33 mil (20 ga.) with a yield stress of 33 ksi. For 30 mil interior studs with a yield strength of 33 ksi, multiply the tabulated values by 0.9.
3. Anchor design per designer. Note that the SJC requires the symmetrical placement of one anchor on each side of the stud centerline.
4. For the bearing plate option, use Simpson Strong-Tie® BP 1/2-3 bearing plates at each ¾"-diameter anchor. Bearing plates are sold separately.



Typical SJC Soffit Installation
(without bearing plate)



Typical SSC Soffit Installation
(with bearing plate)

SFC Steel Framing Connector



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

SFC connectors are a low-cost, multi-use utility clips for light to moderate loading conditions in CFS stud-to-stud and stud-to-structure applications where long leg lengths are not required.

Features:

- Reduced number of screws reduces installation cost
- Prepunched holes reduce installation cost by eliminating predrilling
- Intuitive fastener hole positions ensure accurate clip installation in accordance with design, support a wide range of design and application requirements and provide installation flexibility
- In soft-side stud installations, SFC will not interfere with stud lips up to 3/4" long*
- Also suitable for u-channel bridging

Material: SFC — 54 mil (50 ksi)

Finish: Galvanized (G90)

Installation:




- Use all specified fasteners/anchors

Codes: See p. 15 for Code Reference Key Chart


Ordering Information:

Model No.	Ordering SKU	Package Quantity
SFC2.25	SFC2.25-R300	Bucket of 300
SFC4.25	SFC4.25-R175	Bucket of 175
SFC6.25	SFC6.25-R100	Bucket of 100


For detailed product dimensions, refer to p. 103.




US Patent.
See strongtie.com/patent.



U-Channel to Jamb



Stud Blocking with CS Coiled Strap



Box Headers to Jambs
(also shown S/LS angles)


*SFC2.25 clips will accommodate 5/8" long stiffener clips.

SFC Steel Framing Connector

SFC Connectors — CFS to CFS Allowable Loads (lb.)




Model No.	Connector Material Thickness mil (ga.)	L (in.)	Framing Member Depth (in.)	Fasteners			Allowable F ₄ Load (lb.)				Code Ref.
				Pattern ¹	Carried Member	Carrying Member	Minimum Member Thickness			Maximum Connector Load ³	
							33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)		
SFC2.25	54 (16)	2¼	2½, 3¾	Min.	(2) #10	(2) #10	295	355	585	585	IBC, FL, LA
SFC4.25	54 (16)	4¼	6	Min.	(2) #10	(2) #10	355	525	690	1,615	
				Max.	(6) #10	(6) #10	575	750	1,615		
SFC6.25	54 (16)	6¼	8	Min.	(4) #10	(4) #10	590	920	1,840	2,440	
				Max.	(8) #10	(8) #10	590	920	1,880		

1. Min. fastener quantity and load values — fill all round holes;
Max. fastener quantity and load values — fill all round and triangular holes.
2. Allowable loads are based on bracing of the members located within 12" of the connection.
3. Maximum allowable load for connector that may not be exceeded when designing custom installations. Designer is responsible for member and fastener design.
4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



Typical SFC Installation

SFC Utility Clip Dimensions



C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

Rigid Connectors

RCA Rigid Connector Angle

The Simpson Strong-Tie® rigid connector angle is a general purpose clip angle designed for a wide range of cold-formed steel construction applications. With prepunched holes for fastener attachment, these L-shaped clips save time and labor on the job.

Features:

- Use with miscellaneous header/sill connections to jamb studs, jamb stud reinforcement at track, u-channel bridging, stud-blocking, bypass curtain-wall framing, joist connections and other versatile options
- Easy to install, with prepunched holes for quick and accurate fastener attachment

Material: RCAXXX/54 — 54 mil (16 ga.), 50 ksi
 RCAXXX/68 — 68 mil (14 ga.), 50 ksi
 RCAXXX/97 — 97 mil (12 ga.), 50 ksi
 (Note: "XXX" is model number shown below.)


Finish: Galvanized (G90)

Installation:


- Use all specified anchors/fasteners

Ordering Information:


Dimensions (in.)	Model No.	Ordering SKU	Bucket Quantity
2 x 2 x 3	RCA223/54	RCA223/54-R150	150
	RCA223/68	RCA223/68-R125	125
	RCA223/97	RCA223/97-R90	90
2 x 2 x 5	RCA225/54	RCA225/54-R90	90
	RCA225/68	RCA225/68-R75	75
	RCA225/97	RCA225/97-R55	55
2 x 2 x 7	RCA227/54	RCA227/54-R65	65
	RCA227/68	RCA227/68-R55	55
	RCA227/97	RCA227/97-R40	40
2 x 2 x 9	RCA229/54	RCA229/54-R50	50
	RCA229/68	RCA229/68-R50	50
	RCA229/97	RCA229/97-R35	35
2 x 2 x 11	RCA2211/54	RCA2211/54-R45	45
	RCA2211/68	RCA2211/68-R40	40
	RCA2211/97	RCA2211/97-R30	30
3 x 3 x 3	RCA333/54	RCA333/54-R100	100
	RCA333/68	RCA333/68-R85	85
	RCA333/97	RCA333/97-R60	60
3 x 3 x 5	RCA335/54	RCA335/54-R60	60
	RCA335/68	RCA335/68-R50	50
	RCA335/97	RCA335/97-R35	35




RCA Rigid Connector Angle



Typical RCA225 Installation at Sill/Jamb



Typical RCA229 Installation at Joist Connection



Typical RCA335 Installation at Bypass Framing

Screw Patterns for Rigid Connector Angles

Models	Pattern 3A	Pattern 3B	Pattern 3C		
RCA223/54 RCA223/ 68 RCA223/ 97 RCA333/ 54 RCA333/ 68 RCA333/ 97					
Models	Pattern 5A	Pattern 5B	Pattern 5C	Pattern 5D	Pattern 5E
RCA225/54 RCA225/ 68 RCA225/ 97 RCA335/ 54 RCA335/ 68 RCA335/ 97					
Models	Pattern 7A	Pattern 7B	Pattern 7C	Pattern 7D	Pattern 7E
RCA227/54 RCA227/ 68 RCA227/ 97					
Models	Pattern 9A	Pattern 9B	Pattern 9C	Pattern 9D	Pattern 9E
RCA229/ 54 RCA229/ 68 RCA229/ 97					
Models	Pattern 11A	Pattern 11B	Pattern 11C	Pattern 11D	Pattern 11E
RCA2211/ 54 RCA2211/ 68 RCA2211/ 97					

RCA Rigid Connector Angle

RCA Allowable Loads (lb.)

Model	No. of #10 Screws ^{5,6}	Screw Pattern	Stud Framing Thickness ¹¹								
			33 mil (20 ga.)			43 mil (18 ga.)			54 mil (16 ga.)		
			F ₂	F ₃	F ₄	F ₂	F ₃	F ₄	F ₂	F ₃	F ₄
RCA223/54	3	3A	205	495	200	205	765	310	205	810	620
	4	3B	205	660	390	205	805	605	205	805	1,210
	6	3C	205	990	480	205	1,210	740	205	1,210	1,485
RCA223/68	3	3A	310	495	200	310	765	310	310	1,125	620
	4	3B	310	660	390	310	1,020	605	310	1,120	1,210
	6	3C	310	990	480	310	1,530	740	310	1,680	1,485
RCA223/97	3	3A	495	495	200	630	765	310	630	1,530	620
	4	3B	630	660	390	630	1,020	605	630	1,610	1,210
	6	3C	630	990	480	630	1,530	740	630	2,415	1,485
RCA225/54	2	5A	330	330	265	340	510	410	340	545	815
	4	5B	340	660	535	340	810	830	340	810	1,660
	5	5C	340	825	460	340	1,275	705	340	1,365	1,415
	8	5D	340	1,320	915	340	1,620	1,420	340	1,620	2,380
	10	5E	340	1,650	1,035	340	2,030	1,600	340	2,030	2,620
RCA225/68	2	5A	330	330	265	510	510	410	520	760	815
	4	5B	520	660	535	520	1,020	830	520	1,125	1,660
	5	5C	520	825	460	520	1,275	705	520	1,895	1,415
	8	5D	520	1,320	915	520	2,040	1,420	520	2,255	2,835
	10	5E	520	1,650	1,035	520	2,550	1,600	520	2,815	3,200
RCA225/97	2	5A	330	330	265	510	510	410	1,020	1,020	815
	4	5B	660	660	535	1,020	1,020	830	1,050	1,610	1,660
	5	5C	825	825	460	1,050	1,275	705	1,050	2,550	1,415
	8	5D	1,050	1,320	915	1,050	2,040	1,420	1,050	3,220	2,835
	10	5E	1,050	1,650	1,035	1,050	2,550	1,600	1,050	4,025	3,200
RCA227/54	4	7A	475	660	545	475	1,020	840	475	1,095	1,675
	4	7B	475	660	595	475	815	920	475	815	1,840
	7	7C	475	1,155	765	475	1,785	1,185	475	1,920	2,370
	8	7D	475	1,320	1,120	475	1,625	1,730	475	1,625	3,045
	14	7E	475	2,310	1,685	475	2,845	2,605	475	2,845	3,670
RCA227/68	4	7A	660	660	545	725	1,020	840	725	1,525	1,675
	4	7B	660	660	595	725	1,020	920	725	1,130	1,840
	7	7C	725	1,155	765	725	1,785	1,185	725	2,665	2,370
	8	7D	725	1,320	1,120	725	2,040	1,730	725	2,260	3,460
	14	7E	725	2,310	1,685	725	3,570	2,605	725	3,955	4,530
RCA227/97	4	7A	660	660	545	1,020	1,020	840	1,470	2,040	1,675
	4	7B	660	660	595	1,020	1,020	920	1,470	1,610	1,840
	7	7C	1,155	1,155	765	1,470	1,785	1,185	1,470	3,570	2,370
	8	7D	1,320	1,320	1,120	1,470	2,040	1,730	1,470	3,220	3,460
	14	7E	1,470	2,310	1,685	1,470	3,570	2,605	1,470	5,635	5,210
RCA229/54	4	9A	615	660	595	615	1,020	920	615	1,100	1,840
	4	9B	575	660	620	575	815	960	575	815	1,920
	9	9C	615	1,485	1,105	615	2,295	1,705	615	2,475	3,410
	8	9D	615	1,320	1,210	615	1,630	1,865	615	1,630	3,735
	18	9E	615	2,970	2,375	615	3,665	3,670	615	3,665	4,715
RCA229/68	4	9A	660	660	595	935	1,020	920	935	1,525	1,840
	4	9B	660	660	620	935	1,020	960	935	1,130	1,920
	9	9C	935	1,485	1,105	935	2,295	1,705	935	3,435	3,410
	8	9D	935	1,320	1,210	935	2,040	1,865	935	2,260	3,735
	18	9E	935	2,970	2,375	935	4,590	3,670	935	5,090	5,750
RCA229/97	4	9A	660	660	595	1,020	1,020	920	1,890	2,040	1,840
	4	9B	660	660	620	1,020	1,020	960	1,890	1,610	1,920
	9	9C	1,485	1,485	1,105	1,890	2,295	1,705	1,890	4,590	3,410
	8	9D	1,320	1,320	1,210	1,890	2,040	1,865	1,890	3,220	3,735
	18	9E	1,890	2,970	2,375	1,890	4,590	3,670	1,890	7,240	7,340

See footnotes on p. 107.

RCA Rigid Connector Angle

RCA Allowable Loads (lb.) (cont.)

Model	No. of #10 Screws ^{5,6}	Screw Pattern	Stud Framing Thickness ¹¹								
			33 mil (20 ga.)			43 mil (18 ga.)			54 mil (16 ga.)		
			F ₂	F ₃	F ₄	F ₂	F ₃	F ₄	F ₂	F ₃	F ₄
RCA2211/54	4	11A	660	660	620	700	1,020	960	700	1,100	1,915
	4	11B	625	660	635	625	815	980	625	815	1,960
	11	11C	750	1,815	1,450	750	2,805	2,245	750	3,030	4,490
	8	11D	700	1,320	1,250	700	1,630	1,930	700	1,630	3,865
	22	11E	750	3,630	3,075	750	4,480	4,755	750	4,480	5,765
RCA2211/68	4	11A	660	660	620	1,020	1,020	960	1,140	1,530	1,915
	4	11B	660	660	635	1,020	1,020	980	1,060	1,130	1,960
	11	11C	1,140	1,815	1,450	1,140	2,805	2,245	1,140	4,205	4,490
	8	11D	1,140	1,320	1,250	1,140	2,040	1,930	1,140	2,260	3,865
	22	11E	1,140	3,630	3,075	1,140	5,610	4,755	1,140	6,220	7,030
RCA2211/97	4	11A	660	660	620	1,020	1,020	960	2,040	2,040	1,915
	4	11B	660	660	635	1,020	1,020	980	2,040	1,610	1,960
	11	11C	1,815	1,815	1,450	2,310	2,805	2,245	2,310	5,610	4,490
	8	11D	1,320	1,320	1,250	2,040	2,040	1,930	2,310	3,220	3,865
	22	11E	2,310	3,630	3,075	2,310	5,610	4,755	2,310	8,850	9,510
RCA333/54	3	3A	205	495	130	205	600	195	205	600	395
	4	3B	205	660	325	205	805	505	205	805	1,005
	6	3C	205	990	430	205	1,210	665	205	1,210	1,335
RCA333/68	3	3A	310	495	130	310	765	195	310	835	395
	4	3B	310	660	325	310	1,020	505	310	1,120	1,005
	6	3C	310	990	430	310	1,530	665	310	1,680	1,335
RCA333/97	3	3A	495	495	130	630	765	195	630	1,445	395
	4	3B	630	660	325	630	1,020	505	630	1,610	1,005
	6	3C	630	990	430	630	1,530	665	630	2,415	1,335
RCA335/54	2	5A	330	330	205	340	405	320	340	405	635
	4	5B	340	660	450	340	810	695	340	810	1,390
	5	5C	340	825	305	340	1,015	475	340	1,015	945
	8	5D	340	1,320	755	340	1,620	1,170	340	1,620	2,335
	10	5E	340	1,650	860	340	2,030	1,330	340	2,030	2,620
RCA335/68	2	5A	330	330	205	510	510	320	520	565	635
	4	5B	520	660	450	520	1,020	695	520	1,125	1,390
	5	5C	520	825	305	520	1,275	475	520	1,410	945
	8	5D	520	1,320	755	520	2,040	1,170	520	2,255	2,335
	10	5E	520	1,650	860	520	2,550	1,330	520	2,815	2,660
RCA335/97	2	5A	330	330	205	510	510	320	1,020	980	635
	4	5B	660	660	450	1,020	1,020	695	1,050	1,610	1,390
	5	5C	825	825	305	1,050	1,275	475	1,050	2,445	945
	8	5D	1,050	1,320	755	1,050	2,040	1,170	1,050	3,220	2,335
	10	5E	1,050	1,650	860	1,050	2,550	1,330	1,050	4,025	2,660

- As applicable, the tabulated values are calculated based on AISI RP18-4, AISI S100 or generally accepted industry standards.
- The tabulated values do not account for anchorage to the support. Anchor strength must be calculated separately and may reduce the capacity of the connection when compared to the tabulated values.
- Tabulated values do not include shear, web crippling, buckling or other local effects in the member. The designer must check member limit states separately.
- For load combinations that include F₄ and/or F₂ and/or F₃, use an appropriate interaction equation.
- #10–16 screws shall have P_{SS} ≥ 1,620 lb. Calculated values are per AISI S100. Screws must be installed with three (minimum) exposed threads.
- The number of screws is for one clip leg that is attached to the supported stud.
- In addition to calculations of net and gross section tension, F₂ values are also calculated and normally controlled by weak-axis bending of the anchored clip leg with the line of bending at the holes nearest the bend radius of the angle. Moment arm of ¾" is used for F₂ loads. The designer is responsible for calculating pullover, pullout and tension strength of the anchors and this may reduce F₂ strength compared to the tabulated values.
- F₃ strength values are computed using the plate buckling provisions of AISI RP18-4.
- For the F₄ strength values it's assumed that all of the connection eccentricity is taken by the screws in the supported stud. F₄ values are also limited by plate shear buckling per AISI RP18-4. The designer is responsible for calculating the shear capacity of the anchorage, which may reduce F₄ strength compared to the tabulated values.
- In addition to the limit states given in notes 7, 8 and 9, F₂, F₃ and F₄ are also limited by screw shear according to the thinnest connected part of the connector and stud.
- Service load limits for F₃ have not been evaluated since there are no generally accepted industry methods to compute this value. F₂ and F₄ ASD loads are based on AISI Research Report RP18-4, using a safety factor or ½" deflection.
- For 50 ksi studs, 68 mil (14 ga.) and thicker, use the tabulated values for 54 mil (16 ga.) – 50 ksi studs.

LS and S/LS Skewable Angles

LS and S/LS angles are load rated and provide the correct thickness and number of fasteners the specifier is looking for compared with field fabricated clip angles. These angles also have well-defined fastener locations, and testing ensures that the tabulated load values account for connection eccentricities. The connectors are general utility reinforcing angles with multiple uses. LS and S/LS connectors are skewable and can be used to attach members intersecting at angles.



Material: LS — 43 mil (18 ga.); S/LS — 43 mil (18 ga.)

Finish: Galvanized (G90)

Installation:

- Use all specified fasteners
- Field-skewable; bend one time only
- CFS framing must be constrained against rotation when using a single connection


Codes: See p. 15 for Code Reference Key Chart




LS and S/LS Allowable Loads (lb.)

Model No.	Length (in.)	Fasteners	Allowable Load (lb.)						Code Ref.
			33 mil (20 ga.)		43 mil (18 ga.)		54 mil (16 ga.)		
			F4	F2	F4	F2	F4	F2	
LS30	3%	(6) #10	200	—	370	—	500	—	—
S/LS50	4%	(4) #10	200	—	370	—	500	—	
S/LS70	6%	(6) #10	465	—	575	—	715	—	
LS90	7%	(12) #10	465	—	895	—	915	—	


1. Loads are for one part only.
2. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



LS and S/LS Top View



Typical Installation for Gravity Headers



Typical Installation for Curtain-Wall Head

SHH Header Hanger



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The SHH steel header hanger is used to support traditional CFS box headers that are fabricated with top and bottom tracks, as well as large-flange lay-in headers that are common in curtain-wall construction. The connector geometry minimizes drywall buildup, and the screw count has been minimized through extensive testing. A wide array of value-engineered hole patterns are available that will accommodate different load levels while minimizing installed cost.

Features:

- The bottom tabs transfer wind load from the horizontal window header to the jamb studs and help support the header assembly during installation.
- Tabulated loads are based on component assembly testing, which assists to mitigate design risk.
- The SHH6 is manufactured in steel thicknesses of 54 mil (16 ga.) and 68 mil (14 ga.) that are intended for use with 6"-deep (min.) box headers, and the SHH3 is manufactured from 68 mil (14 ga.) steel and is intended for 3 5/8" or 4"-deep (max.) box headers and large-flange lay-in headers.
- To enable easier drywall installation, the gusset portion of the SHH is coped to avoid 1 1/2" (max.) track legs.
- The screw-hole layout at the jamb studs accommodates flange sizes of 1 5/8", 2", 2 1/2", 3" and 3 1/2". This versatility allows two lines of fasteners to distribute the axial load.

Material: SHH3/68 – 68 mil (14 ga.), 40 ksi;
SHH6/54 – 54 mil (16 ga.), 40 ksi;
SHH6/68 – 68 mil (14 ga.), 40 ksi

Finish: Galvanized (G90)

Installation:

- Use all specified anchors/fasteners.
- At each connection to a jamb stud, use one SHH connector on each side of the header. A 1/8" (max.) gap is allowed between the end of the header and the face of the jamb stud. Use all specified fasteners.


Codes: See p. 15 for Code Reference Key Chart.

Ordering Information:


Model No.	Ordering SKU	Package Quantity
SSH3/68	SSH3/68-KT24	12 Left- and 12 Right-Handed Parts
SSH6/54	SSH6/54-KT24	
SSH6/68	SSH6/68-KT24	



Rigid Connectors



SHH3/68
Patent Pending




SHH6/54, SHH6/68
Patent Pending

SHH Header Hanger


SHH Allowable Connector Loads for Both Clips (lb.)

Model No.	Screw Pattern	#10 Screws to Jamb (Total per Connection)	#10 Screws to Header (Total per Connection)	Load Direction	Jamb Stud Thickness mil (ga.)	Header Stud / Track Thickness mil (ga.)					Code Ref.
						33 (20)	43 (18)	54 (16)	68 (14)	97 (12)	
SHH3/68	A1 or A2 (with box header)	Flanges (8) Web (4)	Web (8) Track (4)	F ₁	33 (20)	565	565		565		
					43 (18)		1,020		1,020		
					54 (16)		1,845		1,845		
				F ₄	33 (20)	1,300	1,300		1,300		
					43 (18)		1,740		1,740		
					54 (16)		3,140		3,140		
SHH3/68	B1 or B2 (with large-flange header)	Flanges (8) Web (4)	Flanges (8) Web (4)	F ₁	33 (20)	335	335		335		
					43 (18)		635		635		
					54 (16)		1,150		1,150		
				F ₄	33 (20)	1,285	1,285		1,285		
					43 (18)		1,775		1,775		
					54 (16)		2,275		2,275		
SHH6/54	C1 or C2	Flanges (8) Web (4)	Web (8) Track (4)	F ₁	33 (20)	400	400		400		
					43 (18)		770		770		
					54 (16)		1,705		1,705		
					68 (14)		1,705		1,705		
				F ₄	33 (20)	1,705	1,705		1,705		
					43 (18)		2,310		2,310		
					54 (16)		3,525		3,525		
					68 (14)		3,525		4,180	4,180	
SHH6/54	D1 or D2	Flanges (12) Web (4)	Web (12) Track (4)	F ₁	33 (20)	400	400		400		
					43 (18)		775		775		
					54 (16)		1,495		1,495		
				F ₄	33 (20)	1,705	1,705		1,705		
					43 (18)		2,365		2,365		
					54 (16)		5,335		5,335		
SHH6/54	E1 or E2	Flanges (16) Web (4)	Web (16) Track (4)	F ₁	33 (20)	400	400		400		
					43 (18)		775		775		
					54 (16)		1,495		1,495		
				F ₄	33 (20)	1,705	1,705		1,705		
					43 (18)		2,365		2,365		
					54 (16)		5,335		5,335		


See footnotes on p. 111.



SHH3/68 with Box Header



SHH3/68 with Large-Flange Header



SHH6/54, SHH6/68

SHH Header Hanger

SHH Allowable Connector Loads for Both Clips (lb.) (cont.)

Model No.	Screw Pattern	#10 Screws to Jamb (Total per Connection)	#10 Screws to Header (Total per Connection)	Load Direction	Jamb Stud Thickness mil (ga.)	Header Stud / Track Thickness mil (ga.)					Code Ref.
						33 (20)	43 (18)	54 (16)	68 (14)	97 (12)	
SHH6/54	F1 or F2	Flanges (20) Web (4)	Web (20) Track (4)	F ₁	33 (20)	400	400		400		
					43 (18)		775		775		
					54 (16)		775	1,565	1,565		
					68 (14)				2,565		
				F ₄	33 (20)	1,705	1,705		1,705		
					43 (18)		2,365		2,365		
					54 (16)		2,365	5,650	5,650		
					68 (14)				7,220		
SHH6/54	G1 or G2	Flanges (28) Web (4)	Web (28) Track (4)	F ₁	33 (20)	400	400		400		
					43 (18)		775		775		
					54 (16)		775	1,565	1,565		
					68 (14)				2,565		
					97 (12)						
				F ₄	33 (20)	1,705	1,705		1,705		
					43 (18)		2,365		2,365		
					54 (16)		2,365	5,650	5,650		
					68 (14)				7,700		
					97 (12)				7,700	9,710	
SHH6/68	E1 or E2	Flanges (16) Web (4)	Web (16) Track (4)	F ₁	33 (20)	400	400		400		
					43 (18)		870		870		
					54 (16)		870	1,610	1,610		
					68 (14)				2,565		
				F ₄	33 (20)	1,705	1,705		1,705		
					43 (18)		2,365		2,365		
					54 (16)		2,365	5,665	5,665		
					68 (14)				6,180		
SHH6/68	F1 or F2	Flanges (20) Web (4)	Web (20) Track (4)	F ₁	33 (20)	400	400		400		
					43 (18)		775		775		
					54 (16)		775	1,565	1,565		
					68 (14)				2,565		
				F ₄	33 (20)	1,705	1,705		1,705		
					43 (18)		2,365		2,365		
					54 (16)		2,365	5,665	5,655		
					68 (14)				7,415		
SHH6/68	G1 or G2	Flanges (28) Web (4)	Web (28) Track (4)	F ₁	33 (20)	400	400		400		
					43 (18)		870		870		
					54 (16)		870	1,610	1,610		
					68 (14)				2,565		
					97 (12)				2,565		
				F ₄	33 (20)	1,705	1,705		1,705		
					43 (18)		2,365		2,365		
					54 (16)		2,365	5,665	5,655		
					68 (14)				7,700		
					97 (12)				7,700	10,410	

1. Screws must be located in the patterns shown on p. 112 to achieve listed loads.

2. Connectors must be installed in pairs. Fasteners listed are number of fasteners for both clips in the connection at one end of header.

3. Allowable load is total load at one end of header assembly with both clips (left hand and right hand).

SHH Header Hanger

SHH Screw Patterns (Total Number of Screws Both Clips)

Rigid Connectors

SHH3/68 No. of Screws	Pattern A1	Pattern A2
Header Web (8)		
Header Track (4)		
Jamb Flanges (8)		
Jamb Web (4)		

SHH3/68 No. of Screws	Pattern B1	Pattern B2
Header Flange (8)		
Header Web (4)		
Jamb Flanges (8)		
Jamb Web (4)		

SHH6/54 No. of Screws	Pattern C1	Pattern C2
Header Web (8)		
Header Track (4)		
Jamb Flanges (8)		
Jamb Web (4)		

SHH6/54 No. of Screws	Pattern D1	Pattern D2
Header Web (12)		
Header Track (4)		
Jamb Flanges (12)		
Jamb Web (4)		

SHH6/54 or 68 No. of Screws	Pattern E1	Pattern E2
Header Web (16)		
Header Track (4)		
Jamb Flanges (16)		
Jamb Web (4)		

SHH6/54 or 68 No. of Screws	Pattern F1	Pattern F2
Header Web (20)		
Header Track (4)		
Jamb Flanges (20)		
Jamb Web (4)		

SHH6/54 or 68 No. of Screws	Pattern G1	Pattern G2
Header Web (28)		
Header Track (4)		
Jamb Flanges (28)		
Jamb Web (4)		

GP Gusset Plate

The GP gusset plate is designed to secure strapped shearwalls, truss connectors, miscellaneous wall connectors and other framing applications. The GP66 (6" x 6") and GP69 (6" x 9") have holes conveniently located 1" center-to-center to make screw installation easy and quick. The GP612 (6" x 12") and GP1212 (12" x 12") have holes on the outside edges and dimples in the center. The dimples act as screw locators while allowing strap brace attachment to gusset plates without prepunched holes getting in the way.

Features:



- Multiple stocked sizes and thicknesses to meet job site needs.
- Prepunched holes for easy and quick installation.
- Flexibility of dimples at center of GP612 and GP1212 models allow cross-bracing to attach anywhere in center of gusset plate without hole interference. On applications where gusset plate is attached to CFS framing, dimples act as screw locators, making fastening easier.

Material: 43 mil (18 ga.) — 33 ksi; 54 mil (16 ga.) — 50 ksi; 68 mil (14 ga.) — 50 ksi; 97 mil (12 ga.)— 50 ksi


Finish: Galvanized (G90)

Order and Dimension Information:


Model No.	Ordering SKU	Size (in.)	Thickness mil (ga.)	Connector Quantity
GP66/54	GP66/54-R50	6 x 6	54 (16)	50
GP69/43	GP69/43-R30	6 x 9	43 (18)	30
GP69/54	GP69/54-R25		54 (16)	25
GP612/68	GP612/68-R20	6 x 12	68 (14)	20
GP1212/68	GP1212/68-R15	12 x 12	68 (14)	15
GP1212/97	GP1212/97-R10		97 (12)	10




6" x 6" (GP66/54)



6" x 9" (GP69/43, GP69/54)



6" x 12" (GP612/68)



12" x 12" (GP1212/68, GP1212/97)

GP Gusset Plate

Rigid Connectors

Design Example

Given:

- 2024 IBC and AISI S100-16
- 600S162-68 (50 ksi) studs
- 600T125-68 (50 ksi) tracks @ top and bottom
- Gusset Plate: GP1212-68 ($F_y = 50$ ksi, $F_u = 65$ ksi)
- Strap 6" wide ($F_y = 50$ ksi, $F_u = 65$ ksi) — 14 ga. (0.0713" design thickness)
- Wall height, $H = 10'$; Wall width, $W = 8'$
- Horizontal wind load at top of wall from diaphragm = 8,000 lb. (ASD)
- The straps install on both side of the wall; screw spacing is specified as 1" in both horizontal and vertical directions


Calculations:

The wind load is $V = 8,000$ lb. (4,000 lb./ea. side). Summing the moments about A to achieve equilibrium, we have the following expression. Note axial load has been neglected because this assumption produces the highest anchor tension demand:

$$\Sigma M_A = V_H \times H - R_y \times W = 0$$

Determine ASD Vertical, Horizontal and Diagonal Loads:

Vertical chord load =	10,000 lb. (5,000 lb. ea. GP plate)
Horizontal chord load =	8,000 lb. (4,000 lb. ea. GP plate)
Diagonal load =	6,403 lb. ea. strap



CFS Strap Brace Wall

Flat Tension Strap:

• For strap yielding:


Gross area of cross-section	$T_n = A_g F_y$	(Eq. D2-1)
	$A_g = 0.428$ in ²	
	$\Omega_t = 1.67$	
	$T_n / \Omega_t = 12,808$ lb.	

• For fracture away from connection:

Assume 3 screw holes:	$d_{hole} = 0.190$ in.	(Eq. D3-1)
Net area of cross-section	$T_n = A_n F_u$	
	$A_n = 0.387$ in ²	
	$\Omega_t = 2.0$	
	$T_n / \Omega_t = 12,583$ lb.	

• Tension Rupture:

Effective net area subject to tension $A_e = U_{sl} A_{nt}$	$P_{nt} = A_e F_u$	(Eq. J6.2-1)
Shear lag factor	$A_e = 0.352$ in ²	
Net area subject to tension	$U_{sl} = 0.910$	(Eq. J6.2-4)
	$A_{nt} = 0.387$ in ²	
	$\Omega = 3$	(Table J6-1)
	$P_{nt} / \Omega = 7,629$ lb.	
Allowable Tension of Strap, $T_{allow} =$	7,629 lb.	> 6,403 lb. OK



Gusset Plate Net Section

Tension capacity of Gusset Plate:

• For Gusset Plate yielding:

Gross area of cross-section	$T_n = A_g F_y$	(Eq. D2-1)
	$A_g = 0.612$ in ²	
	$\Omega_t = 1.67$	
	$T_n / \Omega_t = 18,318$ lb.	

• For fracture away from connection:


Assume 6 screw holes:	$d_{hole} = 0.190$ in.	(Eq. D3-1)
Net area of cross-section	$T_n = A_n F_u$	
	$A_n = 0.530$ in ²	
	$\Omega_t = 2.0$	
	$T_n / \Omega_t = 17,213$ lb.	

• Tension Rupture:

Effective net area subject to tension $A_e = U_{sl} A_{nt}$	$P_{nt} = A_e F_u$	(Eq. J6.2-1)
Shear lag factor	$A_e = 0.484$ in ²	
Net area subject to tension	$U_{sl} = 0.913$	(Eq. J6.2-4)
	$A_{nt} = 0.530$ in ²	
	$\Omega = 3$	(Table J6-1)
	$P_{nt} / \Omega = 10,482$ lb.	
Allowable Tension of Gusset Plate, $T_{allow} =$	10,482 lb.	> 6,403 lb. OK

#10 screws 14 ga. (50 ksi) Strap attached to 14 ga. (50 ksi) Gusset Plate

ASD Shear #10 Screws 540 lb. (Simpson Strong-Tie® #10 X Metal Screw)



GP1212/68 Installation

Strap-to-Gusset Plate Connection: Number of screws required = 11.86 **Use 12 #10 screws**

Gusset-to-Stud Connection: Number of screws required = 9.26 **Use 10 #10 screws**

Gusset-to-Track Connection: Number of screws required = 7.41 **Use 8 #10 screws**

RCA-C Rigid Connector Angle for Concrete

Our lineup of rigid connector angles (RCA) has a new addition with the RCA-C. The RCA-C is an ideal solution for attaching stud framing to concrete supports. This connector provides the most anchor options for attaching to concrete in comparison to other similar connectors on the market. The connector's design includes holes for a 1/2"-diameter anchor, or two 1/4"-diameter concrete screws, accompanied by a wide array of fastening options — thus saving the installer the time and cost of drilling connector holes at the jobsite. In addition, the RCA connectors have been rigorously tested and load rated, giving you the confidence of quality and performance for your job.

Features:

- 2" x 2" legs provide plenty of room to make attachments to structure and stud framing.
- Multiple screw pattern options to stud framing for different load ratings.
- Can be used as either a heavy-duty shear and tension connector or light-duty moment connection.
- Prepunched holes for screws to stud framing and attachment to concrete. Prepunched holes on anchor leg provide options for (1) 1/2"-diameter anchor, (2) 1/4"-diameter anchors, or (2) 1/4"-diameter concrete screws.
- Attachment to concrete or masonry can be achieved with 1/2"-diameter Titen HD®, 1/2"-diameter Strong-Bolt® 2, 1/4"-diameter Titen HD, or 1/4"-diameter Titen Turbo™.

Material: RCA-C — 97 mil (12 ga.), 50 ksi

Finish: Galvanized (G90)

Installation:

- Use all specified anchors/fasteners.



Codes: Tested per ICC-ES AC261 and calculations per AISI RP18-4, AISI S100 or generally accepted industry standards. Visit strongtie.com for the latest load values and testing information.

Ordering Information:

Model No.	Ordering SKU	Bucket Quantity
RCA-C223/97	RCA-C223/97-R90	90
RCA-C225/97	RCA-C225/97-R55	55

Simpson Strong-Tie® Anchors for RCA-C Attachment to Concrete or Masonry

Anchor Type	Anchor Diameter
Titen HD Heavy-Duty Screw Anchor	1/2" or 1/4"
Strong-Bolt 2 Wedge Anchor	1/2"
Titen Turbo Concrete and Masonry Screw Anchor	1/4"



RCA-C Rigid Connector Angle for Concrete

Rigid Connectors




Figure A
F4 Loading
(one anchor shown)




Figure B
Anchor Tension, T, Created from Moment
(two anchors shown)




Figure C
Anchor Tension, T, Created from F2
(two anchors shown)

Table 1: RCA-C Allowable Connector Loads

Model No.	Anchor Holes Filled (Ref. Table 2 for Anchorage Design)	Fastener Pattern	No. of #10 Fasteners to Stud	Framing Member Thickness mil (ga.)	Connector Rotational Stiffness β (in.-kip/rad.)	Allowable Load			Anchor Tension, T	
						Moment M (in.-lb.)	Tension F ₂ (lb.)	Shear F ₄ (lb.)	At Allowable Moment, M (lb.) f' _c = 4,000 psi	At Allowable Tension Load, F ₂ (lb.) f' _c = 4,000 psi
RCA-C223/97	(1) 1/2"-dia. Titen HD® or (1) 1/2"-dia. Strong-Bolt® 2	4A or 6A	4 or 6	33 (20)	40	2,145	630	480	1,590	685
				43 (18)	40	2,550	725	740	1,950	790
				54 (16)	40	2,700	1,270	1,485	2,075	1,450
	(2) 1/4"-dia. Titen Turbo™	4C or 6C	4 or 6	33 (20)	40	1,750	630	450	720	685
				43 (18)	55	2,095	630	605	865	685
				54 (16)	65	2,920	630	1,120	1,225	685
RCA-C225/97	(1) 1/2"-dia. Titen HD or (1) 1/2"-dia. Strong-Bolt 2	4A	4	33 (20)	130	845	660	425	345	705
				43 (18)	160	1,500	1,020	550	615	1,105
				54 (16)	165	1,900	1,050	1,050	785	1,140
				33 (20)	155	1,830	1,050	845	755	1,140
		8A	8	43 (18)	160	3,215	1,050	1,105	1,355	1,140
				54 (16)	175	4,075	1,050	2,100	1,745	1,140
				33 (20)	155	3,430	1,050	845	1,455	1,140
				43 (18)	160	4,905	1,050	1,105	2,140	1,140
		10A	10	54 (16)	175	7,640	1,050	2,100	3,540	1,140
				33 (20)	155	1,100	660	480	295	705
				43 (18)	200	1,770	1,020	625	480	1,105
				54 (16)	220	2,005	1,050	1,185	545	1,140
	(2) 1/4"-dia. Titen HD	4B	4	33 (20)	170	2,375	1,050	960	645	1,140
				43 (18)	220	3,795	1,050	1,250	1,040	1,140
				54 (16)	240	4,300	1,050	2,375	1,180	1,140
		8B	8	33 (20)	170	4,450	1,050	960	1,225	1,140
				43 (18)	220	5,790	1,050	1,250	1,610	1,140
				54 (16)	240	8,060	1,050	2,375	2,285	1,140
	(2) 1/4"-dia. Titen Turbo	4C	4	33 (20)	190	1,100	660	480	250	705
				43 (18)	250	1,770	1,020	625	405	1,105
				54 (16)	310	2,005	1,050	1,185	460	1,140
		8C	8	33 (20)	200	2,375	1,050	960	545	1,140
				43 (18)	260	3,795	1,050	1,250	880	1,140
				54 (16)	320	4,300	1,050	2,375	995	1,140
10C		10	33 (20)	200	4,450	1,050	960	1,035	1,140	
			43 (18)	260	5,790	1,050	1,250	1,355	1,140	
			54 (16)	320	8,060	1,050	2,375	1,910	1,140	

- For additional important information, visit strongtie.com.
- The designer is responsible for anchorage design. Reference Table 2 (on p. 117) for anchorage solutions. Table 1 (above) is for clip capacity only and references to anchors are only to note which holes are filled to achieve listed capacities.
- See illustrations for fastener pattern placement.
- Tabulated values are based on framing members with track and stud of the same thickness and (1) #10 screw into each stud flange unless otherwise noted.
- Tabulated moment values correspond to maximum connector strength without consideration of serviceability. The designer must check out-of-plane deflections using tabulated rotational stiffness.
- Tabulated connector rotational stiffness may be used for any wall heights. The designer must consider member deflection due to bending in the stud member.
- Per IBC 2021, 2018, 2015, 2012 Table 1604.3 footnote f, wind load is permitted to be taken as 0.42 times "component and cladding loads" for deflection checks. For IBC 2009 and earlier, the factor is 0.7 instead of 0.42. Tabulated values have not been adjusted.
- Allowable loads are based on cold-formed steel members with a minimum F_y of 33 ksi and F_u of 45 ksi for 43 mil (18 ga.) and thinner and a minimum F_y of 50 ksi and F_u of 65 ksi for 54 mil (16 ga.) and thicker.
- Connectors subjected to tension, shear and moment loads: $F_2/F_{2all} + F_4/F_{4all} + M/M_{all} \leq 1.0$. F₄ interaction with Moment not required to be checked for walls 2'-0" or taller. Where: F₂, F₄ and M are the applied ASD tension, shear and moment, respectively. F_{2all}, F_{4all}, M_{all} are the allowable tension, shear and moment from Table 1, respectively.
- Anchor tension, T, is the force in the anchor, or both anchors for two-anchor solutions, at maximum allowable, M, or maximum allowable tension, F₂. See Table 2 for pre-engineered anchorage solutions that incorporate anchor T into the solution.
- Anchor tension is calculated using AISC Steel Design Guide 1. The Anchor Bolt Design illustration (Figure B) shows the anchor tension, T, based on an applied moment, M. An illustration for the anchor tension, T, based on a vertical tension load, F₂, shown in Figure C.
- Anchor tension, T, may be interpolated. Examples for RCA-C225/97:
 - M_{req} = 3,312 in.-lb. (given), fastener pattern 10C, 54 mil studs. Anchor tension, T, at allowable moment = (3,312/8,060) x 1,910 = 785 lb.
 - T_{req} = 525 lb. (given), fastener pattern 4A, 33 mil studs. Anchor tension, T, at allowable tension load, F₂ = (525/660) x 705 = 561 lb.
- Tabulated anchor tension, T, is based on f'_c = 4,000 psi. For f'_c = 3,000 psi, use an increase factor of 1.05.

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

RCA-C Rigid Connector Angle for Concrete

Table 2: RCA-C Allowable Anchorage Loads

Model No.	Type of Concrete	Anchor Type	Nominal Embedment Depth, h_{nom}	Min. Concrete Thickness, $h_{min.}$	Min. Anchor Edge Distance	Uncracked 4,000 psi Concrete			Cracked 4,000 psi Concrete						
						Wind and Seismic in SDC A & B			Wind and Seismic in SDC A & B			Seismic in SDC C-F			
						Allowable			Allowable			Allowable			
						Moment M	Tension F_2	Shear F_4	Moment M	Tension F_2	Shear F_4	Moment M	Tension F_2	Shear F_4	
(in.-lb.)	(lb.)	(lb.)	(in.-lb.)	(lb.)	(lb.)	(in.-lb.)	(lb.)	(lb.)							
RCA-C223/97	SLWC	(1) 1/2"-dia. Titen HD®	3/4	5	3	1,750	1,125	885	1,285	825	635	465	300	295	
					12	1,970	1,270	1,560	1,440	925	1,105	525	340	515	
		(1) 1/2"-dia. Strong-Bolt® 2	2 3/4	6	4	1,280	825	975	1,355	870	965	495	320	450	
					12	1,675	1,080	1,465	1,355	870	1,035	495	320	485	
			(2) 1/4"-dia. Titen Turbo™	1 3/4	3 3/4	1 3/4	735	455	495	—	—	—	—	—	—
						3	1,060	750	520	—	—	—	—	—	—
	NWC	(1) 1/2"-dia. Titen HD	3/4	5	3	2,465	1,585	1,305	1,830	1,180	930	680	440	435	
					12	2,760	1,775	2,295	2,045	1,315	1,625	765	495	760	
		(1) 1/2"-dia. Strong-Bolt 2	2 3/4	6	4	1,825	1,175	1,435	1,930	1,240	1,420	720	465	665	
					12	2,370	1,525	2,150	1,930	1,240	1,525	720	465	710	
			(2) 1/4"-dia. Titen Turbo	1 3/4	3 3/4	1 3/4	1,080	660	520	—	—	—	—	—	—
						3	1,540	1,075	520	—	—	—	—	—	—

- Anchor allowable loads have been determined using ACI 318-19 Chapter 17 anchorage calculations with the minimum concrete compressive strength, f'_c , and slab thickness listed. Sand-Lightweight Concrete is abbreviated as SLWC, Normal-Weight Concrete is abbreviated as NWC.
- Load values are for anchor based on ACI 318-19, assuming supplementary edge reinforcement not present, load factors from ACI 318 Section 5.3, no supplemental edge reinforcement, $\Psi_{c,v} = 1.0$ for cracked concrete and periodic special inspection. Reference ICC-ES or IAPMO-UES evaluation reports for further information.
- Allowable Stress Design (ASD) values were determined by multiplying calculated strength design values by a conversion factor, Alpha (α), of 0.7 for seismic loads and 0.6 for wind loads. ASD values for other load combinations may be determined using alternate conversion factors.
- End distances are assumed as N/A perpendicular to load.
- Tabulated allowable ASD loads for Wind and Seismic in SDC A & B are based on using wind conversion factors and may be increased by 1.17 for seismic SDC A & B only.
- Allowable loads have been divided by an Omega (Ω) seismic factor of 2.5 for brittle failure as required by ACI 318-19 Chapter 17.
- Tabulated capacities are based on maximum allowable anchorage loads only. The capacity of the connection system shall be the minimum of the tabulated value and the RCA-C allowable load value listed on Table 1.
- Tabulated loads in Table 2 are based on $f'_c = 4,000$ psi. For $f'_c = 3,000$ psi, use an adjustment factor of 0.86 for the blue-shaded values and 1.0 for all other values.
- For anchor subjected to tension, shear and moment loads:


When $(F_4/F_{4all}) \leq 0.2$	Then $F_2/F_{2all} + M/M_{all} \leq 1.0$
$(F_4/F_{4all}) > 0.2$	$F_2/F_{2all} + M/M_{all} \leq 1.2$
$(F_2/F_{4all} + M/M_{all}) \leq 0.2$	$F_4/F_{4all} \leq 1.0$
$(F_2/F_{4all} + M/M_{all}) > 0.2$	$F_2/F_{2all} + M/M_{all} \leq 1.2$
- For anchor subjected to tension, shear and moment loads:

When $(F_4/F_{4all}) \leq 0.2$	Then $F_2/F_{2all} + M/M_{all} \leq 1.0$
$(F_2/F_{2all} + M/M_{all}) \leq 0.2$	$F_4/F_{4all} \leq 1.0$
$(F_4/F_{4all}) > 0.2$ or $(F_2/F_{2all} + M/M_{all}) > 0.2$	$F_2/F_{2all} + M/M_{all} \leq 1.2$

Where F_2, F_4 and M are the applied ASD tension, shear and moment, respectively. $F_{2all}, F_{4all}, M_{all}$ are the allowable tension, shear and moment from Table 2, respectively.

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

Rigid Connectors



RCA-C Fastener Patterns

(1) 1/2"-Diameter Titen HD/Strong-Bolt 2		
Pattern 4A	Pattern 8A	Pattern 10A
(2) 1/4"-Diameter Titen HD		
Pattern 4B	Pattern 8B	Pattern 10B
(2) 1/4"-Diameter Titen Turbo		
Pattern 4C	Pattern 8C	Pattern 10C

RCA-C Rigid Connector Angle for Concrete

Example #1: Exterior Parapet Stud

- 2024 IBC (ASCE 7-22) and AISI S100-16
- 600S162-43 (33 ksi) stud @ 16" o.c. supported at base
- Parapet height, $L = 24"$
- Wind design pressure = 55.24 psf (LRFD)
- Deflection Limit, $\Delta_{allow} = L/240$ (Ref. IBC Table 1604.3)
- 4,000 psi NWC uncracked, SDC A & B, 3" edge

1. Determine ASD Wind Pressure:

$$p = (0.6) (55.24 \text{ psf}) = 33.14 \text{ psf}$$

$$w = (33.14 \text{ psf}) (16 \text{ in.}) (1 \text{ ft.}/12 \text{ in.}) = 44.19 \text{ plf}$$

2. Connector Moment Check:

$$M_{req} = \frac{wL^2}{2} = \frac{(44.19 \text{ plf})(24 \text{ in.})^2}{2 \left(12 \frac{\text{in.}}{\text{ft.}}\right)} = 1,061 \text{ in.-lb.}$$

From Table 1 for 600S162-43 (33ksi), 6" deep 43 mil stud:
 Select RCA-C225/97 (Fastener Pattern 4A) with $\frac{1}{2}" \phi$ anchor and
 (4) #10 screws, attaching to each stud @ 16" o.c.
 Allowable Moment 1,500 in.-lb. > 1,061 in.-lb. **OK**

3. Check Deflection at Required Moment:

$$\Delta_{req} = \Delta_{stud} + \Delta_{connection} = \frac{(0.7)wL^4}{8 E I_{xe}} + \left(\frac{(0.7)(M_{req})}{\beta}\right) L =$$

$$\Delta_{req} = \left(\frac{(0.7 \times 44.19 \text{ plf})(1 \text{ ft.}/12)(24 \text{ in.})^4}{8 (29,500,000 \text{ psi})(2.32 \text{ in.}^4)}\right) + \left(\frac{(0.7)(1,061 \text{ in.-lb.})}{\frac{165,000 \text{ in.-lb.}}{\text{rad.}}}\right) 24 \text{ in.} = 0.002 \text{ in.} + 0.108 \text{ in.} = 0.110 \text{ in.}$$

$$\Delta_{allow} = \frac{2L}{240} = \frac{2(24 \text{ in.})}{240} = 0.200 \text{ in.} > 0.110 \text{ in.} \text{ **OK**}$$

4. Select Anchorage:

Normal-weight concrete with $f'_c = 4,000$ psi
 Table 2 — Uncracked concrete in SDC A & B
 (1) $\frac{1}{2}"$ -diameter Titen HD® with $3\frac{1}{4}"$ embedment and 3" edge

$$F_{4req} = \frac{(44.19 \text{ plf})(24 \text{ in.})}{\left(12 \frac{\text{in.}}{\text{ft.}}\right)} = 88.4 \text{ lb.} \quad F_{4all} = 1,305 \text{ lb.} \quad F_{4req}/F_{4all} = 0.07 < 1 \text{ **OK**}$$

$$M_{req} = 1,061 \text{ in.-lb.} \quad M_{all} = 4,330 \text{ in.-lb.} \quad M_{req}/M_{all} = 0.25 < 1 \text{ **OK**}$$

Notes:

1. 2024 IBC load combinations for ASD include a factor of 0.6 for wind loads.
2. Per IBC table 1604.3 footnote f, 0.42 factor can be used to calculate deflections for component and cladding wind loads for LRFD loads; ASD load conversion is 0.7.

Example #2: Load-Bearing Wall with Tension and Shear on Base Connector

- 2024 IBC (ASCE7-22) and AISI S100-16
- 600S162-33 (33 ksi) stud @ 16" o.c. load bearing condition
- Base connection 4,000 psi NWC uncracked, SDC A & B, 3" edge (nearest fastener)
- Reactions $F_2 = 425 \text{ lb.}$, $F_4 = 147 \text{ lb.}$ (ASD Loads)

Select RCA-C225/97 (Fastener Pattern 4C) with (4) #10 screws and
 (2) $\frac{1}{4}"$ -diameter, $1\frac{3}{4}"$ embedded Titen Turbo™.

1. Determine Connector Allowables and Interactions (Reference Table 1 for Allowables):

$$F_{2req} = 425 \text{ lb.} \quad F_{2all} = 660 \text{ lb.} \quad F_{2req}/F_{2all} = 0.64 < 1 \text{ **OK**}$$

$$F_{4req} = 147 \text{ lb.} \quad F_{4all} = 480 \text{ lb.} \quad F_{4req}/F_{4all} = 0.31 < 1 \text{ **OK**}$$



$$\text{Interaction} = 0.95 < 1 \text{ **OK**}$$

2. Determine Anchorage Allowables and Interactions (Reference Table 2 for Allowables):

$$F_{2req} = 425 \text{ lb.} \quad F_{2all} = 1,205 \text{ lb.} \quad F_{2req}/F_{2all} = 0.35 < 1 \text{ **OK**}$$

$$F_{4req} = 147 \text{ lb.} \quad F_{4all} = 520 \text{ lb.} \quad F_{4req}/F_{4all} = 0.28 < 1 \text{ **OK**}$$

$$\text{Interaction} = 0.63 < 1.2 \text{ **OK**}$$



RCKW™ Kneewall Connector



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The Simpson Strong-Tie® RCKW is a heavy 171 mil (7 ga.) rigid connector that has been developed to resist an overturning moment at the base of exterior kneewalls and parapets as well as interior partial-height walls or overhead ribbon window conditions. These connectors offer a unique small and large anchor-hole pattern that permits anchorage to both concrete and structural steel. The single-anchor RCKW has been redesigned to have all of the same features as the previous model but with an added two-anchor option that accommodates ½"- or ¾"-diameter concrete anchors. If load requires more capacity, a stiffener, the RCKWS can be added. The RCKWS is a heavy 171 mil (7 ga.) stiffener that nests onto the RCKW clip. The screw holes and anchor holes in the stiffener line up with those in the RCKW clip, making fastener and anchor installation a snap. The RCKW clip and RCKWS stiffener are sold separately.

Features:

- In addition to our RCKW3 and RCKW3S with a large single bolt hole for 3½" framing, we have the RCKW3D and RCKW3DS, which have two large holes for anchorage. This provides an option for more capacity in 3½"-framed kneewalls.
- Anchorage legs incorporate stiffened flanges, improving overturning moment resistance.
- Large-diameter anchor holes accommodate ½"-diameter concrete screw anchor and wedge anchors, such as the Simpson Strong-Tie Titen HD® heavy-duty screw anchor and the Strong-Bolt® 2 wedge anchor.
- The RCKW5.5 and RCKW7.5 have three large holes for added versatility. The center hole is for a one-anchor solution at the edge or center of slab. The outer holes are for a two-anchor solution that requires higher capacities at the center of slab. In addition, two ¾" Titen HD screw anchors have been tested in the outer holes for shallow embedment conditions like fluted deck. The RCKW3 and RCKW3S have single large holes in the center, and the RCKW3D and RCKW3DS have two large holes on the outside for increased anchorage capacity.
- The smaller-diameter anchor holes enable attachment to structural steel with #12 self-drilling screws.
- Attachment to CMU can be achieved with Titen HD or Titen Turbo™ concrete and masonry screws.
- For the RCKWS: 171 mil (7 ga.) stiffeners are secured to the RCKW clip with screws, optimizing overturning moment resistance and stiffness.



Material: RCKW and RCKWS — 171 mil (7 ga.), 33 ksi

Coating: Galvanized (G90)

Installation:

- Use all specified screw fasteners. To achieve tabulated load values, use #12–14 screws according to the fastener patterns on p. 124.
- When using the RCKWS, secure the stiffener to the clip with the specified screw fasteners. Screws must be at least 1" long and extend through the connection with a minimum of three exposed threads.
- Use all specified anchors. To achieve tabulated stiffness values, the installation torque for concrete anchors shall be at least 17 ft.-lb. or the torque requirements of the anchor, whichever is greater.
- When using the larger-diameter anchor holes, the bottom track must be predrilled or punched with a ¼"-diameter hole.

Codes: See p. 15 for Code Reference Key Chart



US Patent. See strongtie.com/patent.

RCKW™ Kneewall Connector

Ordering Information:

Model No.	Ordering SKU	Package Quantity
RCKW3	RCKW3-R10	(10) RCKW3 clips
RCKW3D	RCKW3D-R10	(10) RCKW3D clips
RCKW5.5	RCKW5.5-R10	(10) RCKW5.5 clips
RCKW7.5	RCKW7.5-R10	(10) RCKW7.5 clips
RCKW3S	RCKW3S-R10	(10) RCKW3S stiffeners
RCKW3DS	RCKW3DS-R10	(10) RCKW3DS stiffeners
RCKW5.5S	RCKW5.5S-R10	(10) RCKW5.5S stiffeners



RCKW assembly test with member failure.

Assembly Tested


Many cold-formed steel connector manufacturers provide limited technical data for their products. As a result, designers often rely on detailed and time-consuming hand calculations for CFS connection design. This often involves assumptions regarding connection eccentricity, prying and connection stiffness.

Simpson Strong-Tie strives for ease of specification by providing comprehensive load tables based on tests that simulate real-world conditions. These load tables ensure that tabulated values reflect not only the strength of the connector, but also the strength of the fasteners, the anchorage, the member near the connection, and the overall stiffness. The photo to the right is an example of member failure near the connection. Such failures are reflected in our tabulated loads because of our assembly testing.

Simplified Stiffness Calculations

Some manufacturers tabulate stiffness values only for the connector. It's often unknown or unclear if their stiffness includes the screw fastener slip and how this varies with the thickness of the stud. Additionally, with some manufacturers, the deflection of the stud must be added to the deflection from the rotation of the connector in order to arrive at the final deflection for design.

Because we have tested the entire assembly, Simpson Strong-Tie tabulates stiffness that includes connector deflection, fastener slip and stud deflection for walls up to 38" in height. Our stiffness also takes into account the thickness of the stud, making it simple for the designer to calculate deflections: Simply divide the required moment by the tabulated stiffness, and then multiply the result by the stud length (Ref. Example #1 on p. 126). For walls over 38", a different approach is required (Ref. Example #2 on pp. 127-128).






Figure A
F₄ Loading
(one anchor shown)




Figure B
Anchor Tension, T, Created from Moment
(two anchors shown)




Figure C
Anchor Tension, T, Created from F₂
(two anchors shown)

Table 1: RCKW Allowable Loads (lb.) — Concrete Applications

Model No.	Fastener Pattern No.	Anchor Bolt Diameter (in.)	Fasteners to Stud	Framing Members Thickness mil (ga.)	Assembly Rotational Stiffness β_c (in.-kip / rad.)	Connector Rotational Stiffness β_c (in.-kip / rad.)	Allowable Load			Anchor Tension, T				Code Ref.
							Moment M (in.-lb.)	Tension F ₂ (lb.)	Shear F ₄ (lb.)	At Allowable Moment, M (lb.)		At Allowable Tension Load, F ₂ (lb.)		
										f' _c = 3,000 psi	f' _c = 4,000 psi	f' _c = 3,000 psi	f' _c = 4,000 psi	
RCKW3	1	(1) ½	(4) #12	33 (20)	94	101	2,060	860	620	1,545	1,495	1,080	1,055	IBC, FL, LA
				43 (18)	116	125	2,860	1,340	755	2,290	2,160	1,780	1,705	
				54 (16)	135	145	4,015	1,850	1,120	3,640	3,255	2,645	2,470	
				68 (14)	148	157	5,150	1,850	1,120	6,520	4,570	2,645	2,470	
RCKW3D	1B	(2) ½	(4) #12	33 (20)	120	132	2,060	860	620	855	845	1,080	1,055	—
				43 (18)	148	163	2,945	1,340	755	1,245	1,225	1,780	1,705	
				54 (16)	217	243	4,330	1,850	1,120	1,885	1,845	2,645	2,470	
				68 (14)	350	407	5,120	1,850	1,120	2,275	2,205	2,645	2,470	
RCKW3 and RCKW3S (Stiffener)	2	(1) ½	(9) #12	33 (20)	156	172	3,335	1,310	620	2,790	2,590	1,730	1,665	IBC, FL, LA
				43 (18)	156	172	3,910	1,710	795	3,490	3,145	2,390	2,250	
				54 (16)	156	172	5,855	2,220	1,120	6,700	4,585	3,410	3,085	
				68 (14)	156	172	5,855	2,410	1,415	6,700	4,585	3,875	3,425	
RCKW3D and RCKW3DS (Stiffener)	2B	(2) ½	(9) #12	33 (20)	231	269	4,440	1,310	620	1,940	1,895	1,730	1,665	—
				43 (18)	231	269	5,790	1,710	795	2,615	2,525	2,390	2,250	
				54 (16)	260	298	6,400	2,220	1,120	2,935	2,820	3,410	3,085	
				68 (14)	335	387	7,755	2,410	1,415	3,700	3,505	3,875	3,425	

See footnotes on p. 123.

RCKW™ Kneewall Connector

Table 1: RCKW Allowable Loads (lb.) — Concrete Applications (cont.)

Model No.	Fastener Pattern No.	Anchor Bolt Diameter (in.)	Fasteners to Stud	Framing Members Thickness mil (ga.)	Assembly Rotational Stiffness β_c (in.-kip / rad.)	Connector Rotational Stiffness β_c (in.-kip / rad.)	Allowable Load			Anchor Tension, T				Code Ref.
							Moment M (in.-lb.)	Tension F_2 (lb.)	Shear F_4 (lb.)	At Allowable Moment, M (lb.)		At Allowable Tension Load, F_2 (lb.)		
										$f'_c = 3,000$ psi	$f'_c = 4,000$ psi	$f'_c = 3,000$ psi	$f'_c = 4,000$ psi	
RCKW5.5	3	(1) ½	(6) #12	30 (20 DW) ^{5,6}	258	280	3,625	1,030	600	1,395	1,375	1,250	1,235	IBC, FL, LA
				33 (20 STR) ⁶	258	280	4,360	1,140	665	1,700	1,670	1,395	1,375	
				33 (20)	270	289	4,360	1,140	665	1,700	1,670	1,395	1,375	
				43 (18)	316	332	5,795	1,440	1,035	2,320	2,260	1,790	1,755	
				54 (16)	316	332	7,630	2,455	1,390	3,175	3,050	3,255	3,125	
				68 (14)	415	438	9,375	2,455	1,390	4,060	3,850	3,255	3,125	
	3A	(2) ¾	(6) #12	30 (20 DW) ^{5,6}	258	280	3,625	1,030	600	735	735	1,250	1,235	
				33 (20 STR) ⁶	258	280	4,360	1,140	665	890	885	1,395	1,375	
				33 (20)	270	289	4,360	1,140	665	890	885	1,395	1,375	
				43 (18)	347	370	5,795	1,440	1,035	1,190	1,180	1,790	1,755	
				54 (16)	411	438	8,865	2,455	1,390	1,845	1,830	3,255	3,125	
				68 (14)	502	534	10,775	2,455	1,390	2,265 ¹⁶	2,235 ¹⁶	3,255	3,125	
	3B	(2) ½	(6) #12	30 (20 DW) ^{5,6}	258	280	3,625	1,030	600	735	735	1,250	1,235	
				33 (20 STR) ⁶	258	280	4,360	1,140	665	890	885	1,395	1,375	
				33 (20)	270	289	4,360	1,140	665	890	885	1,395	1,375	
				43 (18)	347	370	5,795	1,440	1,035	1,190	1,180	1,790	1,755	
				54 (16)	593	650	9,995	2,455	1,390	2,095	2,070	3,255	3,125	
				68 (14)	717	786	10,015	2,455	1,390	2,100	2,075	3,255	3,125	
RCKW5.5 and RCKW5.5S (Stiffener)	4	(1) ½	(10) #12	33 (20)	460	503	4,855	1,660	665	1,910	1,870	2,090	2,040	
				43 (18)	460	503	7,835	2,165	1,035	3,275	3,140	2,815	2,720	
				54 (16)	476	512	10,740	2,980	1,390	4,830 ¹⁵	4,510 ¹⁵	4,115	3,895	
				68 (14)	517	552	13,020	2,980	1,830	6,315 ¹⁵	5,700 ¹⁵	4,115	3,895	
	4A	(2) ¾	(10) #12	33 (20)	460	503	4,855	1,660	665	990	985	2,090	2,040	
				43 (18)	460	503	7,835	2,165	1,035	1,625	1,610	2,815	2,720	
				54 (16)	482	520	11,985	2,980	1,390	2,535 ¹⁶	2,500 ¹⁶	4,115	3,895	
				68 (14)	625	676	14,300	2,980	1,830	3,065 ¹⁶	3,010 ¹⁶	4,115	3,895	
	4B	(2) ½	(10) #12	33 (20)	460	503	4,855	1,660	665	990	985	2,090	2,040	
				43 (18)	460	503	7,835	2,165	1,035	1,625	1,610	2,815	2,720	
				54 (16)	681	759	12,485	2,980	1,390	2,650	2,610	4,115	3,895	
				68 (14)	826	919	16,515	2,980	1,830	3,585	3,505	4,115	3,895	
RCKW7.5	5	(1) ½	(6) #12	33 (20)	531	559	5,990	1,095	795	1,680	1,655	1,315	1,300	
				43 (18)	531	559	7,610	1,280	1,200	2,165	2,125	1,550	1,530	
				54 (16)	565	590	10,570	2,165	1,695	3,100	3,020	2,715	2,655	
				68 (14)	605	628	13,895	2,165	1,695	4,225	4,065	2,715	2,655	
	5A	(2) ¾	(6) #12	33 (20)	531	559	5,990	1,095	795	1,015	1,010	1,315	1,300	
				43 (18)	531	559	7,610	1,280	1,200	1,300	1,290	1,550	1,530	
				54 (16)	806	858	12,840	2,165	1,695	2,230 ¹⁶	2,205 ¹⁶	2,715	2,655	
				68 (14)	1129	1212	13,835	2,165	1,695	2,410 ¹⁶	2,385 ¹⁶	2,715	2,655	
	5B	(2) ½	(6) #12	33 (20)	531	559	5,990	1,095	795	1,015	1,010	1,315	1,300	
				43 (18)	531	559	7,610	1,280	1,200	1,300	1,290	1,550	1,530	
				54 (16)	865	925	13,255	2,165	1,695	2,305	2,280	2,715	2,655	
				68 (14)	912	965	15,640	2,165	1,695	2,745	2,705	2,715	2,655	

See footnotes on p. 123.

RCKW™ Kneewall Connector

Table 1: RCKW Allowable Loads (lb.) — Concrete Applications (cont.)


Model No.	Fastener Pattern No.	Anchor Bolt Diameter (in.)	Fasteners to Stud	Framing Members Thickness mil (ga.)	Assembly Rotational Stiffness β_c (in.-kip / rad.)	Connector Rotational Stiffness β_c (in.-kip / rad.)	Allowable Load			Anchor Tension, T				Code Ref.
							Moment M (in.-lb.)	Tension F_2 (lb.)	Shear F_4 (lb.)	At Allowable Moment, M (lb.)		At Allowable Tension Load, F_2 (lb.)		
										$f'_c = 3,000$ psi	$f'_c = 4,000$ psi	$f'_c = 3,000$ psi	$f'_c = 4,000$ psi	
RCKW7.5 and RCKW5.5S (Stiffener)	6	(1) ½	(10) #12	33 (20)	484	514	8,705	1,730	795	2,505	2,455	2,130	2,095	IBC, FL, LA
				43 (18)	600	636	10,125	2,255	1,200	2,955	2,880	2,840	2,775	
				54 (16)	625	650	13,030	2,625	1,695	3,920	3,785	3,360	3,265	
				68 (14)	625	650	15,460	2,665	2,065	4,790 ¹⁵	4,580 ¹⁵	3,420	3,320	
	6A	(2) ¾	(10) #12	33 (20)	484	514	8,705	1,730	795	1,490	1,480	2,130	2,095	
				43 (18)	600	636	10,125	2,255	1,200	1,745	1,730	2,840	2,775	
				54 (16)	901	966	15,930	2,625	1,695	2,795 ¹⁶	2,760 ¹⁶	3,360	3,265	
				68 (14)	977	1,038	17,040	2,665	2,065	3,005 ¹⁶	2,960 ¹⁶	3,420	3,320	
	6B	(2) ½	(10) #12	33 (20)	484	514	8,705	1,730	795	1,490	1,480	2,130	2,095	
				43 (18)	600	636	10,125	2,255	1,200	1,745	1,730	2,840	2,775	
				54 (16)	938	1,009	18,495	2,625	1,695	3,280	3,225	3,360	3,265	
				68 (14)	1,104	1,183	21,735	2,665	2,065	3,900	3,820	3,420	3,320	

- For additional important information, see General Information and Notes on p. 28.
- The designer is responsible for anchorage design.
- See illustrations for fastener pattern placement.
- Tabulated values are based on framing members with track and stud of the same thickness and (1) #10 screw into each stud flange unless otherwise noted.
- Tabulated values may be used for framing members with track and stud of thickness 20 mil, $F_y = 57$ ksi (20 EQ).
- Tabulated values are applicable for framing members with CFS track of thickness 20 mil, $F_y = 57$ ksi (20 EQ).
- EQ — equivalent, DW — drywall, STR — structural.
- Tabulated moment values correspond to maximum connector strength without consideration of serviceability. Designer must check out-of-plane deflections using tabulated Rotational Stiffness.
- Tabulated Assembly Rotational Stiffness is applicable for walls at 38" tall with corresponding framing member depth and thickness. Reference Example #1 on p. 126.
- Tabulated Connector Rotational Stiffness may be used for any wall heights; the designer must consider member deflection due to bending in the stud member. Reference Example #2 on pp. 127–128.
- Per IBC 2012 and later Table 1604.3 footnote f, wind load is permitted to be taken as 0.42 times "component and cladding loads" for deflection checks. For IBC 2009 and earlier, the factor is 0.7 instead of 0.42. Tabulated values have not been adjusted.
- Anchor tension, T, is the force in the anchor, or both anchors for two-anchor solutions, at maximum allowable, M, or maximum allowable tension, F_2 .
- Tabulated values for anchor tension, T, at allowable tension load, F_2 , are provided for total anchor tension for (1) anchor and (2) anchors. See p. 129 for anchorage design tables and illustrations.
- Anchor tension is calculated using AISC Steel Design Guide 1. The 'Anchor Bolt Design' illustration (Figure B) shows the anchor tension, T, based on an applied moment, M. An illustration for the anchor tension, T, based on a vertical tension load, F_2 , shown in Figure C.
- Tabulated allowable tension loads for the connectors with ½"-diameter anchor bolts require ASTM F3125, Grade A325 or ASTM A449 high-strength bolts. For A307 Grade A bolt, anchor tension load is limited to 4,410 lb.
- Tabulated allowable tension loads for the connectors with ¾"-diameter anchor bolts require ASTM F3125, Grade A325 or ASTM A449 high-strength bolts. For A307 Grade A bolt, anchor tension load is limited to 2,200 lb.
- Anchor tension, T, may be interpolated..


RCKW™ Kneewall Connector

RCKW Fastener Patterns


RCKW3 and RCKW3S Options




RCKW3D and RCKW3DS Options










RCKW5.5 and RCKW5.5S Options



RCKW7.5 and RCKW5.5S Options



RCKW™ Kneewall Connector



RCKW™ Kneewall Connector

Example #1: Exterior Parapet Stud

Given:

- 2024 IBC (ASCE7-22) and AISI S100-16
- 600S162-33 (33 ksi) studs @ 16" o.c. supported at the base
- Parapet height, $L = 38''$ -tall studs
- Wind design pressure = 49.67 psf (LRFD)
- Deflection Limits, $\Delta_{allow} = L/240$ (Ref. IBC Table 1604.3)
- 3,000 psi concrete, cracked, SDC A & B, 3" anchor edge

Calculations:

Determine ASD wind pressure:

$$p = (0.6)(49.67 \text{ psf}) = 29.8 \text{ psf}$$

Note: 2024 IBC load combinations for ASD include a factor of 0.6 for wind loads.

$$w = (29.8 \text{ psf}) \frac{16 \text{ in.}}{12 \text{ in.}} = 39.7 \text{ plf}$$

Determine Required Moment:

$$M_{req} = \frac{wL^2}{2} = \frac{(39.7 \text{ plf})(38 \text{ in.})^2}{2 \left(12 \frac{\text{in.}}{\text{ft.}}\right)} = 2,389 \text{ in.-lb.}$$

From Table 1 (p. 121–123) for 600S162-33, 6"-deep 33-mil stud:

- Select RCKW5.5 connector, fastener pattern 3, with 1/2" anchor diameter and (6) #12 self-drilling screws, attaching to each stud @ 16" o.c.
- Allowable Moment = 4,670 in.-lb. > 2,389 in.-lb. **OK**
- Assembly Rotational Stiffness, $\beta = 304,000 \text{ in.-lb. / rad.}$ for RCKW5.5 connector at 38" wall height


Check Deflection at Required Moment:

$$\Delta_{req} = \left(\frac{(0.7)(M_{req})}{\beta}\right) L = \left(\frac{(0.7)(2,389 \text{ in.-lb.})}{304,000 \frac{\text{in.-lb.}}{\text{rad.}}}\right) 38 \text{ in.} = 0.209 \text{ in.}$$

Note: Per IBC Table 1604.3 footnote f, 0.42 factor can be used to calculate deflections for components and cladding wind loads for LRFD loads. ASD load conversion is 0.7.

Allowable Deflection:

$$\Delta_{allow} = \frac{2L}{240} = \frac{2(38 \text{ in.})}{240} = 0.317 \text{ in.} > 0.209 \text{ in.} \text{ **OK**}$$



Select Anchorage:

Normal-weight concrete with $f'_c = 3,000 \text{ psi}$
Table 2 (p. 129–130) — Cracked Concrete, Wind and Seismic
in SDC A & B

(1) Titen HD® with 3 1/4" embedment and 3" edge

$$F_{4req} = 39.7 * 38 / 12 = 125.7 \text{ lb.}$$

$$M_{req} = 2,389 \text{ in.-lb.}$$

$$F_{4all} = 930 * 0.86 = 799.8 \text{ lb.}$$

$$M_{all} = 3,525 * 0.86 = 3,031 \text{ in.-lb.}$$

***Note:** 0.86 comes from note 11, Table 2 (p. 131)
(3,000 psi concrete)

$$F_{4req} / F_{4all} = 125.7 / 799.8 = 0.16 < 1 \text{ **OK**}$$

$$M_{req} / M_{all} = 2,389 / 3,031 = 0.79 < 1 \text{ **OK**}$$

$$\text{Interaction} = 0.16 + 0.79 = 0.95 < 1.2 \text{ **OK**}$$



Computer-Assisted Design Note:

Please use kneewall module in
Simpson Strong-Tie® CFS Designer™

RCKW™ Kneewall Connector

Example #2: High Interior Half-Wall — Concrete Slab, No Edge, Two Anchor

Given:

- 2024 IBC (ASCE7-22) and AISI S100-16
- The top track 600T125-54 (50 ksi) spans between 600S162-54 (50 ksi) studs @ spacing, $S = 32"$ o.c. supported at the base
- 6" drywall studs at 16" o.c. as infill between the bottom and top track
- Wall height, $L = 48"$ -tall studs
- Design Load: $w = 50$ plf or $P = 200$ lb. concentrated load for guard or handrail applications in accordance with Section 4.5.1 of ASCE (Ref. IBC 1607.9.1 and 1607.9.1.1)
- Deflection Limit, $\Delta_{\text{allow}} = L/120$ (Ref. IBC Table 1604.3)
- 4,000 psi NWC, uncracked A & B, no edge, 5" concrete thickness

Calculations:

Design criteria #1 for linear load of 50 lb./ft.

Determine Required Concentrated Load, P_{req} :

$$P = (w)(S) = (50 \text{ plf})(32 \text{ in.}) \left(\frac{1 \text{ ft.}}{12 \text{ in.}} \right) = 133.3 \text{ lb.}$$

Determine Required Moment, M_{req} :

$$M_{\text{req}} = (P_{\text{req}})(L) = (133.3 \text{ lb.})(48 \text{ in.}) = 6,400 \text{ in.-lb.}$$

Design criteria #2 for concentrated load of 200 lb.

Note: From a 3D structural analysis with the 200 lb. concentrated load at the end stud, a continuous top track distributes some load to adjacent studs so that the worst-case moment is $M_{\text{req(max)}} = 7,513 \text{ in.-lb.}$ and maximum shear is $V_{\text{req(max)}} = 157 \text{ lb.}$ as indicated in the illustration.

From Table 1 (p. 121–123) for 600S162-54, 6"-deep, 54-mil stud:

- Select a RCKW5.5 connector, screw pattern 3B with (6) #12 self-drilling screws and (2) 1/2"-diameter anchors
- Allowable Moment = 9,995 in.-lb. > 6,400 in.-lb. (for linear load) **OK**
- Allowable Moment = 9,995 in.-lb. > 7,513 in.-lb. (for concentrated load) **OK**
- Connector Rotational Stiffness $\beta_c = 651,000 \text{ in.-lb. / rad.}$

Check Deflection for Design Criteria #1 at Required Load:

Determine Stud Deflection, Δ_s , at $P_{\text{req}} = 133.3 \text{ lb.}$


$$\Delta_s = \frac{P_{\text{req}} L^3}{3EI_{xe}} = \left(\frac{(133.3 \text{ lb.})(48 \text{ in.})^3}{3(29,500,000 \text{ psi})(2.86 \text{ in.}^4)} \right) = 0.058 \text{ in.}$$

Note: Effective moment of inertia for a 600S162-54 stud is $I_{xe} = 2.86 \text{ in.}^4$

Determine Connector Deflection, Δ_c , at $M_{\text{req}} = 6,400 \text{ in.-lb.}$ by utilizing the Connector Rotational Stiffness, $\beta_c = 651,000 \text{ in.-lb. / rad.}$ for RCKW5.5.

$$\Delta_c = \frac{M_{\text{req}} L}{\beta_c} = \frac{6,400 \text{ in.-lb.}}{651,000 \frac{\text{in.-lb.}}{\text{rad.}}} (48 \text{ in.}) = 0.472 \text{ in.}$$

Note: The Connector Rotational Stiffness may be used for any wall height; the designer must consider member deflection due to bending in the stud member. See footnote 10 of Table 1 (p. 123).



RCKW5.5 Installation on Concrete

RCKW™ Kneewall Connector

Example #2: High Interior Half-Wall — Concrete Slab, No Edge, Two Anchor (cont.)

Total Deflection is the sum of the Stud Deflection and the Connector Deflection.

$$\Delta_{total} = \Delta_s + \Delta_c = 0.058 \text{ in.} + 0.472 \text{ in.} = 0.53 \text{ in.}$$

Allowable Deflection:

$$\Delta_{allow} = \frac{2L}{120} = \frac{(2)(48 \text{ in.})}{120} = 0.800 \text{ in.} > 0.53 \text{ in.} \text{ OK}$$

Check Deflection for Design Criteria #2 at Required Load:

Determine Stud Deflection, Δ_s , at $M_{req(max)} = 7,513 \text{ in.-lb.}$ from concentrated load.

$$\Delta_s = \frac{M_{req}L^2}{3EI_{ke}} = \left(\frac{(7,513 \text{ in.-lb.})(48 \text{ in.})^2}{3(29,500,000 \text{ psi})(2.86 \text{ in.}^4)} \right) = 0.068 \text{ in.}$$

Determine Connector Deflection, Δ_c , at $M_{req(max)} = 7,513 \text{ in.-lb.}$ by utilizing the Connector Rotational Stiffness, $\beta_c = 651,000 \text{ in.-lb. / rad.}$ for RCKW5.5.

$$\Delta_c = \frac{M_{req(max)} L}{\beta_c} = \frac{7,513 \text{ in.-lb.}}{651,000 \frac{\text{in.-lb.}}{\text{rad.}}} (48 \text{ in.}) = 0.554 \text{ in.}$$

Total Deflection is the sum of Stud Deflection and Connector Deflection.

$$\Delta_{total} = \Delta_s + \Delta_c = 0.068 \text{ in.} + 0.554 \text{ in.} = 0.622 \text{ in.}$$

Allowable Deflection:

$$\Delta_{allow} = \frac{2L}{120} = \frac{(2)(48 \text{ in.})}{120} = 0.800 \text{ in.} > 0.622 \text{ in.} \text{ OK}$$

Select Anchorage:

Normal-weight concrete with $f'_c = 4,000 \text{ psi}$

Table 2 (p. 129–130) — Uncracked Concrete Wind and Seismic in SDC A & B (2) ½"-diameter Titen HD® with 3¼" embedment

$F_{4req} = 157 \text{ lb.}$

$F_{4all} = 3,765 \text{ lb.}$ Table 2 (p. 129–130) two anchors assumed to act in shear with no edge condition

$F_{4req}/F_{4all} = 157 \text{ lb.}/3,765 \text{ lb.} = 0.04 < 1 \text{ OK}$

$M_{req(max)} = 7,513 \text{ in.-lb.}$

$M_{req} = 10,800 \text{ in.-lb.}$ Table 2 (p. 129–130)

$M_{req(max)}/M_{all} = 7,513 \text{ in.-lb.} / 10,280 \text{ in.-lb.} = 0.73 < 1 \text{ OK}$

Interaction = $0.04 + 0.73 = 0.77 < 1.2 \text{ OK}$

Note: Per ASCE Section 4.5.1, for handrail and guardrail systems, there is no need to apply the 50 plf linear load and the 200 lb. concentrated load concurrently. Example #2 demonstrates the design for both loading cases, and the outermost anchored stud governs when using the 200 lb. concentrated load.



Computer-Assisted Design Note:

Please use kneewall module in Simpson Strong-Tie® CFS Designer™.




Figure 1
One Anchor




Figure 2
Two Anchors

Table 2: RCKW Allowable Anchorage Loads — Concrete Applications

Model No.	Min. Anchor Edge Distance (in.)	Type of Concrete	Anchor Type	Nominal Embedment Depth, h _{nom} (in.)	Minimum Concrete Thickness, h _{min} (in.)	Uncracked 4,000 psi Concrete			Cracked 4,000 psi Concrete					
						Wind and SDC A & B			Wind and SDC A & B			SDC C-F		
						Allowable			Allowable			Allowable		
						Moment M (in.-lb.)	Tension F ₂ (lb.)	Shear F ₄ (lb.)	Moment M (in.-lb.)	Tension F ₂ (lb.)	Shear F ₄ (lb.)	Moment M (in.-lb.)	Tension F ₂ (lb.)	Shear F ₄ (lb.)
RCKW3 or RCKW3+RCKW3S	1 7/8	SLWC	(1) 1/2"-dia. Titen HD®	3 1/4	5	1,170	670	410	850	490	295	305	175	135
				3 3/4	6	1,295	745	425	935	535	305	335	190	140
		NWC	(1) 1/2"-dia. Titen HD	3 1/4	5	1,680	965	605	1,230	705	430	445	255	200
				3 3/4	6	1,865	1,070	625	1,350	775	445	495	285	210
	No edge	SLWC	(1) 1/2"-dia. Titen HD	3 1/4	5	2,005	1,150	1,560	1,450	835	1,105	530	305	515
				3 3/4	6	2,515	1,445	2,685	1,840	1,055	2,465	680	390	805
		NWC	(1) 1/2"-dia. Strong-Bolt® 2	3 3/8	6	2,395	1,375	2,820	1,755	1,010	2,820	645	370	1,185
				(1) 1/2"-dia. Titen HD	3 1/4	5	2,825	1,625	2,295	2,080	1,195	1,625	770	445
			(1) 1/2"-dia. Titen HD	3 3/4	6	3,500	2,010	2,685	2,610	1,500	2,685	980	565	805
				(1) 1/2"-dia. Strong-Bolt 2	3 3/8	6	3,340	1,920	2,820	2,490	1,430	2,820	935	535
RCKW3D or RCKW3D+RCKW3DS	6	NWC	(2) 1/2"-dia. Titen HD	3 1/4	5	4,955	2,005	2,060	3,590	1,495	1,470	1,300	565	685
				3 3/4	6	4,955	2,005	2,260	3,590	1,495	1,615	1,300	565	755
	No edge	NWC	(2) 1/2"-dia. Titen HD	3 1/4	5	4,955	2,440	3,765	3,590	1,845	2,665	1,300	710	1,245
				3 3/4	6	6,245	2,805	5,370	4,555	2,155	5,370	1,660	850	1,610

Table continued on next page.

RCKW™ Kneewall Connector

Table 2: RCKW Allowable Anchorage Loads — Concrete Applications (cont.)


Model No.	Min. Anchor Edge Distance (in.)	Type of Concrete	Anchor Type	Nominal Embedment Depth, h _{nom} (in.)	Minimum Concrete Thickness, h _{min} (in.)	Uncracked 4,000 psi Concrete			Cracked 4,000 psi Concrete						
						Wind and SDC A & B			Wind and SDC A & B			SDC C-F			
						Allowable			Allowable			Allowable			
						Moment M (in.-lb.)	Tension F ₂ (lb.)	Shear F ₄ (lb.)	Moment M (in.-lb.)	Tension F ₂ (lb.)	Shear F ₄ (lb.)	Moment M (in.-lb.)	Tension F ₂ (lb.)	Shear F ₄ (lb.)	
RCKW5.5 or RCKW5.5+RCKW5.5S	3	SLWC	(1) ½"-dia. Titen HD®	3¼	5	3,360	1,055	815	2,435	765	635	870	275	295	
				3¾	6	3,855	1,210	915	2,770	870	655	995	310	305	
		NWC	(1) ½"-dia. Titen HD	3¼	5	4,845	1,520	1,305	3,525	1,105	930	1,275	400	435	
				3¾	6	5,535	1,735	1,350	4,015	1,260	965	1,450	455	450	
	No edge	SLWC	(1) ½"-dia. Titen HD	3¼	5	3,815	1,195	1,560	2,735	855	1,105	980	305	515	
				3¾	6	4,845	1,520	2,685	3,490	1,095	2,465	1,260	395	805	
		NWC	(1) ½"-dia. Titen HD	3¼	5	5,485	1,720	2,295	3,965	1,245	1,625	1,435	450	760	
				3¾	6	6,935	2,175	2,685	5,040	1,580	2,685	1,830	575	805	
			(1) ½"-dia. Strong-Bolt 2	3¾	6	6,585	2,065	2,820	4,795	1,505	2,820	1,740	545	1,185	
				(2) ¾"-dia. Titen HD	2½	4" slab and ¾" top of metal deck	4,460	1,430	1,020	2,060	700	725	725	250	335
	NWC	(2) ¾"-dia. Strong-Bolt 2	2¼	4	4,360	1,440	700	3,070	1,035	700	1,095	370	330		
			(2) ¾"-dia. Titen HD	2½	4" slab and ¾" top of metal deck	6,505	2,050	1,500	3,020	1,015	1,065	1,070	360	480	
	SLWC	(2) ½"-dia. Titen HD	3¼	5	7,080	1,900	2,560	5,040	1,380	1,815	1,790	500	845		
			3¾	6	9,040	2,265	5,370	6,460	1,650	4,380	2,305	600	1,610		
	NWC	(2) ½"-dia. Strong-Bolt 2	3¾	6	8,570	2,720	5,645	6,145	2,000	5,500	2,185	735	2,225		
			(2) ½"-dia. Titen HD	3¼	5	10,280	2,700	3,765	7,365	1,975	2,665	2,625	725	1,245	
		(2) ½"-dia. Strong-Bolt 2	3¾	6	13,110	3,185	5,370	9,415	2,350	5,370	3,360	875	1,610		
			3¾	6	12,425	3,780	5,645	8,945	2,830	5,645	3,190	1,070	2,370		
	RCKW7.5 or RCKW7.5+RCKW5.5S	4	SLWC	(1) ½"-dia. Titen HD	3¼	5	5,265	1,210	1,245	3,760	865	890	1,340	310	415
					3¾	6	6,485	1,490	1,410	4,665	1,070	1,010	1,670	385	470
NWC			(1) ½"-dia. Strong-Bolt 2	3¾	6	5,145	1,180	1,465	4,580	1,050	1,050	1,635	375	490	
				(1) ½"-dia. Titen HD	3¼	5	7,615	1,750	1,830	5,475	1,260	1,310	1,965	450	610
No edge		SLWC	(1) ½"-dia. Titen HD	3¼	5	5,265	1,210	1,560	3,760	865	1,105	1,340	310	515	
				3¾	6	6,710	1,540	2,685	4,810	1,105	2,465	1,725	395	805	
		NWC	(1) ½"-dia. Strong-Bolt 2	3¾	6	6,365	1,460	2,820	4,580	1,050	2,820	1,635	375	1,185	
				(1) ½"-dia. Titen HD	3¼	5	7,615	1,750	2,295	5,475	1,260	1,625	1,965	450	760
			(1) ½"-dia. Strong-Bolt 2	3¾	6	9,680	2,225	2,685	6,985	1,605	2,685	2,510	575	805	
				3¾	6	9,180	2,110	2,820	6,640	1,525	2,820	2,385	550	1,185	
SLWC		(2) ¾"-dia. Titen HD	2½	4" slab and ¾" top of metal deck	5,365	1,450	1,020	2,475	700	725	870	250	335		
			(2) ¾"-dia. Strong-Bolt 2	2¼	4	5,245	1,460	700	3,690	1,045	700	1,315	370	330	
NWC		(2) ¾"-dia. Titen HD	2½	4" slab and ¾" top of metal deck	7,835	2,095	1,500	3,630	1,025	1,065	1,285	365	480		
			(2) ¾"-dia. Strong-Bolt 2	2¼	4	7,660	2,110	700	5,420	1,515	700	1,910	545	330	
		SLWC	(2) ½"-dia. Titen HD	3¼	5	8,530	1,940	2,560	6,065	1,400	1,815	2,150	500	845	
				3¾	6	10,905	2,320	5,370	7,780	1,675	4,380	2,770	600	1,610	
NWC		(2) ½"-dia. Strong-Bolt 2	3¾	6	10,335	2,805	5,645	7,400	2,040	5,500	2,625	740	2,225		
			(2) ½"-dia. Titen HD	3¼	5	12,410	2,780	3,765	8,875	2,020	2,665	3,155	730	1,245	
		(2) ½"-dia. Strong-Bolt 2	3¾	6	15,855	3,305	5,370	11,360	2,410	5,370	4,040	880	1,610		
			3¾	6	15,020	3,965	5,645	10,790	2,920	5,645	3,835	1,080	2,370		

See footnotes on p. 131.

RCKW™ Kneewall Connector

Table 2 Footnotes:

- Anchor Allowable Loads have been determined using ACI 318-19 Chapter 17 anchorage calculations with the minimum concrete compressive strength, f'_c , and slab thickness listed. Sand-Lightweight Concrete is abbreviated as 'SLWC', Normal-Weight Concrete is abbreviated as 'NWC'.
- Load values are for anchors based on ACI 318-19, assuming supplementary reinforcement not present, load factors from ACI 318-19 Section 5.3, no supplemental edge reinforcement, $\Psi_{c,V} = 1.0$ for cracked concrete and periodic special inspection. Reference ICC-ES or IAPMO-UES evaluation reports for further information.
- Allowable Stress Design (ASD) values were determined by multiplying calculated Strength Design values by a conversion factor, Alpha (α), of 0.7 for seismic loads and 0.6 for wind loads. ASD values for other load combinations may be determined using alternate conversion factors.
- End distances are assumed as $1.5 \times \text{Min. Edge Distance}$ in one direction and 'N/A' in the other direction. See figure on this page.
- Edge and end distances are assumed as 'N/A' in all directions at locations for (No Edge).
- Tabulated allowable ASD loads for Wind and SDC A & B are based on using wind conversion factors and may be increased by 1.17 for seismic SDC A & B only.
- Allowable loads have been divided by an Omega (Ω) seismic factor of 2.5 for brittle failure as required by ACI 318-19 Chapter 17, unless steel failure governs.
- Tabulated capacities are based on maximum allowable anchorage loads only. The capacity of the connection system shall be the minimum of the tabulated value and the RCKW allowable load value listed on p. 121–123.
- Tabulated loads in Table 2 are based on $f'_c = 4,000$ psi. For $f'_c = 3,000$ psi, use an adjustment factor of 0.86 for the blue-shaded values and 1.0 for all other values.
- For anchor subjected to both tension and shear loads, it shall be designed to satisfy following:
 - For $N_a / N_{al} \leq 0.2$, the full allowable load in shear is permitted.
 - For $V_a / V_{al} \leq 0.2$, the full allowable load in tension is permitted.
 - For all other cases: $N_a / N_{al} + V_a / V_{al} \leq 1.2$.
 where:
 N_a = Applied ASD tension load
 N_{al} = Allowable tension load from Table 2
 V_a = Applied ASD shear load
 V_{al} = Allowable shear load from Table 2.




RCKW™ Kneewall Connector

Rigid Connectors

Table 3: RCKW Allowable Loads — Steel Applications with Anchorage

Model No.	Framing Member Depth (in.)	Fastener to Structural Steel ²	Fastener to Stud ³	Framing Member Thickness mil (ga.)	Assembly Rotational Stiffness ^{6,8} β (in.-lb. / rad)	Connector Rotational Stiffness ^{7,8} β_c (in.-lb. / rad)	Allowable Load			Code Ref.
							Moment ^{4,5} M (in.-lb.)	Tension F_2 (lb.)	Shear F_4 (lb.)	
RCKW3	3.625	(2) #12	(4) #12	33 (20)	55	58	2,105	850	455	—
				43 (18)	73	76	2,570	1,170	745	
				54 (16)	87	91	2,690	1,170	1,115	
				68 (14)	87	91	2,690	1,170	1,115	
		(4) 3/16"–1" weld	(9) #12	33 (20)	209	250	3,815	1,310	620	
				43 (18)	269	322	5,215	1,710	795	
				54 (16)	331	395	7,930	2,220	1,120	
				68 (14)	405	484	7,930	2,410	1,120	
				33 (20)	199	209	5,165	1,245	650	
RCKW5.5	6.00	(4) #12	(6) #12	43 (18)	265	275	6,370	1,900	1,060	—
				54 (16)	265	275	6,430	2,000	1,295	
				68 (14)	265	275	6,430	2,000	1,295	
				33 (20)	758	820	4,855	1,660	665	
		(4) 3/16"–1" weld	(10) #12	43 (18)	833	888	8,445	2,165	1,035	
				54 (16)	1,483	1,628	13,455	2,980	1,390	
				68 (14)	1,685	1,833	16,515	2,980	1,390	
				33 (20)	456	483	7,030	965	655	
				43 (18)	571	603	9,595	1,950	1,135	
RCKW7.5	8.00	(6) #12	(6) #12	54 (16)	693	731	11,320	2,185	1,710	—
				68 (14)	693	731	11,320	2,185	1,710	
				33 (20)	776	804	8,705	1,730	795	
				43 (18)	1,020	1,070	10,915	2,255	1,200	
		(4) 3/16"–1" weld	(10) #12	54 (16)	1,732	1,852	19,940	2,625	1,695	
				68 (14)	1,822	1,930	22,555	2,665	1,695	

- For additional important information, see General Information and Notes on p. 28
- Designer is responsible for structural steel design.
- See illustrations for stud fastener patterns. For weld pattern to steel beam, see illustration below.
- Tabulated values are based on framing members with track and stud of the same thickness and #10 screws into each stud fange.
- Table based on (4) 3/16" thickness –1" length welds installed in minimum 3/16"-thick structural steel with $F_y = 36$ ksi.
- Tabulated moment values correspond to the maximum connector strength without consideration of serviceability. Designer must check out-of-plane deflections using tabulated Rotational Stiffness.
- Tabulated Assembly Rotational Stiffness is for walls at 38" tall.
- The tabulated Connector Rotational Stiffness is for any wall heights. The designer must consider member deflection due to bending in the stud.
- Per IBC 2015 Table 1604.3 footnote f, wind load is permitted to be taken as 0.42 times "component and cladding loads" for deflection checks.



C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

MSSC4.25KW and MSSC6.25KW Kneewall Connectors

MSSC connectors are designed to work in tandem with Simpson Strong-Tie® BP $\frac{1}{2}$ -3 bearing plates to provide solutions for moment-resisting kneewall lighter-duty applications.

Features:

- One simple custom hole pattern for each stud size simplifies specification and installation
- $\frac{3}{8}$ " diameter anchor bolt location enables easy tool access

Material: MSSC — 97 mil (50 ksi); BP — 229 mil (33 ksi)

Finish: MSSC — Galvanized (G90); BP — None


Installation:

- Use all specified fasteners/anchors
- Install BP $\frac{1}{2}$ -3 bearing plate over anchor leg of MSSC connectors as shown in the illustrations


Codes: See p. 15 for Code Reference Key Chart

Ordering Information:

Model No.	Ordering SKU	Package Quantity
MSSC4.25KW	MSSC4.25KW-KT20	Box of 20 connectors and 20 BP bearing plates
MSSC6.25KW	MSSC6.25KW-KT20	



**MSSC4.25KW
Fastener Pattern**



**MSSC6.25KW
Fastener Pattern**

MSSCKW Allowable Loads

Model No.	Connector Material Thickness mil (ga.)	L (in.)	Framing Member Depth (in.)	Fasteners ⁵		Stud Thickness mil (ga.)	Allowable Moment, M (in.-lb.) ¹	Anchor Tension at Allowable Moment (lb.) ²	Rotational Stiffness for Wind Deflection (in.-lb./rad.) ^{3,4}	Code Ref.
				Anchor Diameter (in.)	Stud					
MSSC4.25KW	97 (12)	4 $\frac{1}{4}$	6	$\frac{3}{8}$	(8) #10	33 (20)	3,135	1,610	64,800	IBC, FL, LA
						43 (18)	4,320	2,305 ⁵		
						54 (16)	5,830	3,300 ⁵		
MSSC6.25KW	97 (12)	6 $\frac{1}{4}$	8	$\frac{3}{8}$	(12) #10	33 (20)	3,845	1,290	110,350	IBC, FL, LA
						43 (18)	3,845	1,290		
						54 (16)	8,350	2,980 ⁵		

1. Tabulated values correspond to maximum connector strength without consideration of serviceability. Designer must check out-of-plane deflections using tabulated rotational stiffness.

2. Uplift may be linearly interpolated for design moment less than allowable. Designer is responsible for anchorage design.


3. Tabulated stiffness is applicable for walls up to 38" tall. For taller walls, the designer must consider additional deflection due to bending in the studs.

4. Per IBC 2015 Table 1604.3 footnote f, wind load is permitted to be taken as 0.42 times "component and cladding loads" for deflection checks.

For IBC 2009 and earlier, the factor is 0.7 instead of 0.42.

5. Tabulated allowable tension loads for the connectors with $\frac{3}{8}$ "-diameter anchor bolts require ASTM F3125 Grade A325 or ASTM A449 high-strength bolts. For A307 Grade A bolt, anchor tension load is limited to 2,200 lb.

6. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



Typical MSSCKW Installation

MSSC4.25KW and MSSC6.25KW Kneewall Connectors

Kneewall Connector Anchorage Solutions

Uncracked Concrete, Wind and SDC A & B ^{8,10}									
Model No.	Minimum Concrete Thickness (h _{min})	¾"-Diameter Simpson Strong-Tie Anchor Type	Nominal Embedment Depth (h _{nom}) (in.)	Allowable Moment, M (in.-lb.)					
				Edge of Slab ³			Center of Slab ⁴		
				SLWC	NWC		SLWC	NWC	
				3,000 psi	3,000 psi	4,000 psi	3,000 psi	3,000 psi	4,000 psi
MSSC4.25KW	4" or thicker	Strong Bolt [®] 2	2¼	—	—	—	1,350	1,985	2,295
		Titen HD [®]	2½	1,385	2,040	2,355	1,385	2,040	2,355
	6" or thicker	Strong Bolt 2	2⅞	—	—	—	1,715	2,520	2,910
		Titen HD	3¼	1,980	2,910	3,360	2,290	3,370	3,890
		ET-3G [®]	4	1,030	2,025	2,240	3,275	3,600	3,600
		AT-3G™	4	1,375	2,275	2,480	3,575	3,575	3,575
	Concrete thickness ≥ 9.5"	SET-3G	7½	955	1,875	2,075	3,600	3,600	3,600
		AT-3G	7½	1,200	2,350	2,415	3,575	3,575	3,575
MSSC6.25KW	4" or thicker	Strong Bolt 2	2¼	—	—	—	2,140	3,150	3,635
		Titen HD	2½	2,195	3,235	3,730	2,195	3,235	3,730
	6" or thicker	Strong Bolt 2	2⅞	—	—	—	2,720	4,000	4,615
		Titen HD	3¼	3,630	5,340	6,165	3,630	5,340	6,165
		SET-3G	4	2,115	4,145	4,585	5,190	5,705	5,705
		AT-3G	4	2,895	4,855	5,290	5,665	5,665	5,665
	Concrete thickness ≥ 9.5"	SET-3G	7½	1,960	3,840	4,245	5,705	5,705	5,705
		AT-3G	7½	2,520	4,945	5,090	5,665	5,665	5,665

See footnotes on p. 135.

Cracked Concrete, Wind and SDC A & B ^{8,10}									
Model No.	Minimum Concrete Thickness (h _{min})	¾"-Diameter Simpson Strong-Tie Anchor Type	Nominal Embedment Depth (h _{nom}) (in.)	Allowable Moment, M (in.-lb.)					
				Edge of Slab ³			Center of Slab ⁴		
				SLWC	NWC		SLWC	NWC	
				3,000 psi	3,000 psi	4,000 psi	3,000 psi	3,000 psi	4,000 psi
MSSC4.25KW	4" or thicker	Strong Bolt 2	2¼	—	—	—	950	1,400	1,615
		Titen HD	2½	635	930	1,075	635	930	1,075
	6" or thicker	Strong Bolt 2	2⅞	—	—	—	1,425	2,095	2,420
		Titen HD	3¼	1,385	2,040	2,355	1,385	2,040	2,355
		SET-3G	4	1,240	2,435	2,610	1,970	3,600	3,600
		AT-3G	4	1,015	1,995	2,050	1,755	3,440	3,540
	Concrete thickness ≥ 9.5"	SET-3G	7½	2,330	3,600	3,600	3,600	3,600	3,600
		AT-3G	7½	1,905	3,575	3,575	3,290	3,575	3,575
MSSC6.25KW	4" or thicker	Strong Bolt 2	2¼	—	—	—	1,510	2,220	2,560
		Titen HD	2½	1,005	1,480	1,705	1,005	1,480	1,705
	6" or thicker	Strong Bolt 2	2⅞	—	—	—	2,260	3,320	3,835
		Titen HD	3¼	2,195	3,235	3,730	2,195	3,235	3,730
		SET-3G	4	2,540	4,985	5,340	3,125	5,705	5,705
		AT-3G	4	2,140	4,195	4,315	2,780	5,455	5,615
	Concrete thickness ≥ 9.5"	SET-3G	7½	4,765	5,705	5,705	5,705	5,705	5,705
		AT-3G	7½	4,010	5,665	5,665	5,215	5,665	5,665

See footnotes on p. 135.

MSSC4.25KW and MSSC6.25KW Kneewall Connectors

Kneewall Connector Anchorage Solutions (cont.)

Cracked Concrete, SDC C-F ^{9,10}									
Model No.	Minimum Concrete Thickness (h _{min})	¾"-Diameter Simpson Strong-Tie® Anchor Type	Nominal Embedment Depth (h _{nom}) (in.)	Allowable Moment, M (in.-lb.)					
				Edge of Slab ³			Center of Slab ⁴		
				SLWC	NWC		SLWC	NWC	
				3,000 psi	3,000 psi	4,000 psi	3,000 psi	3,000 psi	4,000 psi
MSSC4.25KW	4" or thicker	Strong Bolt® 2	2¼	—	—	—	335	490	565
		Titen HD®	2½	220	325	375	220	325	375
	6" or thicker	Strong Bolt 2	2¾	—	—	—	500	735	845
		Titen HD	3¼	485	715	825	485	715	825
		SET-3G®	4	435	850	915	690	1,350	1,450
	Concrete thickness ≥ 9.5"	AT-3G™	4	340	660	680	585	1,145	1,175
SET-3G		7½	815	1,595	4,195	1,295	4,195	4,195	
MSSC6.25KW	4" or thicker	Strong Bolt 2	2¼	—	—	—	530	775	895
		Titen HD	2½	350	520	600	350	520	600
	6" or thicker	Strong Bolt 2	2¾	—	—	—	790	1,165	1,340
		Titen HD	3¼	770	1,130	1,305	770	1,130	1,305
		SET-3G	4	890	1,745	1,870	1,095	2,145	2,300
	Concrete thickness ≥ 9.5"	AT-3G	4	710	1,395	1,435	925	1,815	1,865
SET-3G		7½	1,670	6,655	6,655	2,050	6,655	6,655	
		AT-3G	7½	1,335	2,615	6,610	1,735	6,610	6,610

- Allowable Moments have been determined using ACI 318-19 Chapter 17 anchorage calculations with the minimum concrete compressive strength, f_c and slab thickness listed. Sand-Lightweight Concrete is abbreviated as 'SLWC', Normal-Weight Concrete is abbreviated as 'NWC'.
- Nominal Embedment Depth/Effective Embedment Depth relationships:
 - ¾" Titen HD in 4" concrete: $2.50" (h_{nom}) / 1.77" (h_{ef})$
 - ¾" Titen HD in 6" concrete: $3.25" (h_{nom}) / 2.40" (h_{ef})$
 - ¾" carbon steel Strong-Bolt 2 into 4" concrete: $2.25" (h_{nom}) / 1.875" (h_{ef})$
 - ¾" carbon steel Strong-Bolt 2 into 6" concrete: $2.875" (h_{nom}) / 2.5" (h_{ef})$
 - SET-3G or AT-3G adhesive with ¾" F1554 Gr. 36 all-thread rod in 6" concrete: $4.0" (h_{nom}) = 4" (h_{ef})$
 - SET-3G or AT-3G adhesive with ¾" F1554 Gr. 36 all-thread rod in 9.5" concrete: $7.5" (h_{nom}) = 7.5" (h_{ef})$
- At edge of slab, edge distances are assumed to be 3.0" and 4.0" (½ of stud width) as determined for 6" and 8" studs, respectively. 'End distances' are assumed as 1.5 x Min. Edge Distance in one direction and 'N/A' in the other direction. See figure on p. 133.
- At center of slab, edge and end distances are assumed as 'N/A' in all directions at locations away from edge of slab. See figure on p. 133.
- Load values are for a single anchor based on ACI 318-19, supplementary reinforcement not present, load factors from ACI 318-19 Section 5.3, no supplemental edge reinforcement, $\psi_{c,v} = 1.0$ for cracked concrete and periodic special inspection. Reference ICC-ES or IAPMO-UES evaluation reports for further information.
- Load values are based on a short-term temperature range of 160°F and 176°F for SET-3G and AT-3G. Long-term temperature range is assumed to be 110°F and 122°F for SET-3G and AT-3G. Dry hole conditions are assumed. Other conditions may be evaluated using Anchor Designer for Concrete software. See strongtie.com/software.
- Allowable Stress Design (ASD) values were determined by multiplying calculated LRFD capacities by a conversion factor, Alpha (α), of 0.7 for seismic loads and 0.6 for wind loads. ASD values for other load combinations may be determined using alternate conversion factors.
- Tabulated allowable ASD loads for Wind and SDC A & B are based on using wind conversion factors and may be increased by 1.17 for SDC A & B only.
- Allowable loads have been divided by an Omega (Ω) seismic factor of 2.5 for brittle failure as required by ACI 318-19 Chapter 17, unless steel failure governs.
- Tabulated allowable moments are for MSSC Kneewall Connectors attached to studs with 54 (16) mil (ga.) thickness. Allowable moment may be increased for MSSC Kneewall Connectors attached to studs with 33 (20) or 43 (18) mil (ga.) thickness by multiplying by a factor of 1.06 for both MSSC4.25KW and MSSC6.25KW.
- Tabulated capacities assume lateral force applied at height of 38" above concrete. Tabulated capacities are based on maximum allowable anchorage loads only. The capacity of the connection system shall be the minimum of the tabulated value and the allowable load value from the MSSCKW Connectors: Allowable Load Tables.

PHC™ Panel Hoist Clip

The PHC panel hoist clip allows easier installation and lifting of wall panels on the job and at assembly sites. The PHC clip features a small profile design to fit inside holes as small as 1.5". Contractors can either drill holes in the track onsite or have the track manufactured with holes for easier installation of the clip through the top track. The rolled edges and rolled hoist-edge-hole provide greater strength and give the capacity needed for heavy panel projects. Maximum and minimum screw patterns give you options for heavier or lighter load needs. The PHC hoist clip has been assembly tested for tension and panel pick up, providing an increased level of safety for panelizers, installers and engineers.

Features:

- Small profile to allow for easy installation through the top track
- Greater top track strength with reduced opening size required for hoist clip to fit through top track
- Rolled stiffener for increased strength across the entire length of clip
- Rolled hoist-edge-hole for increased strength and smooth mounting edge
- Screw pattern options allow for varying load needs; fill round holes for minimum loads, or fill round holes and triangular holes for maximum loads
- Chamfered top corners and minimized distance of material above hoist hole allows for the lifting device to slide freely without getting stuck
- Assembly tested for tension and panel pick up at different angles for attachment to stud web
- Optional panel hoist clip cover (PHC-C) available to cover track hole and create a tight connector fit for the concrete pour when embedding the installed hoist in concrete or other hole cover needs

Material: PHC12 — 97 mil (12 ga.), 50 ksi;
PHC-C — 33 mil (20 ga.)


Finish: Galvanized (G90)

Installation: Use all specified fasteners/anchors. One time use.



Codes: Testing performed in accordance with ICC-ES AC261. Visit strongtie.com for the latest load values and testing information.

Ordering Information:

Model No.	Ordering SKU	Package Quantity
PHC12	PHC12	50
PHC-C	PHC-C	50




PHC-C
Panel Hoist Clip Cover
(for concrete pour or other hole cover needs, sold separately)




PHC12
Panel Hoist Clip

PHC™ Panel Hoist Clip




F2 Tension Load




F4 Flat Panel Pickup

PHC Allowable Loads per Clip (lb.)

Model No.	No. of #10 Screws to Framing	Stud Thickness mil (ga.)	PHC12 Attach to Stud Web			
			Tension Load F ₂		Flat Panel Pickup F ₄	
			θ = 45°	θ = 75° to 90°	θ = 45°	θ = 75° to 90°
PHC12	5 (Light Pattern)	33 (20)	330	885	215	290
		43 (18)	435	1,315	320	375
		54 (16)	620	1,740	450	615
		68 (14)	780	1,930	570	775
		97 (12)	780	1,955	570	775
	8 (Medium pattern)	33 (20)	530	1,415	215	460
		43 (18)	695	2,105	335	600
		54 (16)	990	2,785	450	985
		68 (14)	1,250	3,220	570	1,240
		97 (12)	1,250	3,220	570	1,240
	12 (max. pattern)	33 (20)	795	2,120	215	690
		43 (18)	1,040	2,785	335	900
54 (16)		1,485	2,785	450	1,160	
68 (14)		1,875	3,220	570	1,405	
97 (12)		1,875	3,220	570	1,405	



Five-Screw Pattern




Eight-Screw Pattern





Twelve-Screw Pattern

1. For General Information and Notes, see General Information and Notes on p. 28.
2. Allowable loads are for clip and anchorage to stud.
3. Light pattern is screws as shown in Five-Screw Pattern. Medium pattern is screws to all round holes; maximum pattern is screws to round and triangle holes.
4. Linear interpolation is allowed for angles between 45° and 75°.
5. Tabulated values are based on 3½" to 8" framing members with track and stud of the same thickness and 2½" maximum diameter hole centered in the top track for lifting devices.
6. Lifting devices should be connected to the PHC12 with a closed-loop attachment of sufficient strength to carry the allowable load.
7. The listed allowable tension load is the allowable vertical load of the hoist clip (not the allowable load in the direction of force).



Incorrect Loading

To prevent unintended eccentric loading, be sure to load the PHC clip with the force directly inline with the PHC hole, pulling from the top only without twisting the clip.



PHC Attached to Stud Web

SUBH Bridging Connectors



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

Simpson Strong-Tie® SUBH and MSUBH wall stud bridging connectors for cold-formed steel (CFS) framing offer a compact profile that allows standard 1½" studs to be sistered directly against adjacent studs. The LSUBH connector provides the same installation benefits of the SUBH/MSUBH connectors, and is suitable for many wind- and load-bearing situations where the load demand is light to moderate. Many applications require only one screw, greatly reducing labor costs and increasing productivity.

Features:

- Tested to include stud-web strength and stiffness in the tabulated design values
- Design values ensure compliance with AISI S100 Sections C2.2.1 and C2.3 for axially and laterally-loaded studs
- Flexible design solutions for web thicknesses of 33 mil (20 ga.) through 97 mil (12 ga.) and stud sizes from 3¾" to 8"
- SUBH and LSUBH accommodates single studs 33 mil (20 ga.) to 54 mil (16 ga.)
- MSUBH accommodates single studs 54 mil (16 ga.) to 97 mil (12 ga.) and back-to-back built-up members ranging from 33 mil (20 ga.) to 54 mil (16 ga.)

Material: LSUBH3.25 — 33 mil (20 ga.); SUBH3.25 — 43 mil (18 ga.); MSUBH3.25 — 68 mil (14 ga.)

Finish: Galvanized (G90)

Installation:

- See pp. 139–141

Codes: See p. 15 for Code Reference Key Chart

Ordering Information:

Model No.	Ordering SKU	Package Quantity
LSUBH3.25	LSUBH3.25-R150	150
SUBH3.25	SUBH3.25-R150	150
MSUBH3.25	MSUBH3.25-R100	100

Compact Geometry

Facilitates efficient installation in industry-standard 1.5" web knockouts

Contoured Flanges

Fits snug over industry-standard 1.5" wide u-channels

Web Slots


Offers strong rotational resistance without the use of screws

Embossments

Enhance connector strength and stiffness

Dual Installation Options

For maximum design and application flexibility




SUBH3.25


(LSUBH3.25 and MSUBH3.25 similar)
US Patent. See strongtie.com/patent.

SUBH Bridging Connectors


Installation Instructions




Step 1: With the u-channel in a stable, horizontal position, insert either end of the SUBH into the web knockout at approximately 45°.



Step 2: Rotate the SUBH into a horizontal position aligned with the u-channel so the slots engage the stud web.



Step 3: Slide the SUBH down over the u-channel flanges, ensuring that the connector and u-channel are fully seated.
(Note: For installations at slip track, the connector may be installed inverted — see next page.)




Step 4: Install the specified type and number of screws through the holes of the SUBH into the u-channel.


SUBH Bridging Connectors

Installation Details

Typical Orientations




1
Round Hole Near Side




2
Round Hole Far Side

Recommended Details at Built-Up Studs




1


(MSUBH only)



3




2



4

Recommended Detail at Slip Track




1


SUBH Bridging Connectors

Alternate and Optional U-Channel Bridging Installation Details at End Conditions

Recommended details for end-of-wall conditions, where knockout access is restricted, or where additional u-channel restraint is needed for load path considerations.



For End-of-Run Conditions, See SUBE on p. 148.



Consider Simpson Strong-Tie® SSC Clip for 2 and 3.

SUBH Bridging Connectors

How to Use Bridging Connector Allowable Load Table


The tabulated strength and stiffness values are for use with Sections C2.2.1 and C2.3 of the 2016 edition of AISI North American Specification for the Design of Cold-Formed Steel Structural Members (AISI S100-16) as follows:

Bracing Design for Laterally Loaded C-Studs

- Step 1: Calculate required bracing force for each flange using equation C2.2.1-3
- Step 2: Multiply result by stud depth to obtain torsional moment
- Step 3: Select connector with tabulated allowable torsional moment that exceeds torsional moment from Step 2 for the stud depth and gauge required

Bracing Design for Axially Loaded C-Studs

- Step 1: Calculate required brace strength using equation C2.3-1
- Step 2: Calculate required brace stiffness using equation C2.3-2a
- Step 3: Select connector with tabulated allowable brace strength that exceeds strength from Step 1 and tabulated brace stiffness that exceeds stiffness from Step 2 for the stud depth and gauge required



SUBH Bridge Clip Connector — Strength and Stiffness

Model No.	Stud Depth (in.)	Stud Thickness mils (ga.)	Laterally Loaded C-Stud		Axially Loaded C-Stud			Code Ref.	
			Allowable Torsional Moment ¹ (in.-lb.)		Allowable Brace Strength ¹ (lb.)		Brace Stiffness ² (lb./in.)		
			Min.	Max.	Min.	Max.	Min.		Max.
LSUBH3.25	3.50 or 3.625	33 (20)	200	310	145	260	4,050	4,225	IBC, FL, LA
		43 (18)	215	345	165	290	7,415	10,095	
		54 (16)	210	345	185	325	7,415	14,780	
SUBH3.25		33 (20)	320	345	230	370	2,790	3,680	
		43 (18)	355	430	255	420	5,130	6,435	
		54 (16)	420	455	290	475	5,130	6,690	
MSUBH3.25		54 (16)	550	800	435	630	5,560	7,470	
		68 (14)	640	860	485	695	10,055	12,785	
		97 (12)	670	860	515	770	17,255	23,295	
LSUBH3.25	6.00	33 (20)	210	310	115	130	1,010	1,185	
		43 (18)	235	365	145	265	1,695	2,560	
		54 (16)	245	365	170	305	1,695	3,365	
SUBH3.25		33 (20)	275	385	110	110	860	860	
		43 (18)	295	525	230	250	1,750	1,940	
		54 (16)	350	550	275	415	2,075	2,610	
MSUBH3.25		54 (16)	565	895	385	430	2,475	2,600	
		68 (14)	655	925	455	620	3,255	4,015	
		97 (12)	690	960	505	765	5,870	6,680	
LSUBH3.25	8.00	43 (18)	225	350	125	125	985	1,005	
		54 (16)	235	350	170	240	1,585	1,585	
SUBH3.25		43 (18)	255	570	190	190	885	885	
		54 (16)	325	605	250	300	1,385	1,470	
		54 (16)	545	890	270	270	1,455	1,460	
MSUBH3.25		68 (14)	635	925	435	455	2,110	2,110	
		97 (12)	665	955	545	545	4,040	4,040	
MSUBH3.25		10, 12	54 (16)	—	775	—	200	—	570

1. Allowable loads are for use when utilizing Allowable Stress Design methodology. For LRFD loads multiply the ASD tabulated values by 1.6.
 2. Brace stiffness is at 40% of ultimate load per test standard AISI S915-20. Tabulated values apply to both ASD and LRFD.
 3. Allowable loads consider bridging connection only. It is responsibility of the designer to verify the strength and serviceability of the framing members.
 4. Min. fastener quantity and tabulated values – fill round hole (one screw total); Max. fastener quantity and tabulated values – fill round and triangle holes (two screws total).
 5. For 4" and 5.5" stud depth, reference SUBH connector page at strongtie.com.


SUBH Design Tables

LSUBH — Maximum Vertical Spacing for Rows of U-Channel Bridging (ft.)

Stud Spacing (in.)	Stud Section	Stud Thickness mil (ga.)	Lateral Stud Pressure (psf)																					
			5		10		15		20		25		30		35		40		45		50			
			Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.		
16	362S162	33 (20)	8	8	8	8	8	8	8	6	8	5	8	4	6	—	5	—	5	—	4	—	4	
		43 (18)	8	8	8	8	8	8	7	8	5	8	4	7	4	6	—	5	—	5	—	5	—	4
		54 (16)	8	8	8	8	8	8	7	8	5	8	4	7	4	6	—	5	—	5	—	5	—	4
	362S200	33 (20)	8	8	8	8	6	8	5	8	4	6	—	5	—	4	—	4	—	4	—	—	—	—
		43 (18)	8	8	8	8	7	8	5	8	4	7	—	6	—	5	—	4	—	4	—	4	—	—
		54 (16)	8	8	8	8	7	8	5	8	4	7	—	6	—	5	—	4	—	4	—	4	—	—
	362S250	43 (18)	8	8	8	8	6	8	4	7	—	5	—	4	—	4	—	4	—	—	—	—	—	—
		54 (16)	8	8	8	8	5	8	4	7	—	5	—	4	—	4	—	4	—	—	—	—	—	—
	600S162	33 (20)	8	8	8	8	8	8	8	8	6	8	5	8	4	6	—	5	—	4	—	6	—	4
		43 (18)	8	8	8	8	8	8	8	8	7	8	6	8	5	8	4	6	—	5	—	4	—	5
		54 (16)	8	8	8	8	8	8	8	8	7	8	6	8	5	8	4	6	—	5	—	4	—	5
	600S200	33 (20)	8	8	8	8	8	8	6	8	4	7	4	6	—	5	—	4	—	4	—	—	—	—
		43 (18)	8	8	8	8	8	8	6	8	5	8	4	7	—	6	—	5	—	4	—	4	—	4
		54 (16)	8	8	8	8	8	8	7	8	5	8	4	7	4	6	—	5	—	4	—	4	—	4
	600S250	43 (18)	8	8	8	8	7	8	5	8	4	6	—	5	—	4	—	4	—	—	—	—	—	—
		54 (16)	8	8	8	8	7	8	5	8	4	6	—	5	—	4	—	4	—	—	—	—	—	—
	800S162	43 (18)	8	8	8	8	8	8	8	8	7	8	6	8	5	8	4	6	—	5	—	4	—	6
		54 (16)	8	8	8	8	8	8	8	8	8	7	8	6	8	5	7	4	6	—	5	—	4	6
	800S200	43 (18)	8	8	8	8	8	8	7	8	5	8	4	7	4	6	—	5	—	5	—	5	—	4
		54 (16)	8	8	8	8	8	8	7	8	6	8	5	7	4	6	—	5	—	5	—	5	—	4
	800S250	43 (18)	8	8	8	8	7	8	5	8	4	7	—	5	—	5	—	4	—	—	—	—	—	—
		54 (16)	8	8	8	8	8	8	6	8	4	7	4	6	—	5	—	4	—	4	—	4	—	—
	24	362S162	33 (20)	8	8	8	8	6	8	4	6	—	5	—	4	—	—	—	—	—	—	—	—	—
			43 (18)	8	8	8	8	6	8	4	7	—	6	—	5	—	4	—	—	—	—	—	—	—
54 (16)			8	8	8	8	6	8	4	7	—	6	—	5	—	4	—	—	—	—	—	—	—	
362S200		33 (20)	8	8	6	8	4	7	—	5	—	4	—	—	—	—	—	—	—	—	—	—	—	
		43 (18)	8	8	7	8	4	8	—	6	—	4	—	4	—	—	—	—	—	—	—	—	—	
		54 (16)	8	8	7	8	4	8	—	6	—	4	—	4	—	—	—	—	—	—	—	—	—	
362S250		43 (18)	8	8	6	8	4	6	—	4	—	—	—	—	—	—	—	—	—	—	—	—	—	
		54 (16)	8	8	5	8	—	6	—	4	—	—	—	—	—	—	—	—	—	—	—	—	—	
600S162		33 (20)	8	8	8	8	7	8	5	8	4	6	—	5	—	4	—	4	—	—	—	—	—	—
		43 (18)	8	8	8	8	8	8	6	8	4	7	4	6	—	5	—	4	—	—	—	—	—	
		54 (16)	8	8	8	8	8	8	6	8	5	7	4	6	—	5	—	4	—	—	—	—	—	
600S200		33 (20)	8	8	8	8	5	8	4	6	—	4	—	4	—	—	—	—	—	—	—	—	—	
		43 (18)	8	8	8	8	6	8	4	7	—	5	—	4	—	4	—	—	—	—	—	—	—	
		54 (16)	8	8	8	8	6	8	4	7	—	5	—	4	—	4	—	—	—	—	—	—	—	
600S250		43 (18)	8	8	7	8	4	7	—	5	—	4	—	—	—	—	—	—	—	—	—	—	—	
		54 (16)	8	8	7	8	5	7	—	5	—	4	—	—	—	—	—	—	—	—	—	—	—	
800S162		43 (18)	8	8	8	8	8	8	6	8	5	8	4	6	—	5	—	5	—	—	—	—	—	4
		54 (16)	8	8	8	8	8	8	7	8	5	8	4	7	4	6	—	5	—	—	—	—	—	4
800S200		43 (18)	8	8	8	8	6	8	4	7	—	6	—	5	—	4	—	—	—	—	—	—	—	—
		54 (16)	8	8	8	8	6	8	5	7	4	6	—	5	—	4	—	—	—	—	—	—	—	—
800S250		43 (18)	8	8	7	8	5	7	—	5	—	4	—	—	—	—	—	—	—	—	—	—	—	—
		54 (16)	8	8	8	8	5	8	4	6	—	4	—	4	—	—	—	—	—	—	—	—	—	—

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

1. See General Information and Notes on pp. 16–19 and 28.
2. Tabulated solutions are for ASD lateral pressure. Contact Simpson Strong-Tie for LRFD solutions.
3. Lateral pressure shall be determined based on load combinations of the applicable code. For designs in accordance with the 2009 IBC and earlier, wind pressures are at working stress level and may be used directly. For designs in accordance with the 2012 IBC and later, wind pressures are at strength level and must be multiplied by 0.6 for ASD load combinations.
4. "Min." designates a solution with the minimum number of fasteners ((1) #10 screw installed in round hole). "Max." designates a solution requiring the maximum number of fasteners ((2) #10 screws; fill both round and triangle holes). Blank areas designate conditions where the LSUBH does not offer a solution.



Bridging, Bracing and Backing


SUBH Design Tables

SUBH — Maximum Vertical Spacing for Rows of U-Channel Bridging (ft.)

Bridging, Bracing and Backing

Stud Spacing (in.)	Stud Section	Stud Thickness mil (ga.)	Lateral Stud Pressure (psf)																				
			5		10		15		20		25		30		35		40		45		50		
			Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	
16	362S162	33 (20)	8	8	8	8	8	8	8	8	8	8	8	6	7	5	6	5	5	4	4	4	4
		43 (18)	8	8	8	8	8	8	8	8	8	8	8	7	8	6	7	5	6	5	6	4	5
		54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	7	6	6	5	5
	362S200	33 (20)	8	8	8	8	8	8	7	8	6	6	5	5	4	4	—	4	—	—	—	—	—
		43 (18)	8	8	8	8	8	8	8	8	6	8	5	6	4	5	4	5	—	4	—	4	4
		54 (16)	8	8	8	8	8	8	8	8	8	8	6	7	5	6	5	5	4	4	4	4	4
	362S250	43 (18)	8	8	8	8	8	8	6	8	5	6	4	5	—	4	—	4	—	—	—	—	—
		54 (16)	8	8	8	8	8	8	8	8	6	7	5	5	4	5	4	4	—	—	—	—	—
	600S162	33 (20)	8	8	8	8	8	8	8	8	8	8	6	8	5	8	5	7	4	6	4	5	7
		43 (18)	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	4	8	4	8	7
		54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	5	8	8
	600S200	33 (20)	8	8	8	8	8	8	7	8	6	8	5	7	4	6	—	5	—	4	—	4	4
		43 (18)	8	8	8	8	8	8	8	8	6	8	5	8	4	8	4	7	—	6	—	6	5
		54 (16)	8	8	8	8	8	8	8	8	7	8	6	8	5	8	4	7	4	6	—	6	6
	600S250	43 (18)	8	8	8	8	8	6	8	5	8	4	7	—	6	—	5	—	5	—	5	—	4
		54 (16)	8	8	8	8	8	7	8	6	8	5	8	4	6	—	6	—	6	—	5	—	4
	800S162	43 (18)	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	4	8	4	8	8
		54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	6	8	6	8	8
	800S200	43 (18)	8	8	8	8	8	7	8	6	8	5	8	4	8	—	8	—	7	—	7	—	7
		54 (16)	8	8	8	8	8	8	8	8	8	8	6	8	5	8	5	8	4	8	4	8	7
	800S250	43 (18)	8	8	8	8	8	6	8	4	8	4	8	—	7	—	6	—	6	—	6	—	5
		54 (16)	8	8	8	8	8	7	8	6	8	5	8	4	8	—	7	—	6	—	6	—	5
	24	362S162	33 (20)	8	8	8	8	8	6	7	5	5	4	4	—	—	—	—	—	—	—	—	—
			43 (18)	8	8	8	8	8	7	8	6	7	5	6	4	5	—	4	—	4	—	4	—
54 (16)			8	8	8	8	8	8	8	8	7	7	6	6	5	5	4	4	4	4	4	—	—
362S200		33 (20)	8	8	8	8	6	7	5	5	4	4	—	—	—	—	—	—	—	—	—	—	—
		43 (18)	8	8	8	8	7	8	5	6	4	5	—	4	—	—	—	—	—	—	—	—	—
362S250		43 (18)	8	8	8	8	6	7	4	5	—	4	—	—	—	—	—	—	—	—	—	—	—
		54 (16)	8	8	8	8	7	7	5	5	4	4	—	—	—	—	—	—	—	—	—	—	—
600S162		33 (20)	8	8	8	8	8	6	8	5	7	4	6	—	5	—	4	—	4	—	4	—	—
		43 (18)	8	8	8	8	8	7	8	5	8	4	8	4	7	—	6	—	5	—	5	—	5
		54 (16)	8	8	8	8	8	8	8	7	8	5	8	5	7	4	6	—	6	—	6	—	5
600S200		33 (20)	8	8	8	8	6	8	5	7	4	5	—	4	—	4	—	—	—	—	—	—	—
		43 (18)	8	8	8	8	7	8	5	8	4	7	—	6	—	5	—	4	—	4	—	4	—
600S250		43 (18)	8	8	8	8	5	8	4	7	—	6	—	5	—	4	—	—	—	—	—	—	—
		54 (16)	8	8	8	8	6	8	5	8	4	6	—	5	—	4	—	4	—	—	—	—	—
800S162		43 (18)	8	8	8	8	8	7	8	5	8	4	8	4	8	—	7	—	7	—	7	—	6
		54 (16)	8	8	8	8	8	8	8	8	7	8	6	8	5	8	4	8	4	7	—	6	—
800S200		43 (18)	8	8	8	8	6	8	5	8	4	8	—	7	—	6	—	5	—	5	—	4	—
		54 (16)	8	8	8	8	8	8	6	8	5	8	4	8	—	7	—	6	—	5	—	5	—
800S250		43 (18)	8	8	8	8	5	8	4	8	—	7	—	6	—	5	—	4	—	4	—	—	—
		54 (16)	8	8	8	8	6	8	5	8	4	7	—	6	—	5	—	4	—	4	—	—	—

1. See General Information and Notes on pp. 16–19 and 28.
2. Tabulated solutions are for ASD lateral pressure. Contact Simpson Strong-Tie for LRFD solutions.
3. Lateral pressure shall be determined based on load combinations of the applicable code. For designs in accordance with the 2009 IBC and earlier, wind pressures are at working stress level and may be used directly. For designs in accordance with the 2012 IBC and later, wind pressures are at strength level and must be multiplied by 0.6 for ASD load combinations.
4. "Min." designates a solution with the minimum number of fasteners ((1) #10 screw installed in round hole). "Max." designates a solution requiring the maximum number of fasteners ((2) #10 screws; fill both round and triangle holes). Blank areas designate conditions where the SUBH does not offer a solution.



SUBH Design Tables


MSUBH — Maximum Vertical Spacing for Rows of U-Channel Bridging (ft.)

Stud Spacing (in.)	Stud Section	Stud Thickness mil (ga.)	Lateral Stud Pressure (psf)																				
			5		10		15		20		25		30		35		40		45		50		
			Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	
16	362S162	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	7	8	
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
	362S200	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	6	8	5	7
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	7	8	6	8
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8
	362S250	54 (16)	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	7	4	7	4	6
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	7	5	6	
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	6	7	5	6	
	600S162	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
	600S200	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	7	8	6	8	
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
	600S250	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	5	7
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	6	8	
	800S162	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
	800S200	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8
800S250	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	5	8		
	68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	6	8			
	97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	7	8	6	8		
1000S162	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
1000S200	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
1000S250	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
1200S162	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
1200S200	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
1200S250	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

Bridging, Bracing and Backing

1. See General Information and Notes on pp. 16–19 and 28.
2. Tabulated solutions are for ASD lateral pressure. Contact Simpson Strong-Tie for LRFD solutions.
3. Lateral pressure shall be determined based on load combinations of the applicable code. For designs in accordance with the 2009 IBC and earlier, wind pressures are at working stress level and may be used directly. For designs in accordance with the 2012 IBC and later, wind pressures are at strength level and must be multiplied by 0.6 for ASD load combinations.
4. "Min." designates a solution with the minimum number of fasteners ((1) #10 screw installed in round hole). "Max." designates a solution requiring the maximum number of fasteners ((2) #10 screws; fill both round and triangle holes). Blank areas designate conditions where the MSUBH does not offer a solution.




SUBH Design Tables

MSUBH — Maximum Vertical Spacing for Rows of U-Channel Bridging (ft.) (cont.)

Bridging, Bracing and Backing

Stud Spacing (in.)	Stud Section	Stud Thickness mil (ga.)	Lateral Stud Pressure (psf)																						
			5		10		15		20		25		30		35		40		45		50				
			Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.			
24	362S162	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	5	7	4	6	
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	6	8	5	7	
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	6	8	5	7
	362S200	54 (16)	8	8	8	8	8	8	8	8	8	7	8	6	8	5	7	4	6	4	5	—	—	5	
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	7	4	6	4	6	4	5
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	7	5	7	5	6	4	5
	362S250	54 (16)	8	8	8	8	8	8	8	7	8	5	8	4	7	4	6	—	5	—	4	—	—	4	
		68 (14)	8	8	8	8	8	8	8	8	6	8	5	7	4	6	4	5	—	5	—	—	—	4	
		97 (12)	8	8	8	8	8	8	8	8	7	8	6	7	5	6	4	5	4	5	—	—	—	4	
	600S162	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	8	
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8
	600S200	54 (16)	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	4	7	4	7	4	6	
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	7	4	6	5	7	
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	5	8	5	7	
	600S250	54 (16)	8	8	8	8	8	8	8	8	6	8	5	8	4	7	4	6	—	5	—	—	—	5	
		68 (14)	8	8	8	8	8	8	8	8	7	8	6	8	5	7	4	6	4	6	—	—	—	5	
		97 (12)	8	8	8	8	8	8	8	8	8	6	8	5	8	5	7	4	6	4	6	4	6	5	
	800S162	54 (16)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	6	8	6	8	
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8
	800S200	54 (16)	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	5	8	4	7	4	6	
		68 (14)	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	5	8	5	7	
		97 (12)	8	8	8	8	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	8	5	7	
800S250	54 (16)	8	8	8	8	8	8	8	8	7	8	5	8	5	8	4	7	—	6	—	—	—	5		
	68 (14)	8	8	8	8	8	8	8	8	8	8	6	8	5	8	5	7	4	6	4	6	4	6		
	97 (12)	8	8	8	8	8	8	8	8	8	8	7	8	6	8	5	7	4	7	4	7	4	6		
1000S162	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
1000S200	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7		
1000S250	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7	—	6	—	—	—	5		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7	—	6	—	—	—	5		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7	—	6	—	—	—	5		
1200S162	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
1200S200	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	8		
1200S250	54 (16)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7	—	6	—	—	—	6		
	68 (14)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7	—	6	—	—	—	6		
	97 (12)	—	8	—	8	—	8	—	8	—	8	—	8	—	8	—	7	—	7	—	—	—	6		

1. See General Information and Notes on pp. 16–19 and 28.
2. Tabulated solutions are for ASD lateral pressure. Contact Simpson Strong-Tie for LRFD solutions.
3. Lateral pressure shall be determined based on load combinations of the applicable code. For designs in accordance with the 2009 IBC and earlier, wind pressures are at working stress level and may be used directly. For designs in accordance with the 2012 IBC and later, wind pressures are at strength level and must be multiplied by 0.6 for ASD load combinations.
4. "Min." designates a solution with the minimum number of fasteners ((1) #10 screw installed in round hole). "Max." designates a solution requiring the maximum number of fasteners ((2) #10 screws; fill both round and triangle holes). Blank areas designate conditions where the MSUBH does not offer a solution.



SUBH Bridging Connectors

Example #1: Curtain-Wall Stud

Given

- 2024 IBC (ASCE7-22) and AISI S100-16
- 600S162-43 (33 ksi) studs at 24" o.c.
- 10'-tall studs with mid-point bracing (5' o.c.)
- Wind design pressure = 41 psf

Select Connector Using Design Table (p. 144)

ASD wind pressure:

$$p = (0.6)(41 \text{ psf}) = 24.6 \text{ psf}$$


Note: 2024 IBC load combinations for ASD include a factor of 0.6 for wind loads.

For 600S162-43 stud with SUBH3.25 connector, and 25 psf wind pressure with 5' bracing distance:

➔ SUBH3.25 with Min. fasteners **OK**

Notes

1. Only lateral load has been included for clarity. Design of curtain-wall studs should consider load combinations with vertical load in accordance with the applicable building code (see Example #2).
2. Bridging connector may also be designed using Allowable Loads table on p. 142 (see Example #2).



Example #2: Exterior Bearing-Wall Stud

Given

- 2024 IBC (ASCE7-22) and AISI S100-16
- 600S162-54 (50 ksi) studs at 24" o.c., 10' tall
Mid-point bracing (5' o.c.)
Required axial stud strength, $P_{ra} = 2,200 \text{ lb.}$
Distance from shear center to mid-plane of web, $m = 0.663''$ (AISI Manual, Table I-2)
- Wind design pressure = 34 psf

Axially-Loaded Stud Design

Required brace strength (AISI S100 Eq. C2.3-1):

$$P_{br,1} = 0.01P_{ra} = (0.01)(2,200 \text{ lb.}) = 22 \text{ lb.}$$

Required brace stiffness (AISI S100 Eq. C2.3-2a):

$$\beta_{rb} = \{2[4 - (2/n)]/L_b\} \Omega P_{ra} = \{2[4 - (2/1)]/60 \text{ in.}\} (2)(2,200) = 294 \text{ lb./in.}$$

From Allowable Loads table (p. 142) for 6"-deep 54-mil stud:

➔ Select SUBH3.25 with Min. fasteners

$$\text{Allowable brace strength} = 275 \text{ lb.} > 22 \text{ lb.} \quad \mathbf{OK}$$

$$\text{Brace stiffness} = 2,075 \text{ lb./in.} > 294 \text{ lb./in.} \quad \mathbf{OK}$$

Laterally-Loaded Stud Design

Design load tributary to a single connector:

$$W = (0.6)(34 \text{ psf})(2 \text{ ft.})(5 \text{ ft.}) = 204 \text{ lb.}$$

Note: 2024 IBC load combinations for ASD include a factor of 0.6 for wind loads.

Required flange force (AISI S100 Eq. C2.2.1-3):

$$P_{L1} = -P_{L2} = 1.5(m/d)W = (1.5)(0.663 \text{ in.}/6 \text{ in.})(204 \text{ lb.}) = 33.8 \text{ lb.}$$

Torsional moment:

$$M_z = P_{L1}d = -P_{L2}d = (33.8 \text{ lb.})(6 \text{ in.}) = 203 \text{ in.-lb.}$$

From Allowable Loads table (p. 142) for 6"-deep 54-mil stud:

➔ Select SUBH3.25 with Min. fasteners

$$\text{Allowable torsional moment} = 350 \text{ in.-lb.} > 203 \text{ in.-lb.} \quad \mathbf{OK}$$

Combined-Loading Check

$$(P_{br,1}/\text{Allowable brace strength}) + (M_z/\text{Allowable torsional moment}) = (22 \text{ lb.}/275 \text{ lb.}) + (203 \text{ in.-lb.}/350 \text{ in.-lb.}) = 0.66 < 1.0 \quad \mathbf{OK}$$

SUBE Bridging Connectors



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

Simpson Strong-Tie® SUBE wall-stud bridging connector for cold-formed steel (CFS) is designed to connect cold-rolled channel (CRC) at the end of a wall or single stud jamb condition, or at the ends of panel walls, curtain walls or load-bearing conditions.

The connector is installed on the open side of the stud with screws to the stud lips, effectively limiting drywall buildup and creating a safer working environment as sharp-point screw perforations through the web are eliminated. Additionally, the SUBE does not require any special tools or clamping during installation as it features outer flanges that enable the connector to fit snugly over the open side of the stud. By eliminating the potential for drywall bulge and on-site safety issues, you will save time and improve efficiencies on your jobsite.

Features:

- Tested to include stud-web strength and stiffness in the tabulated design values
- Design values ensure compliance with AISI S100 Sections C2.2.1 and C2.3 for axially- and laterally-loaded studs
- Flexible design solutions for web thicknesses of 33 mil (20 ga.) through 97 mil (12 ga.) and stud sizes of 3½" and 6"

Material: 54 mil (16 ga.) 50 ksi


Finish: Galvanized (G90)

Codes: Testing performed in accordance with ICC-ES AC261. Visit strongtie.com for the latest load values and testing information.


Material: SUBE is connected to the open face of the stud and is attached to lip of stud with (2) #10 screws. Fasten u-channel to clip with (2) #10 screws.

Ordering Information:


Model No.	Ordering SKU	Bucket Quantity
SUBE362	SUBE362-R100	100
SUBE6	SUBE6-R50	50



SUBE Use at The End of Run or Jamb.
SUBH Used at Typical Stud.



SUBE362 Bridging Connector



SUBE6 Bridging Connector

SUBE Bridging Connectors

SUBE Bridging Clip End Connector — Strength and Stiffness

Model No.	Stud Depth (in.)	Stud Thickness mil (ga.)	Fasteners		Laterally-Loaded C-Stud	Axially-Loaded C-Stud	
			Stud	U-Channel	Allowable Torsional Moment ¹ (in.-lb.)	Allowable Brace Strength (lb.)	Brace Stiffness ² (lb./in.)
SUBE362	3.625	33 (20)	(2) #10	(2) #10	375	125	2,310
		43 (18)			400	160	2,975
		54 (16)			560	325	2,975
		68 (14)			595	410	3,105
		97 (12)			595	410	3,105
SUBE6	6	33 (20)	(2) #10	(2) #10	495	135	1,305
		43 (18)			575	175	1,685
		54 (16)			880	365	3,180
		68 (14)			880	455	3,920
		97 (12)			880	455	3,920

1. Allowable loads are for use when utilizing Allowable Stress Design (ASD) methodology. For Load and Resistance Factor Design (LRFD) loads, multiply the ASD tabulated values by 1.6.

2. Brace stiffness is at 40% of ultimate load per test standard AISI S915-20. Tabulated values apply to both ASD and LRFD

3. Allowable loads consider bridging connection only. It is responsibility of the designer to verify the strength and serviceability of the framing members.

4. Allowable loads are based on the use of (2) #10 screws between clip and u-channel and (2) #10 screws between clip and stud lips.

How to Use Bridging Connector Allowable Load Table


The tabulated strength and stiffness values are for use with Sections C2.2.1 and C2.3 of the 2016 edition of AISI *North American Specification for the Design of Cold-Formed Steel Structural Members* (AISI S100-2016) as follows:

Bracing Design for Laterally-Loaded C-Studs


- Step 1: Calculate required bracing force for each flange using equation C2.2.1-3
- Step 2: Multiply result by stud depth to obtain torsional moment
- Step 3: Select connector with tabulated allowable torsional moment that exceeds the calculated torsional moment from Step 2 for the stud depth and gauge required

Bracing Design for Axially-Loaded C-Studs

- Step 1: Calculate required brace strength using equation C2.3-1
- Step 2: Calculate required brace stiffness using equation C2.3-2a
- Step 3: Select connector with tabulated allowable brace strength that exceeds strength from Step 1 and tabulated brace stiffness that exceeds stiffness from Step 2 for the stud depth and gauge required



SUBE Lateral Load



SUBE Axial Load

For a similar design example, reference p. 147

SBR/DBR Spacer Bracers



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

Simpson Strong-Tie introduces the SBR and DBR spacer bracers for cold-formed steel construction. These spacer bracers reduce the installed cost of cold-formed steel stud walls by enabling faster stud layout while minimizing the need for bridging clips.

The DBR is used for interior walls to eliminate stud bow and allow for quicker drywall attachment, while the SBR is designed for structural exterior walls. Both products provide bracing along the length of the stud, and for head-of-wall slip conditions. The SBR and DBR also come with prepunched slots that eliminate the need to use bridging clips with on-module studs.

The SBR and DBR spacer bracers come with bracing load data based on assembly testing, thus mitigating risk for designers and maximizing confidence in design specs. In fact, the SBR and DBR are the only spacer bracers on the market with tabulated design values based on assembly tests.

Features:

- SBR and DBR have patent-pending precision-engineered prepunched slots strategically located to enable 12", 16" and 24" on-center stud spacing and can be used to space the studs without having to mark the top track for layout
- The SBR will accommodate 3 $\frac{3}{8}$ " up to 8" studs in thicknesses of 33 mil (20 ga.) through 68 mil (14 ga.)
- The DBR will accommodate 2 $\frac{1}{2}$ ", 3 $\frac{3}{8}$ " and 6" studs in thicknesses of 15 mil (25 ga. EQ) through 33 mil (20 ga.)
- Prepunched holes in the SBR provide rapid screw installation when spacer-bracer splices are needed for axial load-bearing studs
- In off-layout or end-of run conditions, the hat-section profiles enable clip attachments to the stud with Simpson Strong-Tie® LSSC or RCA connectors

Installation:

- Spacer bracers are fed through the stud knockout at a 90° angle until studs align with spacer-bracer slots. With the slots engaging the stud web, the spacer-bracer is then rotated back to the flat position so that the slotted flanges are on the bottom.
- For off-layout or end-of-run studs where a spacer-bracer slot does not engage a stud, manually snip the spacer-bracer flanges with a $\frac{1}{2}$ "-deep slot and secure the spacer bracer to the stud with Simpson Strong-Tie LSSC or RCA connectors. Use all specified fasteners.
- Wear gloves while handling and installing spacer bracers.

Material: SBR/43 — 43 mil (40 ksi);
DBR/30 — 27 mil (33 ksi)


Finish: Galvanized (G90)

Codes: See p. 15 for Code Reference Key Chart

Ordering Information:

Model No.	Ordering SKU	
	Box Quantity	Pallet Quantity
DBR/30	DBR/30-R20	DBR/30-R680
SBR/43	SBR/43-R20	SBR/43-R680


R20 come in boxes of 20. R680 come in pallets of 680 (loose).




SBR/DBR Spacer Bracers

SBR and DBR Spacer Bracer — Connection Strength and Stiffness

Model No.	Stud Depth (in.)	Stud Thickness mil (ga.)	Allowable Torsional Moment (in./lb.)	Allowable Brace Strength (lb.)	Brace Stiffness ² (lb./in.)	Code Ref.
SBR/43	3½	33 (20)	240	330	2,090	—
		43 (18)	310	435	3,190	
		54 (16)	400	435	3,190	
		68 (14)	400	435	3,190	
	6	33 (20)	215	135	655	
		43 (18)	310	330	1,275	
		54 (16)	370	450	1,400	
		68 (14)	370	450	1,400	
	8	33 (20)	195	70	320	
		43 (18)	305	175	635	
		54 (16)	345	315	855	
		68 (14)	345	485	1,350	
DBR/30	2½	15 (25 EQ)	55	—	—	
		18 (25)	55	—	—	
		19 (20 EQ)	65	—	—	
		30 (20 DW)	90	—	—	
		33 (20 STR)	90	—	—	
	6	15 (25 EQ)	55	—	—	
		18 (25)	55	—	—	
		19 (20 EQ)	65	—	—	
		30 (20 DW)	90	—	—	
		33 (20 STR)	90	—	—	



Laterally Loaded C-Stud with SBR Spacer Bracer
(DBR spacer bracer similar)



Axially Loaded C-Stud with SBR Spacer Bracer

1. Allowable loads are for use when utilizing the traditional Allowable Stress Design methodology. For LRFD loads multiply the ASD tabulated values by 1.6.
2. Brace stiffness is at 40% of ultimate load per test standard AISI S915-20. Tabulated values apply to both ASD and LRFD.
3. Allowable loads consider bridging connection only. It is the responsibility of the designer to verify the strength and serviceability of the framing members.
4. EQ — equivalent, DW — drywall, STR — structural.

C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

SBR/DBR Spacer Bracers

SBR and DBR Gross Properties

Model No.	Design Thickness (in.)	F _y (ksi)	Area ² (in.)	I _x ⁴ (in.)	S _x ³ (in.)	R _x (in.)	I _y ⁴ (in.)	S _y ³ (in.)	R _y (in.)	Torsional Properties					
										Jx1,000 ⁴ (in.)	C _w ⁶ (in.)	Y _o (in.)	m (in.)	R _o (in.)	β
SBR/43	0.0468	40	0.126	0.0047	0.1458	0.1936	0.0436	0.0400	0.5891	0.0916	5.56E-04	0.283	0.017	0.681	0.828
DBR/30	0.0289	33	0.060	0.0023	0.0082	0.1936	0.0109	0.0141	0.4259	0.0167	7.05E-05	0.346	0.087	0.582	0.647

SBR and DBR Net Properties


Model No.	Area ² (in.)	I _x ⁴ (in.)	S _x ³ (in.)	R _x (in.)	I _y ⁴ (in.)	S _y ³ (in.)	R _y (in.)	Torsional Properties					
								Jx1,000 ⁴ (in.)	C _w ⁶ (in.)	Y _o (in.)	m (in.)	R _o (in.)	β
SBR/43	0.085	0.0028	0.0097	0.1816	0.0120	0.0184	0.3765	0.0617	3.43E-05	0.355	0.141	0.548	0.581
DBR/30	0.022	0.0001	0.0004	0.0479	0.0008	0.0027	0.1944	0.0061	1.09E-06	0.086	0.051	0.218	0.844

SBR and DBR Allowable Member Strengths

Model No.	M _a (F _y) (in.-lb.)	M _a (12" o.c.) (in.-lb.)	M _a (16" o.c.) (in.-lb.)	M _a (24" o.c.) (in.-lb.)	P _a (12" o.c.) (lb.)	P _a (16" o.c.) (lb.)	P _a (24" o.c.) (lb.)
SBR/43	369	369	369	360	945	904	618
DBR/30	44	40	38	32	—	—	—


1. Net section properties are based a section that excludes all material that is interrupted by the slots.
2. Member strengths are based on DSM Analysis (non-prequalified section, Ω = 2.0).
3. C_b = 1.67 has been applied to M_a to account for a triangular moment diagram with zero end moment.

SBR/DBR Spacer Bracers



Trim the end of the SBR as needed. For 6" studs, use a Simpson Strong-Tie® LSSC4.25. For 3 5/8" studs, use a Simpson Strong-Tie RCA223/54. Use (2) #10-16 screws to the stud web, and (2) #10-16 screws to the spacer bracer.


SBR End-of-Run for 6" Studs with LSSC4.25
(3 5/8" studs with RCA 223/54 similar)



When the SBR slots do not line-up with a stud, field-snip a 1/2"-deep slot in each flange of the SBR. For 6" studs use a Simpson Strong-Tie LSSC4.25. For 3 5/8" studs use a Simpson Strong-Tie RCA223/54. Use (2) #10-16 screws to the stud web, and (2) #10-16 screws to the spacer bracer.


Note: Field-snipped slots shall be at least 4" away from other prepunched slots, and shall be spaced at least 12" o.c. from other field-snipped slots.

SBR Off-Module for 6" Studs with LSSC4.25
(3 5/8" studs with RCA 223/54 similar)



Trim the end of the DBR as needed. For 6" studs, use a Simpson Strong-Tie LSSC4.25. For 3 5/8" studs, use a Simpson Strong-Tie RCA223/54. Use (2) #10-16 screws to the stud web and (2) #10-16 screws to the spacer bracer.

DBR End-of-Run for 3 5/8" Studs with RCA223/54
(6" studs with LSSC4.25 similar)




When the DBR slots do not line up with a stud, field-snip a 1/2"-deep slot in each side of the DBR. For 6" studs, use a Simpson Strong-Tie LSSC4.25. For 3 5/8" studs use a Simpson Strong-Tie RCA223/54 with (2) #10-16 screws to the stud web and (2) #10-16 screws to the spacer bracer.

Note: Field-snipped slots shall be at least 4" away from other prepunched slots, and shall be spaced at least 12" o.c. from other field-snipped slots.


DBR Off-Module for 3 5/8" Studs with RCA223/54
(6" studs with LSSC4.25 similar)

SBR/DBR Spacer Bracers



Trim the end of the DBR as needed. Use Simpson Strong-Tie® SSC2.25 with (2) #10-16 screws to the stud web and (2) #10-16 screws to the spacer bracer.


DBR End-of-Run for 2.5" Studs with SSC2.25



When the DBR slots do not line up with a stud web, field-snip a 1/2"-deep slot in each DBR flange, and use a 3" long section of DBR reinforcement as shown. Secure the DBR reinforcement with (2) #10-16 screws so that the screw spacing is 1 1/2".

Note: Field-snipped slots shall be at least 4" away from other prepunched slots, and shall be spaced at least 12" o.c. from other field-snipped slots.

DBR Off-Module for 2 1/2" Studs with DBR Reinforcement
(DBR and SBR with 3 5/8" studs and 6" studs similar)




Use #10-16 screws as needed to transfer accumulated load for multiple axially loaded studs. (fastener quantity by designer)

Typical SBR Splice for Axially Loaded Studs

SBR/DBR Spacer Bracers

SBR/43 Maximum Bridging Distance (ft.)

Stud Spacing (in.)	Stud Section	Stud Thickness mil (ga.)	Lateral Stud Pressure (psf)									
			5	10	15	20	25	30	35	40	45	50
12	362S162	33 (20)	8	8	8	8	7	6	5	4	4	—
		43 (18)	8	8	8	8	8	8	7	6	5	5
		54 (16)	8	8	8	8	8	8	8	7	7	6
		68 (14)	8	8	8	8	8	8	8	8	7	6
	362S200	33 (20)	8	8	8	7	6	5	4	—	—	—
		43 (18)	8	8	8	8	8	6	5	5	4	4
		54 (16)	8	8	8	8	8	8	6	6	5	4
		68 (14)	8	8	8	8	8	8	6	6	5	4
	600S162	33 (20)	8	8	8	8	8	7	6	5	4	4
		43 (18)	8	8	8	8	8	8	8	7	6	6
		54 (16)	8	8	8	8	8	8	8	8	8	7
		68 (14)	8	8	8	8	8	8	8	8	8	7
600S200	33 (20)	8	8	8	7	6	5	4	—	—	—	
	43 (18)	8	8	8	8	8	7	6	5	5	4	
	54 (16)	8	8	8	8	8	8	7	6	6	5	
	68 (14)	8	8	8	8	8	8	7	6	6	5	
16	362S162	33 (20)	8	8	8	7	5	4	4	—	—	—
		43 (18)	8	8	8	8	7	6	5	4	4	—
		54 (16)	8	8	8	8	8	7	6	5	5	4
		68 (14)	8	8	8	8	8	8	6	6	5	4
	362S200	33 (20)	8	8	7	5	4	—	—	—	—	—
		43 (18)	8	8	8	7	6	5	4	—	—	—
		54 (16)	8	8	8	8	7	6	5	4	4	—
		68 (14)	8	8	8	8	7	6	5	4	4	—
	600S162	33 (20)	8	8	8	7	6	5	4	—	—	—
		43 (18)	8	8	8	8	8	7	6	5	5	4
		54 (16)	8	8	8	8	8	8	7	6	6	5
		68 (14)	8	8	8	8	8	8	7	6	6	5
600S200	33 (20)	8	8	7	5	4	—	—	—	—	—	
	43 (18)	8	8	8	8	6	5	4	4	—	—	
	54 (16)	8	8	8	8	8	6	5	5	4	4	
	68 (14)	8	8	8	8	8	6	5	5	4	4	
24	362S162	33 (20)	8	8	6	4	—	—	—	—	—	—
		43 (18)	8	8	8	6	5	4	—	—	—	—
		54 (16)	8	8	8	7	6	5	4	—	—	—
		68 (14)	8	8	8	7	6	5	4	—	—	—
	362S200	33 (20)	8	7	5	—	—	—	—	—	—	—
		43 (18)	8	8	6	5	4	—	—	—	—	—
		54 (16)	8	8	7	5	4	—	—	—	—	—
		68 (14)	8	8	7	5	4	—	—	—	—	—
	600S162	33 (20)	8	8	7	5	4	—	—	—	—	—
		43 (18)	8	8	8	7	6	5	4	—	—	—
		54 (16)	8	8	8	8	7	6	5	4	4	—
		68 (14)	8	8	8	8	7	6	5	4	4	—
600S200	33 (20)	8	7	5	—	—	—	—	—	—	—	
	43 (18)	8	8	7	5	4	—	—	—	—	—	
	54 (16)	8	8	8	6	5	4	—	—	—	—	
	68 (14)	8	8	8	6	5	4	—	—	—	—	




C-CF-2026 © 2026 SIMPSON STRONG-TIE COMPANY INC.

1. Tabulated solutions are for ASD lateral pressure. Contact Simpson Strong-Tie for LRFD solutions.
2. Lateral pressures shall be determined based on the load combinations of the applicable building code. For designs in accordance with the 2009 IBC and earlier, wind pressures are at the working stress level and may be used directly. For designs in accordance with the 2012 IBC and later, wind pressures are at the strength level and must be multiplied by 0.6 for ASD load combinations.
3. Tabulated values are based on the minimum of the tested connection strength and the calculated SBR/DBR member strength. Studs must be checked separately for unbraced length.
4. For 8"-studs tabulated values, reference strongtie.com.

SBR/DBR Spacer Bracers

DBR/30 Maximum Bridging Distance (ft.)

Stud Spacing (in.)	Stud Section	Stud Thickness mil (ga.)	Lateral Stud Pressure (psf)	
			5	10
12	362S125	15 (25 EQ)	8	5
		18 (25)	8	5
		19 (20 EQ)	8	5
		30 (20 DW)	8	5
		33 (20 STR)	8	5
	600S125	15 (25 EQ)	8	6
		18 (25)	8	6
		19 (20 EQ)	8	6
		30 (20 DW)	8	6
		33 (20 STR)	8	6
16	362S125	15 (25 EQ)	7	—
		18 (25)	7	—
		19 (20 EQ)	7	—
		30 (20 DW)	7	—
		33 (20 STR)	7	—
	600S125	15 (25 EQ)	8	4
		18 (25)	8	4
		19 (20 EQ)	8	4
		30 (20 DW)	8	4
		33 (20 STR)	8	4
24	362S125	15 (25 EQ)	4	—
		18 (25)	4	—
		19 (20 EQ)	4	—
		30 (20 DW)	4	—
		33 (20 STR)	4	—
	600S125	15 (25 EQ)	4	—
		18 (25)	4	—
		19 (20 EQ)	4	—
		30 (20 DW)	5	—
		33 (20 STR)	5	—



1. Tabulated solutions are for ASD lateral pressure. Contact Simpson Strong-Tie for LRFD solutions.
2. Lateral pressures shall be determined based on the load combinations of the applicable building code. For designs in accordance with the 2009 IBC and earlier, wind pressures are at the working stress level and may be used directly. For designs in accordance with the 2012 and later IBC, wind pressures are at the strength level and must be multiplied by 0.6 for ASD load combinations.
3. Tabulated values are based on the minimum of the tested connection strength and the calculated SBR/DBR member strength. Studs must be checked separately for unbraced length.

SBR Spacer Bracer

Design Example

Given

- 2024 IBC (ASCE7-22) and AISI S100-16
- 600S162-54 (50 ksi) studs at 24" o.c., 10'-stud height
 - Mid-point bracing (5' o.c.)
 - Distance from shear center to mid-plane of web, $m = 0.663"$. (AISI Manual, Table I-2)
- Wind design pressure = 34 psf
- P_{ra} = Required ASD axial load = 3,000 lb.

Axially Loaded Stud

Required brace strength (AISI S100, Eq. C2.3-1)

$$P_{rb} = 0.01P_{ra} = (0.01)(3,000 \text{ lb.}) = 30 \text{ lb.}$$

Required brace stiffness (AISI S100, Eq. C2.3-2a)

$$\beta_{rb} = (2[4 - (2/n)]/L_b)(\Omega P_{ra}) = (2[4 - (2/1)]/60)(2)(3,000) = 400 \text{ lb./in.}$$

Check connection strength and stiffness from Strength and Stiffness table (p. 151) for the SBR/43 for 6"-deep, 54-mil studs

- ➔ Allowable brace strength = 450 lb. > 30 lb. **OK**
- ➔ Brace stiffness = 1,400 lb./in. > 400 lb./in. **OK**

Check member strength from Allowable Strengths table (p. 151) for the SBR/43 for 24" o.c.

- ➔ P_a (24" o.c.) = Allowable member strength = 618 lb. > 30 lb. **OK**

Note: Member stiffness and the effects of accumulated load for multiple axially loaded studs have not been accounted for in the above calculations. Reference CFSEI Tech Note W400-23 for additional guidance on these topics.

Laterally Loaded Stud

ASD Design load tributary to brace:

$$W = (0.6)(34 \text{ psf})(2 \text{ ft.})(5 \text{ ft.}) = 204 \text{ lb.}$$

Note: 2024 IBC load combinations for ASD include a factor of 0.6

Required flange force (AISI S100 Eq. C2.2.1-3)

$$P_{L1} = -P_{L2} = 1.5(m/d)W = (1.5)(0.663 \text{ in.}/6 \text{ in.})(204 \text{ lb.}) = 33.8 \text{ lb.}$$

Torsional moment

$$M_z = P_{L1}d = -P_{L2}d = (33.8)(6) = 202.8 \text{ in.-lb.}$$

Moment applied to bridging member

$$M_m = 0.64M_z = (0.64)(202.8) = 129.8 \text{ in.-lb.}$$


Note: The 0.64 factor is from an analysis of a five-span continuous beam that is loaded with equal support moments (Reference AISI Design Guide D110-16, pp. 2-9, Figure 2-6)

Check connection strength from Strength and Stiffness table (p. 151) for the SBR/43 for 6"-deep, 54-mil studs

- ➔ Allowable torsional moment = 370 in.-lb. > 202.8 in.-lb. **OK**

Check member strength from Allowable Strengths table (p. 151) for the SBR/43 for 24" o.c.

- ➔ M_a (24" o.c.) = Allowable moment = 360 in.-lb. > 129.8 in.-lb. **OK**



Combined-Loading Check of Connection

$$(P_{br}/\text{Allowable brace strength}) + (M_z/\text{Allowable torsional moment}) \leq 1.0$$

$$(30 \text{ lb.}/450 \text{ lb.}) + (202.8 \text{ in.-lb.}/370 \text{ in.-lb.}) = 0.61 < 1.0 \text{ OK}$$

Combined-Loading Check of Bridging Member

Reference AISI Eq. H1.2-1.

Reference Chapter E for Ω_c and Chapter F for Ω_b .

$$\frac{\Omega_c P}{P_n} + \frac{\Omega_b M}{M_n} \leq 1.0$$

$$P_n = 2P_a \quad M_n = 2M_a$$

$$\frac{1.8(30)}{2(618)} + \frac{1.67(129.8)}{2(360)} = 0.34 < 1.0 \text{ OK}$$

Note: The allowable strengths given in the Allowable Strengths table (p. 151) have been converted to nominal strengths by multiplying by $\Omega = 2.0$.

SFC Steel Framing Connectors / SSC Steel-Stud Connectors

SFC/SSC Connectors – U-Channel Bridging Allowable Loads


Model No.	Connector Material Thickness mil (ga.)	Clip Length (in.)	Stud Depth (in.)	Stud Thickness mil (ga.)	Fasteners ^{1,5}		Laterally Loaded C-Stud	Axially Loaded C-Stud		Code Ref.
					Stud	Bridging	Allowable Torsional Moment ² (in.-lb.)	Allowable Brace Strength ² (lb.)	Brace Stiffness ³ (lb./in.)	
SFC4.25	54 (16)	4¼	6	33 (20)	(2) #10	(2) #10	275	125	1,080	IBC, FL, LA
				43 (18)	(2) #10	(2) #10	510	195	1,645	
				54 (16)	(2) #10	(2) #10	640	280	2,600	
LSSC4.25	54 (16)	4¼	6	54 (16)	(2) #10	(2) #10	1,010	180	570	
SSC4.25	68 (14)	4¼	6	54 (16)	(2) #10	(2) #10	650	280	2,335	
				68 (14)	(2) #10	(2) #10	800	335	3,035	
				97 (12)	(2) #10	(2) #10	915	660	5,020	
LSSC6.25	54 (16)	6¼	8, 10, 12	54 (16)	(2) #10	(2) #10	1,010	180	885	

1. See illustrations for fastener placement.


2. Allowable loads are for use when utilizing Allowable Stress Design methodology. For LRFD loads, multiply the tabulated ASD values by 1.6.

3. Brace stiffness is at 40% of ultimate load per test standard AISI S915-20. Tabulated values apply to both ASD and LRFD.

4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Typical SFC4.25 Installation



Typical SSC4.25 Installation

DBC Drywall Bridging Connector

Patented design allows for one- or two-screw installation of the DBC, significantly reducing labor and material cost. The first and only connector load rated for 3/4" u-channel, the DBC joins the SUBH line of bridging connectors tested as a system, ensuring that published design capacities capture the influence of stud web depth and thickness.

Features:

- Most applications require only a single screw
- Designed for 3/4" u-channel to fit smaller web knockouts common to drywall studs
- Compatible with drywall stud depths of 3 5/8" and 6" with 1 1/2" wide knockouts

Material: 33 mil (20 ga.) carbon steel

Finish: Galvanized (G90)

Installation:

- With 3/4" x 54 mil (16 ga.) u-channel installed through the stud web knockouts, insert the DBC2.5 through the knockout so that the DBC slots engage the stud web and the DBC flanges engage the u-channel as shown in the illustration
- Use the specified number of #8 screws to fasten the DBC to the u-channel


Codes: See p. 15 for Code Reference Key Chart

Ordering Information:

Model No.	Ordering SKU	Bucket Quantity
DBC2.5	DBC2.5-R200	200



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.



 DBC2.5

US Patent.
See strongtie.com/patent.

DBC Drywall Bridging Connector

DBC — Bridging Connector Strength Allowable Loads

Model No.	Stud Depth	Stud Thickness and Yield Strength			Fasteners		Laterally Loaded C-Stud Allowable Torsional Moment (in.-lb.)	Code Ref.	
		Mil	Gauge ³	F _y (ksi)					
DBC2.5	3½"	15	25 EQ.	50	Min.	(1) #8	65	—	
		18	25	33					
		19	20 EQ.	65					
		20	20 EQ.	57					
		30	20 DW	33	Min.	(1) #8			85
					Max.	(2) #8			125
				Min.	(1) #8	85			
				Max.	(2) #8	125			
	6"	15	25 EQ.	50	Min.	(1) #8	65		
		18	25	33					
		19	20 EQ.	65					
		21	20 EQ.	57					
		30	20 DW	33	Min.	(1) #8			85
					Max.	(2) #8			125
				Min.	(1) #8	85			
				Max.	(2) #8	125			

- Allowable loads are for use when utilizing Allowable Stress Design methodology. For LRFD loads, multiply the ASD tabulated values by 1.6.
- Min. fastener quantity and tabulated values — fill round hole (one screw total);
Max. fastener quantity and tabulated values — fill round and triangle holes (two screws total).
- EQ — equivalent, DW — drywall, STR — structural.

Design Example

Given

- 600S125–18 (33 ksi) studs at 24" o.c., 10' tall
Mid-point bracing (5' o.c.)
Distance from shear center to mid-plane of web, $m = 0.408$ in.
(SFIA Technical Guide Version 2022)
- Lateral load = 5 psf

Laterally-Loaded Stud Design

ASD Design load tributary to brace:

$$W = (5 \text{ psf})(2 \text{ ft.})(5 \text{ ft.}) = 50 \text{ lb.}$$

Required bracing force (AISI S100 Eq. C2.2.1-3):


$$P_{L1} = -P_{L2} = 1.5(m/d)W = (1.5)(0.408 \text{ in.}/6 \text{ in.})(50 \text{ lb.}) = 5.1 \text{ lb.}$$

Torsional moment:

$$M_z = P_{L1}d = -P_{L2}d = (5.1 \text{ lb.})(6 \text{ in.}) = 30.6 \text{ in.-lb.}$$

From Allowable Loads table above, for 6"–18 mil stud:

- ➡ Select DBC2.5 with Min. fasteners ((1) #8)
Allowable torsional moment = 65 in.-lb. > 30.6 in.-lb. **OK**



CS Coiled Strap

CS coiled utility straps are an ideal solution when it is desired to brace wall studs via the flanges with strap. These products are packaged in lightweight (about 40 pounds) cartons and can be cut to length on the jobsite.

Materials: See table.


Finish: Galvanized (G90); ZMAX®

Installation:

- Use all specified fasteners; see General Notes.
- Refer to the applicable code for minimum edge and end distance.
- The table shows the maximum allowable loads and the screws required to obtain them. See footnote #1. Fewer screws may be used as given by footnote #3.

Codes: See p. 15 for Code Reference Key Chart

Ordering Information: Coil Length: CS16 150 ft., CS20 250 ft.




CS16 Hole Pattern
(all other CS straps similar)

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Total Length (ft.)	Connector Material Thickness mil (ga.)	Width (in.)	Fasteners (At Blocking) ⁴			Allowable Tension Load (lb.)	Code Ref.
				Framing Thickness mil (ga.)				
				33 (20)	43 (18)	54 (16)		
CS16	150	54 (16)	1 1/4	(9) #10	(6) #10	(4) #10	1,550	—
CS20	250	33 (20)	1 1/4	(6) #10	(4) #10	(3) #10	945	

1. In order to achieve the tabulated loads in the strap, attach each strap to the blocking with the tabulated number of screws.
2. Strap length at blocking to achieve tabulated load = number of tabulated screws + 1".
3. Calculate the strap value for a reduced number of screws to the blocking as follows:

$$\text{Allowable Load} = \frac{\text{No. of Screws Used}}{\text{No. of Screws in Table}} \times \text{Table Load.}$$
4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Stud Blocking with CS Coiled Strap

LTB Bridging


LTB bridging connectors are a cost-effective solution for bracing between non-load-bearing wall studs when compared with field fabricated blocking and clip angles.

Material: 27 mil (22 ga.)


Finish: Galvanized (G90)

Installation:

- Use (2) #10 screws at each end
- The LTB can be utilized with 3½", 6", 8", and 10" studs at 16" o.c.
- LTB works only in tension, so must be used in cross pairs
- Install bridging tightly; loose installation may allow stud movement



LTB20



Typical LTB20 Installation
for Double-Side Strap

WBAC Wood Backing Steel Connector

The WBAC wood backing steel connector is the ideal solution for connecting wood backing or cold-form steel (CFS) backing to cold-formed steel studs. Perfect for cabinets, shelves, handrails, heavy wall hangings and more, this versatile connector installs easily and provides tested strength. The WBAC is designed to eliminate alignment issues and reduce installation time. Since stiffness and strength are critical for these applications, the fastening pattern into both steel and wood has been engineered to optimize performance.

Features:

- Simple installation using prepunched holes allowing the same screw to be used for both wood backing and stud attachment
- Not limited to just a 1½" flange, the WBAC has been tested to accommodate 1¼" flanges, 1⅝" flanges and 2" flanges
- Works for any stud spacing, predetermined or typical stud spacing not required
- Sight lines to guide installation alignment
- Unique rolled support bottom tabs provide extra strength and stiffness

Materials: WBAC162 33 mil (20 ga.), 33 ksi;
WBAC200 33 mil (20 ga.), 33 ksi

Finish: Galvanized (G90)



Installation:

- Attach to grade lumber, ⅝" fire-rated board or CFS backing
- Use WBAC162 for 1¼" and 1⅝" flanges, and WBAC200 for 2" flanges
- Drywall stud (1¼" flange) — Align top of connector with markings and attach using (4) #8–18 modified truss-head self-drilling screws to stud flange and (3) #8–18 modified truss-head screws to each wood block
- Structural studs (1⅝" and 2" flange) — Attach using (4) #8–18 modified truss-head SDS screws [(2) to stud flange, (1) to lip, and (1) to web] and (3) #8–18 modified truss-head screws to each wood block

Codes: Testing performed in accordance with ICC-ES AC261

Ordering Information:

Model No.	Ordering SKU	Package Quantity
WBAC162	WBAC162-R50	50
WBAC200	WBAC200-R50	50




Typical WBAC162 Installation
(WBAC200 similar)


Fastener Patterns

WBAC162 Installation to 1¼" Flange	WBAC162 Installation to 1⅝" Flange	WBAC200 Installation to 2" Flange


WBAC Wood Backing Steel Connector



WBAC162 Installation to 1 1/4" Flange



WBAC162 Installation to 1 5/8" Flange




WBAC200 Installation to 2" Flange

Allowable Loads on Wood Blocking Supported by WBAC (lb.)


Model No.	Stud Thickness mil. (ga.)	Stud Steel Strength, F_y (ksi)	Fasteners		Allowable Load (lb.)			
			Stud	Wood Blocking	F_2 @ 1/8" Deflection	F_2 @ Strength	F_4 @ 0" Offset	F_4 @ 3" Offset
Stud Flange = 1 1/4"								
WBAC162	15 (25 EQ)	50	(4) #8	(3) #8	95	135	275	60
	18 (25)	33			90	160	175	40
	19 (20 EQ)	57			95	135	275	60
	30 (20 DW)	33			150	265	285	65
	33 (20 Struct)	33			220	295	320	75
Stud Flange = 1 5/8"								
WBAC162	33 (20 Struct)	33	(4) #8	(3) #8	220	295	320	75
	43 (18)	33			260	355	355	85
	54 (16)	50			275	405	395	95
Stud Flange = 2"								
WBAC200	33 (20 Struct)	33	(4) #8	(3) #8	220	295	320	75
	43 (18)	33			260	355	355	85
	54 (16)	50			275	405	395	95

1. Allowable loads may not be increased for wind or seismic load.
2. Allowable loads are the lower of tested ultimate load with a safety factor, load at 1/8" deflection (u.o.n.), or fastener calculation limits in accordance with ICC-ES AC261.
3. Fasteners to stud and wood blocking are #8-18 (3/4" min. long) modified truss-head screws.
4. Wood blocking may be any species of solid sawn or engineered lumber with a minimum specific gravity of 0.42.
5. Listed capacities do not consider the resistance of the gypsum board. The WBAC connector installed with 5/8" gypsum may be increased by a factor of 1.15, 1.15, and 1.35 for F_2 @ 1/8" deflection, F_4 @ 0" offset, and F_4 @ 3" offset, respectively.
6. F_3 is limited to an allowable capacity of 175 lb. with (3) #8-18 (3/4" long) modified truss screws to each wood block or 260 lb. with (3) #8-18 (1" long). F_3 tests do not consider resistance of gypsum board.
7. F_4 may be interpolated between offset 0" and 3".
8. F_2 , F_3 and F_4 loads assumed to act at 1/4 point of wood blocking.
9. For combined loading, use (F_2 @ Strength) and a linear interaction.




WBAC162 Installation to 1 5/8" Stud Flange with Gypsum
(see table footnote 5 for addition of gypsum board)


WBAC CFS Backing Steel Connector



WBAC162 Installation to 1 1/4" Flange



WBAC162 Installation to 1 5/8" Flange




WBAC200 Installation to 2" Flange

Allowable Loads on CFS Blocking Supported by WBAC (lb.)

Model No.	Wall Stud		CFS Blocking		Fasteners		Allowable Load (lb.)			
	Thickness mil. (ga.)	Steel Strength F _y (ksi)	Thickness mil. (ga.)	Steel Strength F _y (ksi)	Wall Stud	CFS Blocking	F ₂ @ 1/8" Deflection	F ₂ @ Strength	F ₄ @ 0" Offset	F ₄ @ 3" Offset
Stud Flange = 1 1/4"										
WBAC162	15 (25 EQ)	50	33 (20)	33	(4) #8	(3) #8	95	135	275	60
	18 (25)	33					90	160	175	40
	19 (20 EQ)	57					95	135	275	60
	30 (20 DW)	33					150	265	285	65
	33 (20 Struct)	33				220	295	320	75	
Stud Flange = 1 5/8"										
WBAC162	33 (20)	33	33 (20)	33	(4) #8	(3) #8	230	320	320	90
	43 (18)	33					230	320	355	90
	54 (16)	50					230	375	395	110
	33 (20)	33	43 (18)	33	(4) #8	(3) #8	230	320	320	90
	43 (18)	33					275	335	355	90
	54 (16)	50					315	375	420	110
	33 (20)	33	54 (16)	50	(4) #8	(3) #8	230	320	320	90
	43 (18)	33					275	335	355	90
54 (16)	50	375					400	510	115	
Stud Flange = 2"										
WBAC200	33 (20)	33	33 (20)	33	(4) #8	(3) #8	230	320	320	90
	43 (18)	33					230	320	355	90
	54 (16)	50					230	375	395	110
	33 (20)	33	43 (18)	33	(4) #8	(3) #8	230	320	320	90
	43 (18)	33					275	335	355	90
	54 (16)	50					315	375	420	110
	33 (20)	33	54 (16)	50	(4) #8	(3) #8	230	320	320	90
	43 (18)	33					275	335	355	90
54 (16)	50	375					400	510	115	

1. Allowable loads may not be increased for wind or seismic load.
2. Allowable loads are the lower of tested ultimate load with a safety factor, load at 1/8" deflection (u.o.n.), or fastener calculation limits in accordance with ICC-ES AC261.
3. Fasteners to stud and steel blocking are #8-18 (3/4" min. long) modified truss-head screws.
4. Listed capacities do not consider the resistance of the gypsum board. The WBAC connector installed with 5/8" gypsum may be increased by a factor of 1.15, 1.15, and 1.35 for F₂ @ 1/8" deflection, F₄ @ 0" offset, and F₄ @ 3" offset, respectively.
5. F₄ may be interpolated between offset 0" and 3".
6. F₃ is limited to an allowable capacity of 260 lb. with (3) #8-18 (3/4" long) modified truss screws to each blocking. F₃ tests do not consider resistance of gypsum board.
7. F₂, F₃ and F₄ loads are assumed to act at 1/4 point of the blocking and therefore 3/4 of load listed assumed to act on WBAC connector. The tables cover the allowable capacity of the WBAC and the attachment to and from the WBAC. The blocking design is by others.
8. For combined loading, use (F₂ @ Strength) and a linear interaction.



WBAC162 Installation to 1 5/8" Stud Flange with Gypsum
(see table footnote 5 for addition of gypsum board)

Ready-Track® Framing



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.


Ready-Track framing is the fast and dependable way to frame curved walls on the jobsite. Simple to bend into smooth curves, it holds its shape without fasteners for easy positioning and installation.

- Ideal for curved walls, stairwells, soffits, clouds and complicated compound radiuses
- Handles almost any application when you need material curved along the flange
- Screw holes in the bottom web allow the top-track radius to be locked down for easy replication, once fitted over the bottom track
- Optional screw holes in the leg allow the radius to be easily locked down from the side

Order and Dimension Information:

Model No.	Track Width (in.)	Length (ft.)	Quantity per Bundle*
20 Gauge (30 mil)			
RT250-8	2½	8	12
RT250-10	2½	10	10
RT350-8	3½	8	12
RT362-8	3¾	8	12
RT362-10	3¾	10	10
RT400-8	4	8	6
RT400-10	4	10	10
RT550-8	5½	8	6
RT600-8	6	8	6
RT600-10	6	10	10
18 Gauge (43 mil)			
RT362-10-18	3¾	10	10
RT600-10-18	6	10	10

*Product is shipped in bundled, straight sections.



Ready-Track



Typical Ready-Track Installation

Ready-Arch® Framing



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

Creating arched openings and designs is simpler than ever with Ready-Arch framing members. Round, elliptical or s-shapes are all easy to form on the jobsite without any cutting or additional reinforcement. Ready-Arch members are also ideal for more challenging applications where material needs to curve along the web.

- Ideal for soffits, arches, light coves and elliptical or eyebrow curves for windows and doorways
- 20-gauge (30 mil) steel holds its shape without any fasteners
- Installs to cold-formed steel or wood framing

Order and Dimension Information:

Model No.	Width (in.)	Length (ft.)	Quantity per Bundle*
RA362-8	3¾	8	10
RA600-8	6	8	6

*Product is shipped in bundled, straight sections.



Ready-Arch



Typical Ready-Arch Installation

Ready-Hat® Framing



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

Whether the plans call for framing over a CMU wall or concrete column or just a curved transition from wall to ceiling, the Ready-Hat furring and framing channel is right for the job. This versatile product is easy to form by hand into the exact shape needed and is secured to concrete or CMU walls with powder-driven fasteners or concrete screws.

- Ideal for furring on curved walls or to create coves, barrel vaults, groin vaults, soffits and serpentine ceilings
- Great for wrapping columns or as cross-framing to eliminate drywall butt joints
- 20-gauge (33 mil) steel holds its shape once formed and positioned for easy fastening

Order and Dimension Information:

Model No.	Channel Height (in.)	Overall Width (in.)	Length (ft.)	Quantity per Bundle*
RH087-10	7/8	2 1/2	10	10

*Product is shipped in bundled, straight sections.



Ready-Hat



Typical Ready-Hat Installation

Ready-Angle® Framing



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

Ready-Angle framing angle adapts to almost any shape, and curves in multiple directions, so it's easy to form challenging compound curves and s-bends. Use two pieces to replicate curved track for steel and wood studs, to form arches of any depth quickly, or to produce finished corners that are ready for drywall.

- Ideal for s-shapes, spirals, sweeps or virtually any free-form shape
- 20-gauge (30 mil) steel holds its shape without any fasteners
- A versatile product for problem-solving on the jobsite

Order and Dimension Information:

Model No.	Angle Leg (in.)	Length (ft.)	Quantity per Bundle*
RL150-8	1 1/2	8	12
RL150-10	1 1/2	10	10

*Product is shipped in bundled, straight sections.



Ready-Angle



Typical Ready-Angle Installation

Ready Track Bender™ Custom Framing Tool

The Ready Track Bender is a portable, on-the-jobsite tool that bends studs and track easily, accurately and conveniently by creating compound indentations at consistent intervals along the length of the material.

- Spaces indentations as close as 2" apart for a tight radius, and up to 12" or more apart for a larger radius
- Forms all standard stud and track profiles up to 20-gauge thick and 6" wide
- No flange or web cutting to form radius and no plywood or strap repair needed for strength
- Reliable and precise — turn the dial to the desired radius and create uniform bends in piece after piece, all day long
- Tough heavy-gauge steel construction throughout for smooth, trouble-free operation job after job
- Rugged plastic case for easy transportation



D150 Deluxe Tool Capabilities:

- Bends 20-gauge and 25-gauge steel
- Forms track or studs 2½" to 6" wide
- Can accommodate leg length up to 3" high

Minimum Bend Radius

Track/Stud Width (in.)	Approx. Min. Radius (in.)	Bend Spacing (in.)
2½	13	2
3½ – 4	19	2
5½ – 6	27	2

To learn more about how Simpson Strong-Tie can make your curved CFS wall and ceiling framing jobs faster and easier, visit strongtie.com/cfs.

AnchorMate® Anchor Bolt Holders

The reusable AnchorMate anchor bolt holder is designed to hold the anchor in place before the concrete pour, as required in some jurisdictions. The gripping section secures the bolt in place without a nut for quicker setup and teardown. It also protects the threads from wet concrete and simplifies trowel finishing.

Features:


- Built-in 2x4 and 2x6 stops eliminate measuring.
- Color coded for easy size identification.
- Use the 5/8" and 7/8" AnchorMate to secure the SABR™ to the formboard before the concrete pour. Alignment arrows (left or right) match the SABR bolt head arrow.

Material: Nylon

Codes: See p. 15 for Code Reference Key Chart

Model No.	Diameter (in.)	Color	Code Ref.
AM1/2	1/2	Yellow	—
AM5/8	5/8	Blue	
AM3/4	3/4	Red	
AM7/8	7/8	Green	
AM1	1	Black	

AnchorMate
Anchor Bolt Holder
 US Patent.
 See strongtie.com/patent.



ABS Anchor Bolt Stabilizer

The ABS stabilizes the anchor bolt to prevent it from being pushed against the form during the concrete pour.


Features:

- Supports the bolt approximately 8" below the top of the concrete
- Model ABS5/8 is for the 5/8" SABR and ABS7/8 is for the 7/8" SABR
- Thin section limits the effect of a cold joint
- Sized for 2x4 and 2x6 mudsills

Material: Engineered Composite Plastic

Codes: See p. 15 for Code Reference Key Chart

Model No.	Diameter (in.)	Color	Code Ref.
ABS5/8	5/8	Blue	—
ABS7/8	7/8	Green	



StrapMate® Strap Holder

The StrapMate is designed to keep the STHD and LSTHD straps vertically aligned during the concrete pour to minimize possibility of spalling. The friction fit allows for quick and easy installation.

Features:


- The StrapMate is reusable
- Works with STHD, LSTHD

Material: Engineered Composite Plastic

- Designed to fit 3/4" plywood forms up to 1 1/4" LVL forms and larger
- The strap is positioned off the front edge of the form board

Codes: See p. 15 for Code Reference Key Chart

Model No.	Nails	Code Ref.
SM1	(2) 8d duplex	—



BP/LBP Bearing Plates

Bearing plates give greater bearing surface than standard cut washers, and help distribute the load at these critical connections.

The BP $\frac{1}{2}$ -3 and BP $\frac{5}{8}$ -3 are 3" x 3" bearing plates that meet the latest requirements of the IBC. These plate washers are available uncoated or with a hot-dip galvanized (HDG) coating.

The BPS and LBPS are bearing plates that offer increased flexibility. The slotted hole allows for adjustability to account for bolts that are not in the middle of the track-bottom plate.



Material: See table

Finish: LBP, LBPS and BP5/8S — Galvanized;
BP7/8-2 and BP5/8S — Zinc Plated; BPS, BP — None.
BPs and BPSs may be ordered HDG;
LBP and LBPS products may be ordered ZMAX®; contact Simpson Strong-Tie. Refer to pp. 21–25 for Corrosion Information.


Installation:

- See General Notes on pp. 16–19.
- BP/BPS — For shearwall applications, position edge of plate washer within ½" of sheathed edge of track bottom plate.

Codes: See p. 15 for Code Reference Key Chart



BPS $\frac{1}{2}$ -6
(other models similar)



Typical BP Installed with a Bottom Track Anchor Bolt

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Bolt Diameter (in.)	Model No.	Thickness	Dimensions (in.)		Code Ref.
			W	L	
3/8	BP 3/8-2	3/16"	2	2	—
1/2	LBP 1/2	9/64"	2	2	
	LBPS 1/2	9/64"	3	3	
	BPS 1/2-3	3 ga.	3	3	
	BPS 1/2-6	3 ga.	3	4 1/2	
	BP 1/2	3/16"	2	2	
	BP 1/2-3	3 ga.	3	3	
5/8	LBP 5/8	9/64"	2	2	
	LBPS 5/8	9/64"	3	3	
	BPS 5/8-3	3 ga.	3	3	
	BPS 5/8-6	3 ga.	3	4 1/2	
	BP 5/8-2	3/16"	2	2	
	BP5/8SKT	3 ga.	4	2	
	BP 5/8	1/4"	2 1/2	2 1/2	
	BP 5/8-3	3 ga.	3	3	
3/4	BP 3/4-3	3 ga.	3	3	
	BPS 3/4-3	3 ga.	3	3	
	BPS 3/4-6	3 ga.	3	4 1/2	
	RP6	3/8"	6	5 3/4	
7/8	BP 7/8-2	3/8"	1 15/16	2 1/4	
	BP 7/8-R	5/16"	3	3	
1	BP1	3/8"	3 1/2	3 1/2	

1. BP5/8SKT sold as a kit.
2. Standard-cut washer required with BPS 1/2-3, BPS 5/8-3, BPS 3/4-3, BPS 1/2-6, BPS 5/8-6, and BPS 3/4-6 (sold separately) per the 2012/2015/2018/2021 IRC 3.3 gauge is 0.229".

CNW Coupler Nuts


Simpson Strong-Tie coupler nuts are a tested and load-rated method to join threaded rod and anchor bolts. The Witness® holes in each nut provides a means to verify when rods are properly installed. The positive stop feature helps ensure even threading into each end of the nut. The CNW exceeds the specified minimum tensile capacity of corresponding standard-strength bolts and threaded rod. The HSCNW exceeds the specified minimum tensile capacity of corresponding high-strength bolts and threaded rod. Contact Simpson Strong-Tie for other coupler nut sizes.

Finish: Zinc Plated


Installation:

- Tighten the two rods until each all-thread rod is visible in the Witness hole. Any portion of thread visible in the Witness hole is a correct installation.
- Standard CNW for use with non-hot-dip galvanized all-thread rod only.
- Couplers available with oversized threads for installation to hot-dip galvanized bolts (order CNW5/8-5/8-OST and CNW7/8-7/8-OST).
- OST couplers are typically oversized on one end of the coupler nut only and will be marked with an “O” on oversized side. Contact Simpson Strong-Tie to order.

Codes: See p. 15 for Code Reference Key Chart




CNW Transition Coupler Nut



Model No.	Rod Diameter (in.)	Allowable Tension Load (lb.)	Code Ref.	
		(100)		
CNW1/2	1/2	4,265	—	
CNW5/8	5/8	6,675		
CNW3/4	3/4	9,610		
CNW7/8	7/8	13,080		
CNW1	1	17,080		
CNW1-1/4	1 1/4	26,690		
HSCNW3/4	3/4	19,880		
HSCNW1	1	35,345		
Transition Couplers				—
CNW5/8-1/2	5/8 to 1/2	4,265		
CNW3/4-5/8	3/4 to 5/8	6,675		
CNW7/8-5/8	7/8 to 5/8	6,675		
CNW1-7/8	1 to 7/8	13,080		

1. Allowable loads shown are based on AISC 360 for A36 and A449 (HS) threaded rods.
2. To obtain LFRD values, multiply ASD load values by 1.5.



Typical CNW Rim Joist Installation

ABL Anchor Bolt Locator

The ABL enables the accurate and secure placement of anchor bolts on concrete-deck forms prior to concrete placement. The structural heavy-hex nut is attached to a preformed steel "chair," which eliminates the need for an additional nut on the bottom of the anchor bolt. Electrogalvanized versions available for HDG anchor bolts. Order ABL-OST when using HDG anchor bolts.


Features:

- Designed for optimum concrete flow
- Installed with two nails or two screws
- Meets code requirement for 1" standoff
- The ABL is designed for use with SAR anchors


Material: Nut — Heavy hex; Chair — 14 gauge

Finish: Nut — None or Electro-galvanized;
Chair — G90

Codes: See p. 15 for Code Reference Key Chart



ABL
US Patent.
See strongtie.com/patent.



Typical ABL Installation

Model No.	Anchor Bolt Diameter (in.)	Code Ref.
ABL4-1	½	—
ABL5-1	⅝	
ABL6-1	¾	
ABL7-1	7⁄8	
ABL8-1	1	
ABL9-1	1 ⅛	
ABL10-1	1 ¼	

Please visit strongtie.com for ABL load ratings.

MASA™/MASAP™ Mudsill Anchors

Mudsill anchors have always been a time-saving alternative to anchor bolts, and the MASA anchors provide an even greater load-carrying capacity alternative. For 5/8" and 1/2" mudsill anchor bolts on bottom tracks, the MASA has load capacities that meet or exceed the parallel and perpendicular to plate shear capacity of other cast-in-place anchors. Two versions of the MASA are available — the standard MASA for installation on standard forms, and the MASAP for panelized forms.

The MASA and MASAP are code listed by ICC-ES under the 2006, 2009, 2012 and 2015 IBC and IRC and have been tested to meet the requirements of ICC-ES acceptance criteria AC-398 for cracked and uncracked concrete.



Material: 16 gauge

Finish: Galvanized, all available in ZMAX® coating. See Corrosion Information, pp. 21–25.

Installation:

- Use all specified fasteners; see General Notes
- Concrete shall have a minimum $f'_c = 2,500$ psi.
- Spalling — Full loads apply for spalls up to a maximum height of 1 1/4" and a maximum depth of 7/8". Any exposed portion of the mudsill anchor must be protected against possible corrosion.
- Minimum MASA end distance is 4" and minimum center-to-center spacing is 8" for a full load.
- For continuous load path, MASA should be installed on the same side of the wall as uplift connectors.


Codes: See p. 15 for Code Reference Key Chart




Allowable Loads for MASA/MASAP Cast-in-Place Mudsill Anchor on CFS Track

Model No.	Fasteners ⁸		Allowable Load (lb.) ^{1,2,3,4,5} 43 mil (18 ga.) CFS						Code Ref.
	Sides	Top of Track	Standard Installation						
			Wind and SDC A & B ⁶			SDC C-F			
			Uplift	Parallel to Track ⁷	Perpendicular to Track	Uplift	Parallel to Track ⁷	Perpendicular to Track	
MASA or MASAP	(3) #10	(6) #10	Non-Cracked						IBC, FL, LA
			645	1,155	855	565	1,010	750	
			Cracked						
			490	1,155	630	425	1,010	550	

1. Allowable loads are governed by tests and may not be increased ($C_D = 1.0$).
2. The tabulated allowable (ASD) loads may be multiplied by 1.67 for designs for wind and in SDC A & B, and by 1.4 for designs in SDC C-F to obtain the LRFD loads.
3. Minimum concrete compression strength, f'_c is 2,500 psi.
4. Allowable loads are based on a minimum stemwall width of 6".
5. For simultaneous loads in more than one direction, the connector must be evaluated using the Unity Equation.
6. Per Section 1613 of the 2012, 2015 and 2018 IBC, detached one- and two-family dwellings in SDC C may use the "Wind and SDC A & B" allowable loads.
7. Parallel-to-Track loads for One-Leg-Up Installation: SDC A-C = 985 lb., SDC C-F = 860 lb.
8. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



Standard MASAP Installation in Concrete



Standard MASA Installation in Concrete

Simpson Strong-Tie® Anchor Solutions for CFS Construction

The most frequently applicable and suitable Simpson Strong-Tie Anchors used with CFS installations. For further information and more anchorage solutions, please visit strongtie.com.

✓ = Code listed ✓ = Tested — = Not tested

Product			Base Materials					Other
			Concrete		Concrete on Metal Deck	CMU		
			Cracked	Uncracked		Grout-Filled	Hollow	
Adhesive Anchors	SET-3G®		✓	✓	—	✓	✓	—
	AT-3G™		✓	✓	—	—	—	—
Mechanical Anchors	Titen HD® (THD) (reference pp. 176–180)		✓	✓	✓	✓	✓	—
	Titen HD Countersunk Screw Anchor		✓	✓	✓	✓	✓	—
	Strong-Bolt® 2 (STB2)		✓	✓	✓	✓	—	—
	Tie-Wire (TW)		—	✓	✓	—	—	—

Simpson Strong-Tie® Anchor Solutions for CFS Construction

✓ = Code listed

✓ = Tested

— = Not tested

Product			Base Materials					
			Concrete		Concrete on Metal Deck	CMU		Other
			Cracked	Uncracked		Grout-Filled	Hollow	
Mechanical Anchors	Titen Turbo™ (TNT)		—	✓	—	✓	✓	—
	Drop-in Anchors (DIAB and DIA-S)		—	✓	✓	—	—	Hollow Core ✓
	Hollow Drop-In (HDIA)		—	✓	—	—	✓	—
	Zinc Nailon™ (ZN)		—	✓	—	—	—	—
	Crimp Drive® (CD)		—	✓	✓	—	—	—
Direct Fastening	Powder-Actuated Fasteners (PDPAT, PDPA) (reference pp. 181–183)		—	✓	✓	✓	✓	Steel ✓
	Gas-Actuated Fasteners (GDP, GDPS)		—	✓	✓	✓	✓	Steel ✓
	Gas-Actuated Fasteners (GDPSK)		—	—	—	—	—	Plywood/ OSB to CFS ✓

Titen HD® Heavy-Duty Screw Anchor

A high-strength screw anchor for use in cracked and uncracked concrete, as well as uncracked masonry. The Titen HD offers low installation torque and outstanding performance. Designed for use in dry, interior, noncorrosive environments or temporary outdoor applications.

Features

- Tested in accordance with ACI 355.2, AC193 and AC106
- Qualified for static and seismic loading conditions
- Thread design undercuts to efficiently transfer the load to the base material
- Standard fractional sizes
- Specialized heat-treating process creates tip hardness for better cutting without compromising the ductility
- No special drill bit required — designed to install using standard-sized ANSI tolerance drill bits
- Hex-washer head requires no separate washer, unless required by code, and provides a clean installed appearance
- Removable — ideal for temporary anchoring (e.g. formwork, bracing) or applications where fixtures may need to be moved
- Zinc-plated model is for use in dry interior environments only
- Mechanically galvanized models are code listed for exterior applications

Codes: ICC-ES ESR-2713 (concrete); ICC-ES ESR-1056 (masonry); City of LA Supplement within ESR-2713 (concrete); City of LA Supplement within ESR-1056 (masonry); Florida FL15730 (concrete and masonry); FM 3017082, 3035761 and 3043442; Multiple DOT listings

Material: Carbon steel

Coating: Zinc plated or mechanically galvanized.
Visit strongtie.com/info for corrosion information

Installation

 Holes in steel fixtures to be mounted should match the diameter specified in the table below.

Use a Titen HD screw anchor one time only — installing the anchor multiple times may result in excessive thread wear and reduce load capacity.

 Do not use impact wrenches to install into hollow CMU.

 **Caution:** Oversized holes in base material will reduce or eliminate the mechanical interlock of the threads with the base material and reduce the anchor's load capacity.

1. Drill a hole in the base material using a carbide drill bit the same diameter as the nominal diameter of the anchor to be installed. Drill the hole to the specified embedment depth plus minimum hole depth overdrill (see table below) to allow the thread tapping dust to settle, and blow it clean using compressed air. (Overhead installations need not be blown clean.) Alternatively, drill the hole deep enough to accommodate embedment depth and the dust from drilling and tapping.
2. Insert the anchor through the fixture and into the hole.
3. Tighten the anchor into the base material until the hex-washer head contacts the fixture.

Additional Installation Information

Titen HD Diameter (in.)	Wrench Size (in.)	Integrated Washer Nominal Diameter (in.)	Recommended Steel Fixture Hole Size (in.)	Minimum Hole Depth Overdrill (in.)
¼	⅜	½	⅜ to ⅞	⅛
⅜	⅝	¾	½ to ⅞	¼
½	¾	1	⅝ to 1 ⅛	½
⅝	1 ⅛	1 ¼	¾ to 1 ¾	½
¾	1 ½	1 ½	⅞ to 1 ⅝	½



Suggested fixture hole sizes are for structural steel thicker than 12 gauge only. Larger holes are not required for wood or thinner cold-formed steel members.



Serrated teeth on the tip of the Titen HD screw anchor facilitate cutting and reduce installation torque.

Titen HD
Screw Anchor

Installation Sequence



Minimum overdrill. See table.

Titen HD® Heavy-Duty Screw Anchor

Titen HD Anchor Product Data — Zinc Plated¹

Size (in.)	Model No.	Drill Bit Dia. (in.)	Wrench Size (in.)	Quantity	
				Box	Carton
¼ x 1½	THDB25178H	¼	¾	100	500
¼ x 2¾	THDB25234H	¼	¾	50	250
¼ x 3	THDB25300H	¼	¾	50	250
¼ x 3½	THDB25312H	¼	¾	50	250
¼ x 4	THDB25400H	¼	¾	50	250
⅜ x 1¾	THD37134H ^{2,3}	⅜	⅝	50	250
⅜ x 2½	THD37212H ^{2,3}	⅜	⅝	50	200
⅜ x 3	THD37300H	⅜	⅝	50	200
⅜ x 4	THD37400H	⅜	⅝	50	200
⅜ x 5	THD37500H	⅜	⅝	50	100
⅜ x 6	THD37600H	⅜	⅝	50	100
½ x 3	THD50300H ^{2,4}	½	¾	25	100
½ x 4	THD50400H	½	¾	20	80
½ x 5	THD50500H	½	¾	20	80
½ x 6	THD50600H	½	¾	20	80
½ x 6½	THD50612H	½	¾	20	40
½ x 8	THD50800H	½	¾	20	40
½ x 12	THD501200H	½	¾	5	25
½ x 13	THD501300H	½	¾	5	25
½ x 14	THD501400H	½	¾	5	25
½ x 15	THD501500H	½	¾	5	25
⅝ x 4	THDB62400H ^{2,4}	⅝	1⅝	10	40
⅝ x 5	THDB62500H	⅝	1⅝	10	40
⅝ x 6	THDB62600H	⅝	1⅝	10	40
⅝ x 6½	THDB62612H	⅝	1⅝	10	40
⅝ x 8	THDB62800H	⅝	1⅝	10	20
⅝ x 10	THDB62100H	⅝	1⅝	10	20
¾ x 4	THD75400H ^{2,5}	¾	1⅞	10	40
¾ x 5	THD75500H	¾	1⅞	5	20
¾ x 6	THDT75600H	¾	1⅞	5	20
¾ x 7	THD75700H	¾	1⅞	5	10
¾ x 8½	THD75812H	¾	1⅞	5	10
¾ x 10	THD75100H	¾	1⅞	5	10

- Length of anchor is measured from underside of the head to end of anchor.
- These models do not meet minimum embedment depth requirements for strength design.
- Installation torque shall not exceed 25 ft.-lb. using a manual torque wrench or maximum torque rating of 100 ft.-lb. when installed with impact wrench.
- Installation torque shall not exceed 50 ft.-lb. using a manual torque wrench or maximum torque rating of 100 ft.-lb. when installed with impact wrench.
- Installation torque shall not exceed 50 ft.-lb. using a manual torque wrench or maximum torque rating of 135 ft.-lb. when installed with impact wrench.

Titen HD Anchor Product Data — Mechanically Galvanized

Size (in.)	Model No.	Drill Bit Dia. (in.)	Wrench Size (in.)	Quantity	
				Box	Carton
⅜ x 3	THD37300HMG	⅜	⅝	50	200
⅜ x 4	THD37400HMG			50	200
⅜ x 5	THD37500HMG			50	100
⅜ x 6	THD37600HMG			50	100
½ x 4	THD50400HMG	½	¾	20	80
½ x 5	THD50500HMG			20	80
½ x 6	THD50600HMG			20	80
½ x 6½	THD50612HMG			20	40
½ x 8	THD50800HMG			20	40
⅝ x 5	THDB62500HMG	⅝	1⅝	10	40
⅝ x 6	THDB62600HMG			10	40
⅝ x 6½	THDB62612HMG			10	40
⅝ x 8	THDB62800HMG			10	20
¾ x 6	THDT75600HMG	¾	1⅞	5	20
¾ x 8½	THD75812HMG			5	10
¾ x 10	THD75100HMG			5	10

Mechanical galvanizing meets ASTM B695, Class 65, Type 1. Visit strongtie.com/info for more corrosion information.

Titen HD is available in Type 304 and Type 316 stainless; see strongtie.com for sizes.

Titen HD® Heavy-Duty Screw Anchor

Table 1: Titen HD — Tension Loads Attaching Cold-Formed Steel to Normal-Weight Concrete (lb.)⁶


Anchor Size (in.)	Drill Bit (in.)	Edge Distance (in.)	End Distance (in.)	Min. Emb. Depth (in.)	Concrete Thickness (in.)	Spacing (in.)	Concrete ≥ 2,500 psi ^{3,4}				Cold-Formed Steel (ASD) ⁵				
							LRFD ^{1,9,10} (Seismic)	LRFD ^{1,8,10} (Wind)	ASD ^{2,9,10} (Seismic)	ASD ^{2,8,10} (Wind)	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	68 mil (14 ga.)	
¼ x 1⅞	¼	1½	3	1⅝	¾	6	470	630	330	375	390	505	920	1,160	
		1¾	3	1⅝	¾	6	530	705	370	425					
		3	3	1⅝	¾	6	540	715	375	430					
1½		3	2½	¾	6	725	965	510	580						
1¾		3	2½	¾	6	790	1,050	555	630						
3		3	2½	¾	6	930	1,240	650	745						
¼ x 2¾	¾	1¾	3	2½	4	6	600	800	420	480	585	760	1,380	1,740	
½ x 4		½	1¾	4	¾	5	8	940	1,255	660	755	585	760	1,380	1,740
			3	4	¾	5	8	1,320	1,760	925	1,055				
	4		4	¾	5	8	1,490	1,985	1,045	1,190					

See footnotes on p. 180.


Table 2: Titen HD — Shear Loads Perpendicular to Edge in Normal-Weight Concrete (lb.)⁶

Anchor Size (in.)	Drill Bit (in.)	Edge Distance (in.)	End Distance (in.)	Min. Emb. Depth (in.)	Concrete Thickness (in.)	Spacing (in.)	Concrete ≥ 2,500 psi ^{3,4}				Cold-Formed Steel (ASD) ⁵			
							LRFD ^{1,9,10} (Seismic)	LRFD ^{1,8,10} (Wind)	ASD ^{2,9,10} (Seismic)	ASD ^{2,8,10} (Wind)	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	68 mil (14 ga.)
¼ x 1⅞	¼	1½	3	1⅝	¾	6	305	305	215	185	350	455	830	1,045
		1¾	3	1⅝	¾	6	385	385	270	230				
		3	3	1⅝	¾	9	555	555	390	335				
1½		3	2½	¾	6	340	340	235	205					
1¾		3	2½	¾	6	425	425	300	255					
3		3	2½	¾	9	635	635	445	380					
¾ x 3	¾	1¾	7	2½	4	5¼	475	475	335	285	510	685	1,240	1,565
		3	7	2½	4	9	1,000	1,000	700	600				
½ x 4	½	1¾	8	¾	5	5¼	545	545	380	325	595	880	1,655	2,085
		3	8	¾	5	9	1,225	1,225	860	735				

See footnotes on p. 180.



Edge and End Distances for Titen HD in Concrete Slab Corner Condition (reference table 1, 2 and 3)



Edge and End Distances for Titen HD in Concrete Over Metal Deck (reference table 4, 5 and 6)

Titen HD® Heavy-Duty Screw Anchor

Table 3: Titen HD — Shear Loads Parallel to Edge in Normal-Weight Concrete (lb./ft.)⁶

Anchor Size (in.)	Drill Bit (in.)	Edge Distance (in.)	End Distance (in.)	Min. Emb. Depth (in.)	Concrete Thickness (in.)	Spacing	Concrete ≥ 2,500 psi ^{3,4}				Cold-Formed Steel (ASD) ⁵			
							LRFD ^{1,9,10} (Seismic)	LRFD ^{1,8,10} (Wind)	ASD ^{2,9,10} (Seismic)	ASD ^{2,8,10} (Wind)	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	68 mil (14 ga.)
¼ x 1⅞	¼	1½	3	1⅞	¾	0' – 6"	790	790	550	470	700	910	1,660	2,090
						0' – 8"	595	595	415	355	525	685	1,245	1,570
						1' – 0"	395	395	275	235	350	455	830	1,045
						1' – 4"	295	295	205	175	265	340	625	785
						2' – 0"	200	200	140	120	175	230	415	525
						2' – 8"	150	150	105	90	130	170	310	390
						4' – 0"	100	100	70	60	90	115	210	260
6' – 0"	65	65	45	40	60	75	140	175						
¼ x 1⅞	¼	3	3	1⅞	¾	0' – 9"	740	740	520	445	465	605	1,105	1,395
						1' – 0"	555	555	390	335	350	455	830	1,045
						1' – 4"	415	415	295	250	265	340	625	785
						2' – 0"	280	280	195	170	175	230	415	525
						2' – 8"	210	210	145	125	130	170	310	390
						4' – 0"	140	140	100	85	90	115	210	260
						6' – 0"	95	95	65	55	60	75	140	175
¼ x 2¾	¼	3	3	2½	¾	0' – 9"	845	845	595	505	465	605	1,105	1,395
						1' – 0"	635	635	445	380	350	455	830	1,045
						1' – 4"	475	475	335	285	265	340	625	785
						2' – 0"	320	320	225	190	175	230	415	525
						2' – 8"	240	240	165	145	130	170	310	390
						4' – 0"	160	160	110	95	90	115	210	260
						6' – 0"	105	105	75	65	60	75	140	175
¾ x 3	¾	3	7	2½	4	0' – 8"	1,770	1,770	1,240	1,060	765	1,030	1,860	2,350
						1' – 0"	1,180	1,180	825	710	510	685	1,240	1,565
						1' – 4"	885	885	620	530	385	515	930	1,175
						2' – 0"	590	590	415	355	255	340	620	780
						2' – 8"	445	445	310	265	190	255	465	585
						4' – 0"	295	295	205	175	130	170	310	390
						6' – 0"	195	195	135	115	85	115	205	260
½ x 4	½	3	8	¾	5	0' – 8"	2,505	2,505	1,755	1,505	895	1,320	2,485	3,130
						1' – 0"	1,670	1,670	1,170	1,000	595	880	1,655	2,085
						1' – 4"	1,255	1,255	880	755	445	660	1,240	1,565
						2' – 0"	835	835	585	500	300	440	830	1,045
						2' – 8"	625	625	440	375	220	330	620	780
						4' – 0"	420	420	295	250	150	220	415	520
						6' – 0"	280	280	195	170	100	145	275	350

See footnotes on p. 180.

Titen HD® Heavy-Duty Screw Anchor

Table 4: Titen HD — Tension Loads Attaching Cold-Formed Steel to Top of Normal-Weight Concrete over Metal Deck (lb.)^{6,11}

Anchor Size (in.)	Drill Bit (in.)	Min. Edge Distance (in.)	Min. End Distance (in.)	Emb. Depth (in.)	Min. Concrete Thickness (in.)	Spacing (in.)	Concrete ≥ 3,000 psi ^{3,4}				Cold-Formed Steel (ASD) ⁵			
							LRFD ^{1,9,10} (Seismic)	LRFD ^{1,8,10} (Wind)	ASD ^{2,9,10} (Seismic)	ASD ^{2,8,10} (Wind)	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	68 mil (14 ga.)
¼ x 1 ½	¼	3 ½	3 ¾	1 ½	2 ½	3 ½	580	775	405	545	390	505	920	1,160
¾ x 3	¾	3	7 ¼	2 ½	3 ¾	3	660	880	460	615	585	760	1,380	1,740

See footnotes below.

Table 5: Titen HD — Shear Loads Perpendicular to Edge in Top of Normal-Weight Concrete over Metal Deck (lb.)^{6,11}

Anchor Size (in.)	Drill Bit (in.)	Min. Edge Distance (in.)	Min. End Distance (in.)	Emb. Depth (in.)	Min. Concrete Thickness (in.)	Spacing (in.)	Concrete ≥ 3,000 psi ^{3,4}				Cold-Formed Steel (ASD) ⁵			
							LRFD ^{1,9,10} (Seismic)	LRFD ^{1,8,10} (Wind)	ASD ^{2,9,10} (Seismic)	ASD ^{2,8,10} (Wind)	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	68 mil (14 ga.)
¼ x 1 ½	¼	3 ½	3 ¾	1 ½	2 ½	3 ½	450	450	315	315	350	455	830	1,045
¾ x 3	¾	3	7 ¼	2 ½	3 ¾	3	660	660	460	460	510	685	1,240	1,565

See footnotes below.

Table 6: Titen HD — Shear Loads Parallel to Edge in Top of Normal-Weight Concrete over Metal Deck (lb./ft.)^{6,11}

Anchor Size (in.)	Drill Bit (in.)	Min. Edge Distance (in.)	Min. End Distance (in.)	Emb. Depth (in.)	Min. Concrete Thickness (in.)	Spacing (in.)	Concrete ≥ 3,000 psi ^{3,4}				Cold-Formed Steel (ASD) ⁵			
							LRFD ^{1,9,10} (Seismic)	LRFD ^{1,8,10} (Wind)	ASD ^{2,9,10} (Seismic)	ASD ^{2,8,10} (Wind)	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	68 mil (14 ga.)
¼ x 1 ½	¼	3 ½	3 ¾	1 ½	2 ½	1'-0"	635	635	445	445	350	455	830	1,045
						1'-4"	475	475	335	335	265	340	625	785
¾ x 3	¾	3	7 ¼	2 ½	3 ¾	0'-9"	1,590	1,590	1,115	1,115	680	915	1,655	2,085
						1'-0"	1,195	1,195	835	835	510	685	1,240	1,565
						1'-4"	895	895	625	625	385	515	930	1,175

1. Anchorage designs conform to ACI 318-19 Chapter 17 and assume cracked concrete with no supplementary reinforcement.
2. Allowable Stress Design (ASD) values are obtained by multiplying Load Resistance Factor Design (LRFD) capacities by 0.7 for seismic and 0.6 for wind.
3. Anchor is considered as an individual anchor without influence from other anchors. For tables 2 and 3, shear load is applied perpendicular and parallel to the edge of concrete respectively.
4. Concrete shall have a minimum f'_c of 2,500 psi; 3,000 psi for concrete over metal deck. Reference ICC-ES ESR-2713 for further information.
5. Cold-Formed Steel (CFS) tension pullover values are based on AISI S-100, Eq. J4.4.2-1, $d_w = 0.50"$ (¼" THD), $d_w = 0.75"$ (¾" and ½" THD) and $\Omega = 3.0$. Reference General Notes for CFS properties. To convert from ASD to LRFD multiply value by 1.5. Tension values where applicable do not account for weak axis bending in the sill member.
6. Governing load is the lesser of concrete and CFS.
7. For conditions not covered by this table, use the Simpson Strong-Tie® Anchor Designer™ software available at strongtie.com.
8. Wind design includes SDC A & B.
9. The listed load values are governed by a brittle failure mode, the Designer shall consider ductility requirements of ACI 318-19 Section 17.10.5.3 for designing anchorage in Seismic Design Category C-F.
10. For installation in sand-lightweight concrete, concrete values shall be multiplied by 0.68.
11. For tables 4, 5 and 6, metal deck configuration to comply with Figure 5 of ICC-ES ESR-2713.

For Titen HD screws used in place of Cast-In-Place J-bolts for light frame construction, see the easy 1-to-1 substitution letter L-A-THDCFS1TO125 at strongtie.com.

Powder-Actuated Fasteners

PDPA — Drive Pin: 0.157" Shank Diameter, 0.300" Head Diameter

Model No.	Pin		Quantity		Compatible Powder-Actuated Tools	
	Length (in.)	Shank Dia. (in.)	Pack	Carton	Simpson Strong-Tie	Others
PDPA-50	½	0.157	100	1,000	PTP-27L PT-27 PT-22A PT-22HA	Other major brands
PDPA-50K	½ knurled					
PDPA-62K	⅝ knurled					
PDPA-75	¾					
PDPA-100	1					
PDPA-106	1 ⅙					
PDPA-125	1 ¼					
PDPA-131	1 ⅝					
PDPA-150	1 ½					
PDPA-187	1 ⅞					
PDPA-200	2					
▶ PDPA-200MG	2					
PDPA-250	2 ½					
▶ PDPA-250MG	2 ½					
PDPA-287	2 ⅞					
▶ PDPA-287MG	2 ⅞					

▶ **Note:** The PDPA-200MG, PDPA-250MG and PDPD-287MG models have mechanically galvanized (Class 65) finish.



PDPA

PDPAT — Drive Pin with Top Hat: 0.157" Shank Diameter, 0.300" Head Diameter

Model No.	Pin		Quantity		Compatible Powder-Actuated Tools	
	Length (in.)	Shank Dia. (in.)	Pack	Carton	Simpson Strong-Tie	Others
PDPAT-50K	½ knurled	0.157	100	1,000	PTP-27L PT-27 PT-22A PT-22HA	Other major brands
PDPAT-62KP	⅝ knurled					
PDPAT-75	¾					
PDPAT-100	1					

Note: PDPAT-62KP is a point protrusion pin. The point of the pin is designed to slightly protrude from the tool to aid in hole location.




PDPAT-62KP

Powder-Actuated Fasteners


PDPA and PDPAT Pins — Allowable Shear and Tension Loads

Model Type	Dia. (in.)	Pin Spacing	Base Material									Attached Material					
			Normal-Weight Concrete ¹			Sand-Lightweight Concrete Filled Steel Deck ^{6,7}			A36 Steel ²			Cold-Formed Steel ³					
			Emb. Depth (in.)	2,500 psi	4,000 psi	Emb. Depth (in.)	Concrete ¹ (Top)	Lower Flute ⁹ (Bottom)	3/16"	1/4"	3/8"	1/2"	3/4"	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	
Allowable Shear Load^{4,5,13} (lb./ft.)																	
PDPA PDPAT	0.157	0'-6"	1	570	620	1	450	560	820	730	770 ¹⁰	770 ¹⁰	650 ⁹	760 ¹²	990 ¹²	1,800 ¹²	
			1 1/4	720	840	1 1/4	840	640									
		0'-8"	1	430	465	1	340	420	615	550	580 ¹⁰	580 ¹⁰	490 ⁹	570 ¹²	745 ¹²	1,350 ¹²	
			1 1/4	540	630	1 1/4	630	480									
		1'-0" or -	1	285	310	1	225	280	410	365	385 ¹⁰	385 ¹⁰	325 ⁹	380 ¹²	495 ¹²	900 ¹²	
			1 1/4	360	420	1 1/4	420	320									
		2'-0"	1	145	155	1	115	140	205	185	195 ¹⁰	195 ¹⁰	165 ⁹	190 ¹²	250 ¹²	450 ¹²	
			1 1/4	180	210	1 1/4	210	160									
		3'-0"	1	95	105	1	75	95	135	120	130 ¹⁰	130 ¹⁰	110 ⁹	125 ¹²	165 ¹²	300 ¹²	
			1 1/4	120	140	1 1/4	140	105									
		Allowable Tension Load^{4,5} (lb.)															
		0.157	—	1	210	310	1	150	145	260	370	3801 ⁰	530 ¹⁰	195 ⁹	225 ¹¹	295 ¹¹	535 ¹¹
1 1/4	320			380	1 1/4	320	170										

- For concrete the minimum edge distance and spacing is 3 1/2" and 5", respectively.
- For A36 steel, the minimum edge distance and spacing is 0.5" and 1", respectively. Entire pointed portion of the fastener must fully penetrate steel base material unless noted otherwise.
- Cold-formed steel (CFS) values are based on AISI-S100. Reference General Notes for CFS properties.
- Governing load is the lesser of the base material and CFS.
- Allowable loads are based on ICC-ES ESR-2138.
- Concrete shall have a minimum compressive strength of $f'_c = 3,000$ psi.
- For steel deck, the minimum depth and thickness is 3" and 33 mil (20 ga.), respectively. Steel deck must have a minimum yield strength of 38,000 psi.
- For installation through steel deck, the minimum edge and end distance is 1 1/2" and 4", respectively with 4" minimum spacing.
- Based upon a minimum penetration depth of 0.46" (11.7 mm).
- For applications to structural steel, the fastener must be driven to where at least some of the point of the fastener penetrates through the steel substrate.
- The following CFS allowable tension loads may be used for PDPAT: 390 lb. (33 mil), 505 lb. (43 mil), 915 lb. (54 mil).
- CFS allowable shear load may be multiplied by 1.15 for PDPAT fastener.
- Shear loads listed do not account for indirect tension due to eccentricity of load at the deflection track. Designer to evaluate combined loading as needed.
- A "-" in the pin spacing means no spacing or load directly at fastener.



PDPA In Lightweight Concrete Over Steel Deck



Typical Powder-Actuated Fastener Installation

Powder-Actuated Fasteners

PDPA in 4,000 psi Normal-Weight Concrete

Fastener	Shank Diameter (in.)	Fastener Length (in.)	Edge Distance (in.)	Spacing in Load Dir. (in.)	Track Width (in.)	Number of Fasteners	Allowable Shear Load (lb.)
PDPA-100	0.157	1	2¼	—	3½	1	240
				¾		2	310
				—	6	1	240
				2¼		2	510
PDPA-125		1.25	2¼	—	3½	1	325
				¾		2	490
				—	6	1	325
				2¼		2	590

1. Allowable loads are based on fasteners installed through 16 ga. cold-formed steel ($F_y > 33$ ksi).
2. Minimum concrete thickness must be three times the fastener length.
3. Edge distance and spacing are shown in figures below.

PDPA in 3,000 psi Sand-Lightweight Concrete

Fastener	Shank Diameter (in.)	Fastener Length (in.)	Edge Distance (in.)	Spacing in Load Dir. (in.)	Track Width (in.)	Number of Fasteners	Allowable Shear Load (lb.)
PDPA-100	0.157	1	2¼	—	3½	1	235
				¾		2	310
				—	6	1	235
				2¼		2	445
PDPA-125		1.25	2¼	—	3½	1	245
				¾		2	455
				—	6	1	245
				2¼		2	530
PDPA-150	1.5	2¼	—	3½	1	245	
			¾		2	470	
			—	6	1	245	
			2¼		2	530	

1. Allowable loads are based on fasteners installed through 16 ga. cold-formed steel ($F_y > 33$ ksi).
2. Minimum concrete thickness must be three times the fastener length.
3. Edge distance and spacing are shown in figures below.




Figure 1: 3½" Track – One Fastener




Figure 2: 3½" Track – Two Fasteners




Figure 3: 6" Track – One Fastener




Figure 4: 6" Track – Two Fasteners

SABR™ Anchor Bolt

The new code-listed SABR anchor bolt is a cast-in-place anchor providing five different diameters for Simpson Strong-Tie® holdowns.

The hot-forged anchor bolt's one-piece sweep design maximizes its position in the concrete, providing increased tension capacity. In addition, all five anchor diameters are designed with a 6" threaded section that accommodates all seat heights of Simpson Strong-Tie holdowns. To simplify product specification, the SABR replaces both the SB and SSTB® models. In most common applications, SABR has significantly higher loads than previous models.

Features and benefits:


- Single anchor solution for all foundation types
- Engineers and contractors can confidently choose the right anchor based on diameter for any required condition
- Stamped model information on the head makes it easy to identify and align for installation
- Having a single length for each diameter simplifies specification and makes it easier for dealers to order and inventory
- Sweep design allows placement near the edge of concrete while increasing tension capacity
- One-piece, hot-forged design eliminates potential loss of components
- Available in HDG (hot-dip galvanized) for additional corrosion resistance

The SABR anchor bolt is fast and easy to install, widely available and backed by our expert service and support.


Material: ASTM F1554 Grade 55

Finish: None. May be ordered in HDG; contact Simpson Strong-Tie.

Codes: ICC-ES ESR-2611, FL, LA



Model No.	Dimensions (in.)		
	Diameter	Length	Min. Embed (l_e)
SABR5/8X24	5/8	24	18
SABR3/4X26	3/4	26	20
SABR7/8X28	7/8	28	22
SABR1X30	1	30	24
SABR114X32	1 1/4	32 1/2	26 1/2




Plan View of SABR Placement in Concrete

SABR™ Anchor Bolt


SABR Bolts at Stemwall

Model No.	Dimensions (in.)				Allowable Tension Loads (lb.)						Code Ref.
	Stemwall Width	Dia.	Length	Min. Embed. (l_e)	Wind and SDC A & B			SDC C-F			
					Middle	Corner	End	Middle	Corner	End	
SABR5/8X24	6	5/8	24	18	8,630	7,560	6,360	8,630	6,300	5,575	IBC, FL, LA
SABR3/4X26	8	3/4	26	20	12,425	7,560	7,175	10,395	6,555	6,290	
SABR7/8X28	8	7/8	28	22	16,670	10,325	7,175	14,615	9,055	6,290	
SABR1X30	8	1	30	24	16,670	12,360	8,300	14,615	10,840	7,280	
SABR114X32	8	1 1/4	32 1/2	26 1/2	18,105	12,360	8,300	14,615	10,840	7,280	

1. Minimum end distances for SABR bolts are as shown in graphics.
2. To obtain LRFD values, multiply ASD seismic load values by 1.43 and wind load values by 1.67.
3. Per Section 1613 of the IBC, detached one- and two-story dwellings in SDC C may use "Wind and SDC A & B" allowable loads.
4. Midwall loads apply when anchor is 1.5 l_e or greater from the end. For bolts acting in tension simultaneously, the minimum bolt center-to-center spacing is 3 l_e .



Stemwall Plan Views



Perspective View


For more application details and allowable load tables, see go.strongtie.com/sabr-details

RFB Retrofit Bolts

RFBs are precut threaded rod, supplied with nut and washer, to use with anchoring adhesives to anchor in to existing concrete and masonry. Each end of the threaded rod is stamped with rod length in inches and color-coded indicating the grade or type of steel for quick and easy identification post-installation. For ½" diameters and larger, our distinctive No-Equal® symbol is also stamped. When used with a Simpson Strong-Tie® adhesive, it offers a complete engineered anchoring system.

Material: ASTM F1554 Grade 36, 55 and 105 (B7); Stainless Steel Types 304 and 316

Finish (Carbon Steel only): Zinc plated, hot-dip galvanized



Grade 36

Grade 55

Grade 105

SS304

SS316

Identification (Head Stamp)

Retrofit Bolt Ordering Information

Size. (in.)	Carbon Steel					Stainless Steel	
	Grade 36		Grade 55	Grade 105		Type 304	Type 316
	Zinc	HDG	Zinc	Zinc	HDG		
¾ x 4	RFB#3X4	RFB#3X4HDG	RFB#3X4-55	—	—	—	—
¾ x 6	RFB#3X6	—	RFB#3X6-55	RFB#3X6-105	RFB#3X6-105HDG	RFB#3X6-SS304	RFB#3X6-SS316
¾ x 8	RFB#3X8	—	RFB#3X8-55	—	—	—	—
½ x 4	RFB#4X4	—	RFB#4X4-55	—	—	—	—
½ x 5	RFB#4X5	RFB#4X5HDG	RFB#4X5-55	—	—	—	—
½ x 6	RFB#4X6	RFB#4X6HDG	RFB#4X6-55	RFB#4X6-105	RFB#4X6-105HDG	RFB#4X6-SS304	RFB#4X6-SS316
½ x 7	RFB#4X7	RFB#4X7HDG	—	—	—	—	—
½ x 8	RFB#4X8	RFB#4X8HDG	RFB#4X8-55	—	RFB#4X8-105HDG	RFB#4X8-SS304	RFB#4X8-SS316
½ x 10	RFB#4X10	RFB#4x10HDG	RFB#4X10-55	—	—	RFB#4X10-SS304	RFB#4X10-SS316
⅝ x 5	RFB#5X5	RFB#5X5HDG	RFB#5X5-55	—	—	—	—
⅝ x 8	RFB#5X8	RFB#5X8HDG	RFB#5X8-55	RFB#5X8-105	RFB#5X8-105HDG	RFB#5X8-SS304	RFB#5X8-SS316
⅝ x 10	RFB#5X10	RFB#5X10HDG	RFB#5X10-55	—	RFB#5X10-105HDG	—	RFB#5X10-SS316
⅝ x 12	—	RFB#5X12HDG	—	—	—	—	—
⅝ x 16	RFB#5X16	RFB#5X16HDG	RFB#5X16-55	—	—	—	—
¾ x 6	RFB#6X6	—	RFB#6X6-55	—	—	—	—
¾ x 8	RFB#6X8	RFB#6X8HDG	RFB#6X8-55	—	—	—	—
¾ x 10½	RFB#6X10.5	RFB#6X10.5HDG	RFB#6X10.5-55	RFB#6X10.5-105	RFB#6X10.5-105HDG	RFB#6X10.5-SS304	RFB#6X10.5-SS316
7⁄8 x 16	—	—	RFB#7X16-55	RFB#7X16-105	—	—	—
1 x 12	—	—	—	RFB#8X12-105	—	—	—
1 x 14	—	—	—	RFB#8X14-105	—	—	—

- All listed sizes are available in single quantities and cartons. Some sizes also available in retail packs of 2.
- For full package quantity details, reference strongtie.com.

Retrofit Bolt Steel Design Strength (ACI 318-19 Chapter 17)

Dia. (in.)	Carbon Steel						Stainless Steel	
	Grade 36		Grade 55		Grade 105		Types 304/ 316	
	Tensile, Ø N _{sa} (lb.)	Shear, Ø V _{sa} (lb.)						
¾	3,395	1,765	4,390	2,280	7,315	3,805	5,850	3,040
½	6,175	3,210	7,990	4,155	13,315	6,925	10,650	5,540
⅝	9,835	5,110	12,715	6,610	21,190	11,020	16,950	8,815
¾	14,530	7,555	18,790	9,770	31,315	16,285	21,295	11,075
7⁄8	20,095	10,450	25,990	13,515	43,315	22,525	29,455	15,315
1	26,365	13,710	34,090	17,725	56,815	29,545	38,635	20,090

- Tensile values are derived in accordance with ACI 318-19 Section 17.6.1.2 with strength reduction factor, Ø, of 0.75 for ductile steel element in tension.
- Shear values are derived in accordance with ACI 318-19 Section 17.7.1.2 with strength reduction factor, Ø, of 0.65 for ductile steel element in shear.
- This table includes only the design strength of steel element. Design strengths of substrate and adhesive bond must be taken into consideration to determine anchorage design strength.

PAB® Pre-assembled Anchor Bolt

The PAB anchor bolt is a versatile cast-in-place anchor bolt ideal for high-tension-load applications, such as rod systems and shearwalls. It features a plate washer, at the embedded end, sandwiched between two fixed hex nuts and a head stamp for easy identification after the pour.

- Available in diameters from 1/2" to 1 1/4" in lengths from 12" to 36" (in 6" increments)
- Available in standard and high-strength steel
- Head stamp contains the No Equal® sign, diameter designation and an "H" on high-strength rods

Material:

Standard Steel — ASTM F1554 Grade 36, A36 or A307; Fu = 58 ksi

High-Strength Steel (up to 1" dia.) — ASTM A449; Fu = 120 ksi

High-Strength Steel (1 1/8" and 1 1/4" dia.) — ASTM A193 B7 or F1554 Grade 105; Fu = 125 ksi

Finish: None. May be ordered in HDG; contact Simpson Strong-Tie.

Installation:

- On HDG PABs, chase the threads to use standard nuts or couplers or use overtapped products in accordance with ASTM A563; for example, Simpson Strong-Tie® NUT^{5/8}-OST, NUT^{7/8}-OST, CNW^{5/8}-OST, CNW^{7/8}-OST. OST couplers are typically oversized on one end of the coupler nut only and will be marked with an "O" on oversized side. Couplers may be special ordered with both ends oversized. Contact Simpson Strong-Tie.

Related Software

The Simpson Strong-Tie Anchor Designer™ Software analyzes and suggests anchor solutions using the ACI 318 strength-design methodology (or CAN/CSA A23.3 Annex D Limit States Design methodology). It provides cracked and uncracked-concrete anchorage solutions for numerous Simpson Strong-Tie mechanical and adhesive anchors as well as the PAB anchor bolt. With its easy-to-use graphical user interface, the software makes it easy for the designer to identify anchorage solutions without having to perform time-consuming calculations by hand. See strongtie.com/software.

How to Specify and Order:


- When calling out PAB anchor bolts, substitute the desired length after the "-" in the Root Model Number
- For a 5/8" x 18" anchor bolt, the model number would be PAB5-18 (or PAB5H-18 for high strength)

PAB Anchor Bolt

Diameter (in.)	Plate Washer Size (in.)	l ₁ (in.)	Root Model No.		Lengths (in.)
			Standard Strength	High Strength	
1/2	3/8 x 1 1/2 x 1 1/2	1 1/8	PAB4-XX	PAB4H-XX	12" to 36" (in 6" increments)
5/8	1/2 x 1 3/4 x 1 3/4	1 3/8	PAB5-XX	PAB5H-XX	
3/4	1/2 x 2 1/4 x 2 1/4	1 1/2	PAB6-XX	PAB6H-XX	
7/8	1/2 x 2 1/2 x 2 1/2	1 5/8	PAB7-XX	PAB7H-XX	
1	5/8 x 3 x 2 3/4	1 7/8	PAB8-XX	PAB8H-XX	
1 1/8	5/8 x 3 1/2 x 3 1/4	2	PAB9-XX	PAB9H-XX	
1 1/4	3/4 x 3 1/2 x 3 1/2	2 1/4	PAB10-XX	PAB10H-XX	

1. Lengths greater than 36" are available as a special order.


2. Plate washers are designed to develop the capacity of the bolt.



Naming Legend



*Units in 1/8" Increments
(Ex: 9 = 9/8" or 1 1/8")



Design loads are calculated using a full shear cone. Coverage on each side of the bolt shall be a minimum of F or reductions must be taken.

PAB® Pre-assembled Anchor Bolt

PAB Anchor Bolt – Anchorage Solutions

Design Criteria	Diameter (in.)	Anchor Bolt	2,500 psi Concrete				3,000 psi Concrete			
			Dimensions (in.)		Tension Load (lb.)		Dimensions (in.)		Tension Load (lb.)	
			d _e	F	ASD	LRFD	d _e	F	ASD	LRFD
Wind	½	PAB4	3½	6½	4,270	6,405	3½	6½	4,270	6,405
	⅝	PAB5	4	7½	5,535	9,230	3½	6½	5,175	8,625
			5	9	6,675	10,010	4½	8	6,675	10,010
	¾	PAB6	5½	9½	8,395	13,990	5	9	8,165	13,605
			6½	11	9,685	14,530	6	10½	9,685	14,530
	⅞	PAB7	6	10½	9,550	15,915	5½	9½	9,380	15,635
			8	13½	13,400	20,095	7½	12½	13,400	20,095
		PAB7H	9	15	16,175	26,960	8½	14	16,425	27,370
	1	PAB8	13½	21½	27,720	41,580	12½	20	27,720	41,580
			8	13½	14,300	23,835	7½	13	14,425	24,040
		PAB8H	9½	16	17,575	26,360	9	15	17,575	26,360
	1½	PAB9	10½	17½	20,420	34,035	10	16½	20,965	34,945
			15½	25	36,360	54,540	15	24	36,360	54,540
	1¼	PAB10	9	15½	16,870	28,115	8	14	15,885	26,475
11½			19	22,125	33,190	10½	17½	22,125	33,190	
Seismic	½	PAB4	4	7	4,270	6,405	4	7	4,270	6,405
	⅝	PAB5	5½	9½	6,675	10,010	5	9	6,675	10,010
	¾	PAB6	6½	11	9,090	12,990	6	10½	8,985	12,835
			7	12	9,685	14,530	6½	11	9,685	14,530
	⅞	PAB7	8	13½	12,110	17,300	7½	12½	12,190	17,415
			9	15	13,400	20,095	8½	14	13,400	20,095
		PAB7H	13½	21½	25,295	36,135	12½	20	24,595	35,135
	1	PAB8	14½	23	27,720	41,580	14	22½	27,720	41,580
			9½	16	15,650	22,355	9	15	15,970	22,815
		PAB8H	10½	17½	17,575	26,360	10	16½	17,575	26,360
	1½	PAB9	16	25½	33,555	47,935	15	24	33,255	47,510
			17	27	36,360	54,540	16	25½	36,360	54,540
	1¼	PAB10	11½	19	20,420	29,170	10½	17½	19,785	28,270
			12½	20½	22,125	33,190	11½	19	22,125	33,190
	1	PAB10	13	21½	25,095	35,850	12½	20½	25,920	37,030
			14½	23½	28,100	42,150	13½	22	28,100	42,150

- Anchorage designs conform to ACI 318-19 and assume cracked concrete with no supplementary reinforcement.
- Seismic indicates Seismic Design Category C-F and designs comply with ACI 318-19, Section 17.10.5.3. Per Section 1613 of the 2012/2015/2018/2021/2024 IBC, detached one- and two-family dwellings in SDC C may use wind values.
- Wind includes Seismic Design Category A & B.
- Foundation dimensions are for anchorage only. Foundation design (size and reinforcement) by designer. The registered design professional may specify alternative embedment, footing size, and anchor bolt.
- Where tension loads are governed by anchor steel, the design provisions from AISC 360 are used to determine the tensile steel limit. LRFD values are calculated by multiplying the nominal AISC steel capacity by a 0.75 phi factor, and allowable values are calculated by dividing the AISC nominal capacity by a 2.0 omega factor.
- Where tension loads are governed by ACI 318 concrete limit, the Allowable Stress Design (ASD) values are obtained by multiplying Load Resistance Factor Design (LRFD) capacities by 0.7 for seismic and by 0.6 for wind.

Simpson Strong-Tie Software



ANCHOR DESIGNER™ for Concrete

Free Professional Strength Design Desktop Software

Overview

Perform anchorage design in accordance with the strength design provisions of ACI 318, CSA A23.3, EN 1992-4, or ETAG for cracked and uncracked concrete conditions.

New Features

User interface improvements simplify the design inputs, geometry verification and calculation results.


Multiple design management allows users to manage all designs within one project file for easy review and comparison of designs.

Load Wizard analyzes multiple load combinations and allows users to view the governing case.


Simplified Geometry option automatically adjusts anchor locations based on base plate edge distance and spacing inputs.

Multi-design feature quickly analyzes all possible anchor types and embedments, and displays a table of all passing results.


Simplified Geometry




Base Plate Thickness Calculator




Quick-Start Designs




Square/
Rectangular BP




Linear pattern




Holddown




Concrete over metal
deck — Bottom side



Concrete over metal
deck — Topside



User-defined
Templates



ANCHOR DESIGNER™ for Masonry

Free Professional Strength Design Web Application

Overview

Anchor Designer for Masonry performs anchorage design in accordance with the strength design provisions of ICC-ES AC508 for cracked and uncracked, grout filled and hollow concrete masonry units.

Features


Simple interface provides easy-to-enter masonry wall geometry, loading, and anchor type and pattern with real time 3D visualization and calculation results displayed.

Multi design feature displays a table of anchor pass/fail results, embedment depths, tension, shear, and combined interaction values.

User-defined templates streamline your standards.

Save design files locally to your device.


Masonry Construction Types



Grout Filled
CMU



Hollow
CMU



Solid Grouted
CMU






Ungrouted
CMU

Access ADC and ADM for free at strongtie.com/software

Simpson Strong-Tie® Fasteners for CFS Construction

Below is a list of Simpson Strong-Tie fasteners and tested base materials. This list does not represent the complete line of Simpson Strong-Tie offerings, but the most suitable fasteners for CFS construction.

✓ = Code listed ✓ = Tested — = Not tested

	Product	Single/ Collated	Fastened Materials						
			CFS to CFS	CFS to Structural Steel	Sheathing to CFS	Fiberglass Sheathing to CFS	Drywall to CFS	Wood to CFS	
Fasteners	Self-Drilling E Metal Screw 	#14 hex head L = 1"	Single	✓	—	—	—	—	—
	Strong-Drive® XL LARGE-HEAD METAL Screw 	#12 hex head L = 1 1/4"	Single/ collated	✓	✓	—	—	—	—
	Strong-Drive XM MEDIUM-HEAD METAL Screw 	#12 hex head L = 1 1/4"	Single/ collated	✓	✓	—	—	—	—
	Strong-Drive Self-Drilling X Metal Screw 	#10, #12 hex head L = 3/4" to 1 1/2"	Single/ collated	✓	✓	—	—	—	—
	Strong-Drive FPHSD FRAMING-TO-CFS Screw 	#10, #12 flat pan head L = 3/4"	Single/ collated	✓	—	—	—	—	—
	Strong-Drive XE EXTERIOR STRUCTURAL METAL Screw 	#10 hex head L = 3/4"	Single/ collated	✓	—	—	—	—	—
	Strong-Drive PHSD FRAMING-TO-CFS Screw 	#8 pan head L = 3/4"	Collated	✓	—	—	—	—	—

Reference the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.

Simpson Strong-Tie® Fasteners for CFS Construction

Below is a list of Simpson Strong-Tie fasteners and tested base materials. This list does not represent the complete line of Simpson Strong-Tie offerings, but the most suitable fasteners for CFS construction.

✓ = Code listed ✓ = Tested — = Not tested

	Product	Single/ Collated	Fastened Materials					
			CFS to CFS	CFS to Structural Steel	Sheathing to CFS	Fiberglass Sheathing to CFS	Drywall to CFS	Wood to CFS
Fasteners	Strong-Drive TB WOOD-TO-STEEL Screw  #12, #14 flat head L = 1 3/4" to 3"	Single/ collated	—	—	—	—	—	✓
	Strong-Drive TF WOOD-TO-STEEL Screw  #14 flat head L = 3"	Single/ collated	—	—	—	—	—	✓
	Strong-Drive PPHD SHEATHING-TO-CFS Screw  #8, #10, #12 flat head L = 1 3/4" to 3"	Single/ collated	—	—	✓	✓	—	—
	CBSDQ Sheathing-to-CFS Screw  #8, #10 ribbed flat head L = 1 5/8" to 2 1/4"	Collated	—	—	✓	—	—	—
	WSF Sheathing-to-CFS Screw  #8 flat head L = 1 1/2"	Collated	—	—	✓	—	—	—
	DWFSD Drywall-to-CFS Screw  #6, #8 bugle head L = 1 1/4" to 2"	Collated	—	—	—	✓	✓	—
	DWF Drywall-to-CFS Screw  #6 bugle head L = 1" to 1 5/8"	Collated	—	—	—	—	✓	—

Reference the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.

S/HDU Holdowns

The S/HDU series of holdowns combines performance with ease of installation. The predeflected geometry virtually eliminates material stretch, resulting in low deflection under load. Installation using self-drilling screws into the studs reduces installation time and saves labor cost.


Material: 118 mil (10 ga.)

Finish: Galvanized (G90)

Installation:

- Specially designed to fit inside open side of stud
- Use standard #14 self-drilling screws to fasten to studs
- Anchor bolt washer is not required
- See SABR™ and PAB® anchor bolts on pp. 184 and 187 for cast-in-place anchorage options
- See SET-3G® and AT-3G™ adhesive products at strongtie.com for anchor bolt retrofit options
- Crescent washer is included with the holdowns. To order replacements, order parts S/HDU4-03 (for S/HDU4 and S/HDU6) or S/HDU9-03 (for S/HDU9 and S/HDU11)


Codes: See p. 15 for Code Reference Key Chart




S/HDU

Typical S/HDU Installation

US Patent. See strongtie.com/patent.



**General Holddown and Tension Ties
Raised Off CFS Bottom Track**



**Typical S/HDU
Floor-to-Floor Installation**



Available in 100 ct. and 2,500 ct. cartons.

Reduce the chance of misinstallations using the wrong size screws; specify Simpson Strong-Tie® #14 Self-Drilling E Metal screw (Model No. E1B1414). Visit strongtie.com for details.

S/HDU Holdowns

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model	H (in.)	Fasteners		Stud Member Thickness ² mil (ga.)	ASD		LRFD		Nominal	Code Ref.				
		Anchor Bolt Diameter ¹ (in.)	Stud Fasteners		Tension Load (lb.)	Deflection at ASD Load ⁴ (in.)	Tension Load (lb.)	Deflection at LRFD Load ⁴ (in.)	Tension Load ⁵ (lb.)					
S/HDU4	7 $\frac{7}{8}$ "	$\frac{5}{8}$ "	(6) #14	33 (20)	1,195	0.069	1,795	0.116	3,575	—				
				43 (18)	1,780	0.068	2,670	0.106	5,095					
				54 (16)	2,550	0.031	4,080	0.053	6,900					
				S/HDU6	10 $\frac{3}{4}$ "	$\frac{5}{8}$ "	(12) #14	2-33 (2-20)	2,320	0.093	3,710	0.149	5,685	IBC, FL, LA
								2-43 (2-18)	3,820	0.114	6,110	0.190	9,365	
								2-54 (2-16)	3,970	0.091	6,350	0.157	9,730	
								$\frac{3}{16}$ " A36 Steel	4,480	0.064	7,165	0.104	12,120	
S/HDU9	12 $\frac{1}{2}$ "	$\frac{7}{8}$ "	(18) #14	33 (20)	2,390	0.064	3,590	0.119	6,590	—				
				43 (18)	3,295	0.054	5,270	0.108	8,915					
				54 (16)	5,100	0.073	8,160	0.167	13,805					
				68 (14)	5,570	0.052	8,915	0.095	15,075					
				S/HDU11	16 $\frac{3}{4}$ "	$\frac{7}{8}$ "	(27) #14	2-33 (2-20)	4,895	0.125	8,480	0.250	10,470	IBC, FL, LA
								2-43 (2-18)	6,120	0.119	9,685	0.250	15,460	
								2-54 (2-16)	6,120	0.107	9,790	0.233	15,005	
								$\frac{3}{16}$ " A36 Steel	7,000	0.069	10,000	0.185	14,695	
S/HDU11	16 $\frac{3}{4}$ "	$\frac{7}{8}$ "	(27) #14	33 (20)	2,855	0.029	4,570	0.045	7,730	—				
				43 (18)	3,725	0.037	5,960	0.061	10,080					
				54 (16)	6,750	0.071	10,805	0.131	18,270					
				68 (14)	8,355	0.087	13,370	0.159	22,610					
				S/HDU11	16 $\frac{3}{4}$ "	$\frac{7}{8}$ "	(27) #14	97 (12)	8,355	0.087	13,370	0.159	22,610	IBC, FL, LA
								2-33 (2-20)	6,950	0.102	11,120	0.186	13,165	
								2-43 (2-18)	9,255	0.124	15,450	0.250	21,810	
								2-54 (2-16)	9,980	0.105	15,970	0.229	24,480	
								$\frac{3}{16}$ " A36 Steel	14,625	0.136	20,890	0.185	31,455	
								43 (18)	4,225	0.039	6,765	0.062	11,440	
54 (16)	7,665	0.070	12,265	0.109	20,740									
68 (14)	9,655	0.087	15,450	0.143	26,130									
97 (12) ³	14,925	0.129	23,880	0.235	40,385									
S/HDU11	16 $\frac{3}{4}$ "	$\frac{7}{8}$ "	(27) #14	2-33 (2-20)	6,950	0.102	11,120	0.186	13,165	IBC, FL, LA				
				2-43 (2-18)	9,585	0.095	15,340	0.162	23,515					
				2-54 (2-16)	9,665	0.110	15,465	0.157	23,710					
				2-43 (2-18) ³	11,100	0.125	17,500	0.250	24,955					
S/HDU11	16 $\frac{3}{4}$ "	$\frac{7}{8}$ "	(27) #14	2-54 (2-16) ³	12,160	0.125	19,455	0.246	29,825	IBC, FL, LA				
				$\frac{3}{16}$ " A36 Steel ³	16,010	0.127	22,875	0.185	31,715					


- The designer shall specify the foundation anchor material type, embedment, and configuration. Some of the tabulated holdown tension loads exceed the tensile strength of typical ASTM A36 or A307 anchor bolts.
- It is acceptable to use the capacity listed for the thickest single member or back-to-back members for thicker stud members in the same configuration. Stud design by specifier.
- A heavy hex nut for the anchor bolt is required to achieve the table loads for S/HDU11.
- Deflection at ASD or LRFD is the deflection of the fastener slip, holdown deformation, and anchor rod elongation for holdowns installed up to 4" above the top of concrete when loaded to the ASD and LRFD load, respectively. Holdowns may be installed raised to 18" above the top of concrete, with no load reduction provided that additional elongation of the anchor rod is accounted for. This movement is strictly due to the holdown deformation under a static load test attached to members listed in the table above.
- For design in accordance with AISI S400, the available strength (i.e., LRFD) of capacity protected components, such as shear wall holdowns, shall be greater than or equal to the required strength, which is the lesser of the load determined from ASCE 7 seismic load combinations with the overstrength factor and the expected strength of the seismic force-resisting system.
- See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.

S/HDU Holdowns

S/HDU Holddown Allowable Uplift Loads for Welding to CFS Stud and Structural Steel (lb.)

Model	Fasteners		Stud Member Thickness mil (ga.)	ASD		LRFD		Nominal Tension Load ⁵ (lb.)
	Anchor Bolt Diameter ¹ (in.)	Weld Quantity, Size and Length ⁷		Tension Load (lb.)	Deflection at ASD Load ⁴ (in.)	Tension Load (lb.)	Deflection at LRFD Load ⁴ (in.)	
S/HDU4	5/8"	(4) 1/8" x 1 1/2"	54 (16)	2,550	0.067	4,080	0.109	6,900
		(4) 1/8" x 2"	3/16" A36 Steel	4,470	0.050	7,165	0.112	12,120
S/HDU6	5/8"	(4) 1/8" x 1 1/2"	54 (16)	5,335	0.157	7,465	0.250	13,685
		(4) 1/8" x 2"	3/16" A36 Steel	6,905	0.106	10,355	0.185	13,805
S/HDU9	7/8"	(4) 1/8" x 2 1/2"	54 (16)	6,750	0.109	10,805	0.186	18,270
			68 (14)	8,355	0.138	13,370	0.240	22,610
		(4) 1/8" x 3 1/2"	97 (12)	8,355	0.138	13,370	0.240	22,610
			3/16" A36 Steel	13,530	0.112	20,295	0.177	27,060
S/HDU11	7/8"	(4) 1/8" x 2 1/2"	54 (16)	7,765	0.128	10,870	0.187	21,100
			68 (14)	9,705	0.164	13,695	0.250	26,200
		(4) 1/8" x 3 1/2"	97 (12)	13,530	0.112	20,295	0.177	27,060
			3/16" A36 Steel ³	13,530	0.112	20,295	0.177	27,060

- The designer shall specify the foundation anchor material type, embedment, and configuration. Some of the tabulated holddown tension loads exceed the tensile strength of typical ASTM A36 or A307 anchor bolts.
- It is acceptable to use the capacity listed for the thickest single member for thicker stud members in the same configuration. Stud design as noted by specifier.
- A heavy hex nut for the anchor bolt is required to achieve the table loads for S/HDU11.
- Deflection at ASD or LRFD is the deflection of the fastener slip, holddown deformation, and anchor rod elongation for holddowns installed up to 4" above the top of concrete when loaded to the ASD and LRFD load, respectively. Holddowns may be installed raised to 18" above the top of concrete, with no load reduction provided that additional elongation of the anchor rod is accounted for. This movement is strictly due to the holddown deformation under a static load test attached to members listed in the table above.
- For design in accordance with AISI S400, the available strength (i.e., LRFD) of capacity protected components, such as shear wall holddowns, shall be greater than or equal to the required strength, which is the lesser of the load determined from ASCE 7 seismic load combinations with the overstrength factor and the expected strength of the seismic force-resisting system.
- The values of S/HDU4 and S/HDU9 in the table are the lesser values between screw application in the strongtie.com and weld application values.
- The welding design is in accordance with AWS D1.3 and AISI S100-16.



S/LTTP2, S/DTT and HTT Tension Ties

The HTT is a single-piece formed tension tie — no rivets, and a four-ply formed seat. No washers are required.

S/DTT2Z tension tie is suitable for lighter-duty holddown applications on single or back-to-back studs, and installed easily with #14 self-drilling screws.

The HTT, S/DTT and S/LTTP2 tension ties are ideal for retrofit or new construction projects. They provide high-strength, post-pour, concrete-to-steel connections.


Material: HTT — 111 mil (11 ga.)
DTT1Z®, S/DTT2Z — 68 mil (14 ga.)
S/LTTP2 — 129 mil (10 ga.)

Finish: HTT, S/LTTP2 — Galvanized (G90);
DTT1Z, S/DTT2Z — ZMAX® coating


Installation:

- Use all specified fasteners.
- Use the specified number of type of screws to attach the strap portion to the steel stud. Bolt the base to the wall or foundation with a suitable anchor; see table for the required bolt diameter.
- S/DTT2Z requires a standard cut washer (included) be installed between the nut and the seat.
- See SABR™ Anchor Bolt on p. 184 for anchorage options.
- See SET-3G® and AT-3G™ adhesive products at strongtie.com for anchor bolt retrofit options.


Codes: See p. 15 for Code Reference Key Chart




DTT1Z
US Patent Pending



S/DTT2Z
US Patent.
See strongtie.com/patent.



HTT5
(HTT4 similar)




S/LTTP2

S/LTTP2, S/DTT and HTT Tension Ties


These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model	Dimensions (in.)			Fasteners		Stud Member Thickness mil (ga.)	ASD		LRFD		Nominal	Code Ref.
	W	H	℄	Anchor Bolt Diameter ¹ (in.)	Stud Fasteners ⁵		Tension Load (lb.)	Deflection at ASD Load ³ (in.)	Tension Load (lb.)	Deflection at LRFD Load ³ (in.)	Tension Load ⁴ (lb.)	
DTT1Z	1½	7½	¾	¾	(6) #10	33 (20)	905	0.156	1,270	0.250	3,485	—
S/LTTP2	2¾	15	1½	½	(12) #10	33 (20)	2,120	0.119	3,180	0.178	5,610	IBC, FL, LA
						2-33 (2-20)	2,820	0.153	3,945	0.250	5,610	
						43 (18)	2,820	0.136	3,945	0.250	5,715	
						2-43 (2-18)	2,895	0.125	4,055	0.250	5,715	
						54 (16)	2,895	0.125	4,055	0.250	5,715	
S/DTT2Z	1½	6¼	¾	½	(8) #14	33 (20)	1,570	0.138	2,200	0.250	4,265	IBC, FL, LA
						43 (18)	1,685	0.151	2,355	0.250	5,570	
						2-33 (2-20)	1,735	0.153	2,430	0.250	5,735	
HTT4	2½	12¾	1¾	¾	(18) #10	33 (20)	3,180	0.104	4,770	0.187	8,215	IBC, FL, LA
						2-33 (2-20)	4,395	0.125	6,675	0.250	11,835	
HTT5	2½	16	1¾	¾	(26) #10	43 (18)	4,150	0.125	6,425	0.250	11,585	IBC, FL, LA
						2-43 (2-18)	4,670	0.125	6,970	0.250	12,195	
						1-54 (1-16)	4,150	0.125	6,425	0.250	12,365	

- The designer shall specify the foundation anchor material type, embedment and configuration.
- Stud design by specifier. Tabulated loads are based on a minimum stud thickness for fastener connection.
- Deflection at ASD or LRFD includes fastener slip, holdown deformation and anchor rod elongation for holdowns installed up to 4" above top of concrete. Holdowns may be installed raised, up to 18" above top of concrete, with no load reduction provided that additional elongation of the anchor rod is accounted for. See bottom of p. 192 for installation detail.
- For design in accordance with AISI S400, the available strength (i.e., LRFD) of capacity protected components, such as shear wall holdowns, shall be greater than or equal to the required strength, which is the lesser of the load determined from ASCE 7 seismic load combinations with the overstrength factor and the expected strength of the seismic force-resisting system.
- It is acceptable to use the capacity listed for the thickest single member or back-to-back members for thicker stud members in the same configuration. Stud design by specifier.
- 2-33 (2-20), 2-43 (2-18) in the stud member thickness signifies holdown attached through back-to-back members.
- See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.



Typical DTT1Z Installation



Typical HTT5 Installation as a Holdown

S/HDS and S/HDB Holdowns

The S/HD series of holdowns is designed for installation with either screws or bolts into the studs or column. The S/HDS series installs with #14 screws and has been designed to utilize fewer fasteners to reduce installation time. The S/HDB series is ideal for bolt-on applications where the cold-formed stud manufacturer can prepunch the bolt holes.


Material: See table

Finish: Simpson Strong-Tie® gray paint. Hot-dip galvanized is available; see Corrosion Information, pp. 21–25.


Installation:

- Use all specified fasteners; some models have extra fastener holes. See General Notes.
- Anchor bolt washer is not required.
- Standard washers are required on stud bolt nuts for model S/HDB.
- Thin wall socket (OD = 2" maximum) is required for S/HD15 to tighten the 1" anchor bolt.
- Stud bolts — use A307.
- Boundary members (back-to-back studs) design shall be by designer.
- S/HDS and S/HDB holdowns can be welded per designer's recommendation and specification. To tie back-to-back stud members together, the designer must determine the fasteners required to bind members to act as one unit. Welders and welding procedures shall be qualified as specified in AWS D1.3. Welded connections used for cold-formed steel structural members in which the thickness of the thinnest connected part is 0.18 inch or less shall comply to AISI S100 Specification Section E2.
- See SABR™ and PAB® Anchor Bolts on pp. 184 and 187 for anchorage options.
- See SET-3G® and AT-3G™ adhesive products at strongtie.com for anchor bolt retrofit options.


Codes: See p. 15 for Code Reference Key Chart




S/HD15B




S/HD15S
(S/HD8S and S/HD10S similar)




Typical S/HD15S
Back-to-Back Stud
Installation



Typical S/HD10S Single
Stud Installation



Typical S/HD10B
PACO Column Installation
See Code Report



Typical S/HD15S Heavy-Duty
(Large Flange) Stud Application
See Code Report

S/HDS and S/HDB Holdowns

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Mil (ga.)	H (in.)	W (in.)	C (in.)	Fasteners		Stud Member Thickness mil (ga.)	ASD		LRFD		Nominal Tension Load (lb.)	Code Ref.
					Anchor Bolt Dia. ¹ (in.)	Stud Fasteners ⁷		Tension Load (lb.)	Deflection at ASD Load ⁴ (in.)	Tension Load (lb.)	Deflection at LRFD Load ⁴ (in.)		
S/HD8S	118 (10)	11	2 ⁵ / ₁₆	1 ¹ / ₂	7 ⁸ / ₁₆	(17) #14 ⁷	33 (20)	2,700	0.029	4,320	0.045	7,305	IBC, FL, LA
							43 (18)	3,520	0.037	5,630	0.061	9,520	
							54 (16)	6,380	0.071	10,205	0.131	17,260	
							68 (14)	7,895	0.087	12,630	0.159	21,355	
							97 (12)	10,245	0.104	16,390	0.188	27,715	
							2-33 (2-20ga)	7,585	0.123	12,140	0.213	13,720	
							2-43 (2-18ga)	8,740	0.086	13,985	0.146	21,435	
							2-54 (2-16ga)	8,845	0.106	14,155	0.162	21,700	
Steel Fixture	10,835	0.053	17,335	0.072	32,525								
S/HD10S	118 (10)	13 ¹ / ₂	2 ⁵ / ₁₆	1 ¹ / ₂	7 ⁸ / ₁₆	(22) #14 ⁷	33 (20)	2,860	0.029	4,575	0.045	7,735	IBC, FL, LA
							43 (18)	3,725	0.037	5,960	0.061	10,080	
							54 (16)	6,755	0.071	10,805	0.131	18,275	
							68 (14)	8,360	0.087	13,375	0.159	22,615	
							97 (12)	10,845	0.111	17,355	0.201	29,345	
							2-33 (2-20ga)	7,650	0.125	12,240	0.202	13,835	
							2-43 (2-18ga)	11,500	0.105	18,395	0.112	20,795	
							2-54 (2-16ga)	12,205	0.096	19,530	0.145	29,940	
Steel Fixture	12,395	0.043	19,830	0.061	33,535								
S/HD15S	171 (7)	17	2 ⁵ / ₁₆	1 ⁹ / ₁₆	1	(30) #14 ⁷	43 (18)	4,580	0.039	7,330	0.066	12,400	IBC, FL, LA
							54 (16)	8,305	0.075	13,290	0.115	22,475	
							68 (14)	10,464	0.093	16,740	0.149	28,315	
							97 (12)	14,925	0.129	23,880	0.235	40,385	
							2-43 (2-18ga)	12,525	0.100	20,035	0.171	22,645	
							2-54 (2-16ga)	13,485	0.108	21,575	0.130	33,075	
Steel Fixture	15,835	0.043	25,335	0.065	42,845								
S/HD8B	118 (10)	11	2 ⁵ / ₁₆	1 ¹ / ₂	7 ⁸ / ₁₆	(2) 3/4" dia.	2-33 (2-20ga)	3,895	0.081	5,620	0.144	8,645	IBC, FL, LA
							2-43 (2-18ga)	5,345	0.098	7,710	0.146	11,865	
							2-54 (2-16ga)	8,930	0.082	14,285	0.141	20,310	
							Steel Fixture	9,085	0.069	14,540	0.104	22,975	
S/HD10B	118 (10)	13 ¹ / ₂	2 ⁵ / ₁₆	1 ¹ / ₂	7 ⁸ / ₁₆	(3) 3/4" dia.	2-33 (2-20ga)	5,840	0.070	8,430	0.124	12,970	IBC, FL, LA
							2-43 (2-18ga)	8,015	0.087	11,565	0.120	17,795	
							2-54 (2-16ga)	12,090	0.125	19,730	0.230	28,050	
							Steel Fixture	15,605	0.091	24,965	0.122	35,495	
S/HD15B	171 (7)	17	2 ⁵ / ₁₆	1 ⁹ / ₁₆	1	(4) 3/4" dia.	2-43 (2-18ga)	10,690	0.118	15,425	0.179	22,165	IBC, FL, LA
							2-54 (2-16ga)	15,985	0.055	25,575	0.094	36,365	
							Steel Fixture	18,650	0.093	29,840	0.139	42,425	

1. The Designer shall specify the foundation anchor material type, embedment, and configuration. Some of the tabulated hold-down tension loads exceed the tensile strength of typical ASTM F1554 Grade 36 or A307 anchor bolts.

2. Stud design by specifier. Tabulated loads are based on a minimum stud thickness for fastener connection.

3. 1/4-inch diameter self-tapping screws may be substituted for #14 self-tapping screws.

4. Deflection at ASD or LRFD is the deflection of the fastener slip, holdown deformation, and anchor rod elongation for holdowns installed up to 4" above the top of concrete when loaded to the ASD and LRFD load, respectively. Holdowns may be installed raised to 18" above the top of concrete, with no load reduction provided that additional elongation of the anchor rod is accounted for. This movement is strictly due to the holdown deformation under a static load test attached to members listed in the table above. See bottom of p. 192 for installation detail.

5. For design in accordance with AISI S400, the available strength (i.e., LRFD) of capacity protected components, such as shear wall holdowns, shall be greater than or equal to the required strength, which is the lesser of the load determined from ASCE 7 seismic load combinations with the overstrength factor and the expected strength of the seismic force-resisting system.

6. Not all fastener holes for S/HDS holdowns need to be filled, as additional fastener holes provided. Install fasteners symmetrically.

7. It is acceptable to use the capacity listed for 2-54 (2-16) member for thicker stud members in the same configuration.

8. See the current Fastening Systems catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.

PA/HPA Purlin Anchors

PA/HPA purlin anchors offer solutions for CFS to concrete and concrete block connections which satisfy code requirements. The HPA offers the highest capacity in concrete. The PAs dual embedment line allows installation in concrete or concrete block.

Material: PA — 12 gauge; HPA — 10 gauge

Finish: Galvanized. PAs available in HDG or ZMAX® coating.

Installation:

- Use all specified fasteners; some models have extra fastener holes. See General Notes.
- Purlin anchor must hook around rebar.
- Allowable loads are for a horizontal installation into the side of a concrete or masonry wall.
- Strap may be bent one full cycle. (Bent vertical 90° then bent horizontal.)

Edge Distance: Minimum concrete edge distance is 5". Minimum concrete block left-to-right edge distance is 20".

Concrete Block Wall: The minimum wall specifications are:


- A One #4 vertical rebar, 32" long, 16" each side of anchor.
- B Two courses of grout filled block above and below the anchor (no cold joints allowed).
- C A horizontal bond beam with two #4 rebars, 40" long, a maximum of two courses above or below the anchor.
- D Minimum masonry compressive strength, $f'_m = 1,500$ psi.

Options: See S/LTTP2 and HTT Tension Ties for alternate retrofit solutions

Codes: See p. 15 for Code Reference Key Chart

ASCE 12.11.2.2.5 states:

... Diaphragm to structural wall anchorage using embedded straps shall have the straps attached to, or hooked around the reinforcing steel or otherwise terminated to effectively transfer forces to the reinforcing steel.




These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.


Wind and SDC A & B — Allowable Load (lb.)										
Model No.	Strap Length L (in.)	l_e^a (in.)	Fasteners ^b			Tension Load		Max. Allowable Strap Tension	Masonry Installation Tension Load	Code Ref.
			Rafter/Stud /Joist Thickness			UnCracked	Cracked			
			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)					
PA18	18½	4	(16) #10	(16) #10	(8) #10	2,430	2,260	NA	1,895	—
PA23	23¾	4	(22) #10	(16) #10	(8) #10	3,220	2,260	NA	2,815	
PA28	29	4	(22) #10	(16) #10	(8) #10	3,230	2,260	NA	2,815	
PA35	35	4	(22) #10	(16) #10	(8) #10	3,230	2,260	NA	2,815	
HPA28	32½	6	(28) #10	(20) #10	(10) #10	5,145	4,675	NA	—	
HPA35	38½	8¼	(32) #10	(22) #10	(12) #10	5,145	5,145	NA	—	
SDC C-F — Allowable Load (lb.)										
PA18	18½	4	(16) #10	(16) #10	(8) #10	2,340	1,980	3,220	1,895	
PA23	23¾	4	(22) #10	(16) #10	(8) #10	2,830	1,980	3,220	2,815	
PA28	29	4	(22) #10	(16) #10	(8) #10	2,830	1,980	3,935	2,815	
PA35	35	4	(22) #10	(16) #10	(8) #10	2,830	1,980	3,935	2,815	
HPA28	32½	6	(28) #10	(20) #10	(10) #10	5,145	4,090	5,145	—	
HPA35	38½	8¼	(32) #10	(22) #10	(12) #10	5,145	5,145	5,145	—	

1. Loads may not be increased for short-term loading.
2. For concrete installs, the minimum compressive strength, $f'_c = 3,000$ psi.
3. Multiply Seismic and Wind ASD load values by 1.4 or 1.67, respectively, to obtain LRFD capacities.
4. In accordance with 2012, 2015, 2018, 2021 and 2024 IBC Section 1613.1, detached one- and two-family dwellings in Seismic Design Category (SDC) C may use (Wind and SDC A & B) allowable loads.
5. Minimum center-to-center spacing is 3 times the required embedment ($S_{min} = 3 \times l_e$) for PA/HPAs acting in tension simultaneously, where l_e = embedment depth. Standard installation is based on minimum 5" edge distance.
6. Install fasteners symmetrically and with a minimum of 4 of the required fasteners between the embedment line and the first tooling hole. In some cases, not all of the fastener holes will need to be filled.
7. For wall anchorage systems in SDC C-F, the maximum strap allowable load shall not be less than 1.4 times the ASD anchor design load.
8. For PA straps, concrete embedment shown; embedment in masonry shall be 6".
9. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.


PA/HPA Purlin Anchors



PA/HPA Purlin to Concrete Wall
Back-to-Back Joist Installation



PA/HPA Purlin to Concrete Wall
Single C-Shape Joist Installation



PA/HPA Purlin
to Concrete Block Wall
(refer to installation
notes above)

STHD/LSTHD Strap Tie Holdowns



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The STHD is an embedded strap-tie holdown offering high-load capacity. The STHD incorporates many features that aid correct installation and improve performance. When installed on the forms with the StrapMate® strap holder, the unique design of the STHD delivers enhanced stability before and during the pour to help prevent both parallel and perpendicular movement (relative to the form). This results in accurate positioning of the strap and reduced possibility of spalling.

Features

- The fastener pattern allows for fastening to the edges of back-to-back studs
- The slots below the embedment line enable increased front-to-back concrete bond and help to reduce spalling
- Rim joist models accommodate up to a 17" clear span without any loss of strap fastening


Material: LSTHD8, LSTHD8RJ — 14 gauge, all others — 12 gauge

Finish: Galvanized

Installation:

- Use all specified fasteners; see General Notes.
- Use table below for both standard concrete and post-tension slab installations.
- Install before concrete pour with a StrapMate or other holding device.
- Fasten strap from the bottom up. Install strap plumb.
- Strap may be bent one full cycle (bent horizontal 90° then bent vertical) to aid wall placement, but may cause spalling behind the strap. If the spall is 1" or less, measured from the embedment line to the bottom of the spall, full loads apply. 1" to 4" spalls for LSTHD8 achieve 0.9 times table loads. STHD10 and STHD14 achieve full load for spalls less than 4". Any portion of the strap left exposed should be protected against corrosion.
- Other than where noted in the two-pour detail, do not install where: (a) a horizontal cold joint exists within the embedment depth between the slab and foundation wall or footing beneath, unless provisions are made to transfer the load, or the slab is designed to resist the load imposed by the anchor; or (b) slabs are poured over concrete block foundation walls.
- Additional studs attached to the shearwall studs or post may be required by the designer for wall sheathing fastening.
- For installation in severe corrosion environments, refer to strongtie.com/cipcorrosion for additional considerations.

Codes: See p. 15 for Code Reference Key Chart



Typical STHD14RJ Rim Joist Application

Allowable Stress Design (ASD) Loads for STHD Strap Style Holdowns on CFS — 2,500 psi Concrete


Wind and SDC A & B — Allowable Tension Loads (lb.) — 33 mil (20 ga.) Studs														
Min. Stem Wall (in.)	Model No.		Strap Length (L)		le (in.)	Uncracked				Cracked				Code Ref.
	Standard	Rim Joist	Standard (in.)	Rim Joist (in.)		Req'd Screws	Midwall	Corner	Endwall	Req'd Screws	Midwall	Corner	Endwall	
	STHD10	STHD10RJ	24%	38½	10	(24) #10	3,535	3,535	1,960	(22) #10	2,910	2,910	1,635	
	STHD14	STHD14RJ	26½	39%	14	(30) #10	4,935	4,935	3,065	(30) #10	4,935	4,935	3,065	
8	LSTHD8	LSTHD8RJ	18%	32½	8	(20) #10	2,985	2,590	2,135	(16) #10	2,565	2,225	1,835	
	STHD10	STHD10RJ	24%	38½	10	(28) #10	4,755	4,075	3,015	(22) #10	4,020	3,350	2,480	
	STHD14	STHD14RJ	26½	39%	14	(30) #10	5,285	5,285	4,410	(30) #10	5,285	5,285	4,410	

SDC C-F — Allowable Tension Loads (lb.) — 33 mil (20 ga.) Studs														
Min. Stem Wall (in.)	Model No.		Strap Length (L)		le (in.)	Uncracked				Cracked				Code Ref.
	Standard	Rim Joist	Standard (in.)	Rim Joist (in.)		Req'd Screws	Midwall	Corner	Endwall	Req'd Screws	Midwall	Corner	Endwall	
	STHD10	STHD10RJ	24%	38½	10	(18) #10	2,750	2,750	1,615	(18) #10	2,550	2,550	1,435	
	STHD14	STHD14RJ	26½	39%	14	(22) #10	3,695	3,695	2,685	(22) #10	3,695	3,695	2,685	
8	LSTHD8	LSTHD8RJ	18%	32½	8	(16) #10	2,615	2,125	1,635	(14) #10	2,250	1,950	1,610	
	STHD10	STHD10RJ	24%	38½	10	(20) #10	3,400	2,940	2,295	(20) #10	3,400	2,940	2,175	
	STHD14	STHD14RJ	26½	39%	14	(24) #10	3,815	3,815	3,500	(24) #10	3,815	3,815	3,500	


1. Deflection at highest allowable loads for install over CFS double studs are as follows: LSTHD8 = 0.065", STHD10 = 0.096" and STHD14 = 0.115".
2. Multiply Seismic and Wind ASD load values by 1.4 or 1.67, respectively, to obtain LRFD capacities.
3. Per 2012, 2015, 2018 and 2021 IBC Section 1613, detached one- and two-family dwellings assigned to Seismic Design Category (SDC) A, B or C are exempt from the seismic design provisions of IBC Section 1613. For this case, the allowable wind loads apply.
4. Minimum center-to-center spacing is 3 times the required embedment ($S_{min} = 3 \times l_e$) for STHD's acting in tension simultaneously. Midwall install is based on $1.5 \times l_e$ end distance.
5. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.

STHD/LSTHD Strap Tie Holdowns


Holdowns and Tension Ties




Typical STHD14 Corner Installation on Three Studs
(end of wall similar)




Typical STHD14 Mid-Wall Installation




Typical STHD End Installation



Spalling Load Reduction
If strap is bent horizontal 90° during installation and then bent vertical for fastening to the stud, concrete spalling could result. Load reductions may apply, see installation note.



Single-Pour Rebar Installation
Maintain minimum rebar cover, per ACI-318 concrete code requirements.



Two-Pour Installation for Downturn Footings

Spall Reduction System for STHD Holddown

Features

- Built-in tab
- StrapMate® locator line
- Additional diamond hole in RJ versions

Benefits

Built-in Tab:


- Reduces spalling and costly retrofits.
- No additional labor to install.
- Holds STHD away from form board.

StrapMate Locator Line:

- Easy inspection to ensure proper location.
- Allows adjustment without removing STHD.

Additional Diamond Hole:

- One more fastener to help prevent the STHD RJ models from bowing out at the rim joint section.




SJC Steel-Joist Connectors

SJC Connectors — CFS to CFS Allowable Loads (lb.)


Model No.	Connector Material Thickness mil (ga.)	Clip Length L (in.)	Framing Member Depth ⁵ (in.)	Fasteners ⁵			Allowable Load F ₄ (lb.) ³			Code Ref.
				Pattern ²	Carried Member	Carrying Member	Minimum Member Thickness		Maximum Connector Load ⁴	
							54 mil (16 ga.)	68 mil (14 ga.)		
SJC8.25	68 (14)	8¼	10	Min.	(4) #10	(4) #10	980	980	2,715	IBC, FL, LA
				Max.	(9) #10	(7) #10	1,060	1,490		
				Inner	(5) #10	(4) #10	1,345	2,005		
MSJC8.25	97 (12)	8¼	10	Min.	(4) #10	(4) #10	1,055	1,710	2,715	
				Max.	(9) #10	(7) #10	1,250	1,765		
				Inner	(5) #10	(4) #10	1,535	2,160		
SJC10.25	68 (14)	10¼	12	Min.	(6) #10	(4) #10	1,285	1,785	3,640	
				Max.	(11) #10	(7) #10	1,285	1,785		
				Inner	(7) #10	(5) #10	1,620	2,385		
MSJC10.25	97 (12)	10¼	12	Min.	(6) #10	(4) #10	1,200	2,045	3,640	
				Max.	(11) #10	(7) #10	1,285	2,045		
				Inner	(7) #10	(5) #10	1,730	2,635		

- See p. 96 for product information.
- Min. fastener quantity and load values — fill all round holes; Max. fastener quantity and load values — fill all round and triangular holes; Inner fastener quantity and load values — see illustrations for fastener placement.
- Allowable loads are based on bracing of the members located within 12" of the connection.
- Maximum allowable load for connector that may not be exceeded when designing custom installations. Designer is responsible for member and fastener design.
- For 6" and 8" joists, SSC connectors are recommended.
- See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.

For smaller framing depth members (3½" to 8"), see SSC Connector on pp. 87–95.




SJC10.25 — Inner Fastener Pattern
(MSJC10.25 similar)




SJC8.25 — Inner Fastener Pattern
(MSJC8.25 similar)

For full dimensioned SJC clips, see p. 100.



SJC Installation with Carried Member Fasteners in Inner Row



SJC8.25 Installation with Min. Screw Pattern (screw in round holes)
For max. screw pattern, fill all round and triangle holes. Min./Max. patterns have screws only in outer row.

S/JCT and S/HJCT Steel-Joist Connectors



This product is preferable to similar connectors because of a) easier installation, b) higher loads, c) lower installed cost, or a combination of these features.

The S/JCT and S/HJCT are unique, skewable steel-joist framing connectors that combine strength, versatility and low installed cost. The connectors can be used with CFS headers, wood headers, steel I-beams (with welds or PAF fasteners) and masonry walls. Installed cost is minimized since these products are shear rather than bearing connectors, eliminating the need for web stiffeners. The connectors also feature horizontal tabs that facilitate top flange alignment and joist support during screw installation.

Material: S/JCT — 68 mil (14 ga.); S/HJCT — 97 mil (12 ga.)

Finish: Galvanized

Features:


- Unidirectional: Joist can be attached from left or right
- One size fits joists 8" through 14" deep
- Optional holes for additional load capacity
- Simplicity of design
- Quick and easy installation
- Field skewable up to 45° left or right

Installation:


- Attach hanger with specified fasteners. Use round holes for minimum load, use round and triangle holes for maximum load.
- May be used for weld-on applications. The minimum required weld to the top flange is 1/8" x 2 1/2" fillet weld to each side of top flange. Consult the code for special considerations when welding galvanized steel.
- May be installed using PDPAT-62KP (0.157" x 5/8") powder-actuated fasteners. Steel headers with thicknesses between 1/4" and 3/4" having a minimum $F_y = 36$ ksi. A Red (level 5) or Purple (level 6) powder load may be required to achieve specified penetration (p). See illustration on next page.

Codes: See p. 15 for Code Reference Key Chart


Ordering Information: The S/JCT is sold in cartons of 50. The S/HJCT is sold in kits as the S/HJCT-KT and contains five (5) connectors and (95) #14 screws.



S/HJCT



S/JCT




S/HJCT Installation with a 4x10 Wood Header

Model No.	Fasteners ⁷			Allowable Load ¹ (lb.)		Code Ref.	
	Top	Face	Joist	Uplift	Down		
Attached to CFS Header: 54 mil (16 ga.)³ — Straight Hanger							
S/JCT (min.)	(1) #10	(2) #10	(4) #10	940	1,195	IBC, FL, LA	
S/JCT (max.)	(1) #10	(4) #10	(6) #10	1,435	2,105		
S/HJCT (min.)	(2) #10	(4) #14	(6) #14	1,510	2,920		
S/HJCT (max.)	(2) #10	(8) #14	(9) #14	1,670	3,855		
Attached to CFS Header: 54 mil (16 ga.)³ — Skewed Hanger							
S/JCT (min.)	(1) #10	(2) #10	(4) #10	940	1,135		
S/JCT (max.)	(1) #10	(4) #10	(6) #10	940	1,185		
S/HJCT (min.)	(2) #10	(4) #14	(6) #14	1,510	2,305		
Attached to Steel Wide-Flange Header⁴ — Straight and Skewed Hanger							
S/JCT (min.)	1/8" x 2 1/2" fillet weld to each side of top flange		(4) #10	145	940	—	
S/HJCT (min.)			(4) #14	195	1,450		
S/HJCT (min.) Skew			(4) #14	195	1,235		
S/JCT (min.)	(2) 0.157" x 5/8" powder-actuated fastener ⁸		(4) #10	145	750		
S/HJCT (min.)			(4) #14	195	1,185		
Attached to Masonry⁷ — Straight and Skewed Hanger							
S/HJCT (min.)	(2) 1/4" x 2 1/4" Titen Turbo™	(4) 1/4" x 2 1/4" Titen Turbo	(6) #14	710	1,785		
S/HJCT (min.) Skew				710	1,410		


Model No.	Fasteners ⁷			Allowable Load ^{1,2} (lb.)		Code Ref.	
	Top	Face	Joist	Uplift (160)	Down (100)		
Attached to 4x DF/SP Wood Header — Straight Hanger							
S/JCT (min.)	(1) 10d	(2) 10d	(4) #10	555	945	IBC, FL, LA	
S/JCT (max.)	(1) 10d	(4) 10d	(6) #10	945	1,465		
S/HJCT (min.)	(2) 10d	(4) 1/4"x3" SDS	(6) #14	1,210	2,625		
S/HJCT (max.)	(2) 10d	(8) 1/4"x3" SDS	(9) #14	1,475	2,980		
Attached to 4x DF/SP Wood Header — Skewed Hanger							
S/JCT (min.)	(1) 10d	(2) 10d	(4) #10	390	845		
S/JCT (max.)	(1) 10d	(4) 10d	(6) #10	775	1,300		
S/HJCT (min.)	(2) 10d	(4) 1/4" x 3" SDS	(6) #14	1,210	1,935		

1. Allowable loads are based on a minimum of single 54 mil (16 ga.) CFS joist member. CFS joist shall be laterally braced per designer specification.
2. Allowable loads for wood header are based on 4x DF/SP minimum, for SPF/HF wood species use an adjustment factor of 0.72.
3. CFS header must be braced to prevent web buckling per designer specification and header must have full bearing of 1 1/8" flange-depth.
4. Backing in the steel beam cavity is not required behind the hanger for load listed. Allowable loads for PAFs to steel header are acceptable to HSS tubes provided an additional (2) & (4) PDPAT-62KP are added to the face in the round holes for S/JCT and S/HJCT respectively.
5. Screws shall be installed using joist hanger holes screwing through the hanger into the joist.
6. CFS joists with up to a 0.50" gap (short cut), use an adjustment factor of 0.87 and joists with a 0.50" to 0.90" gap (short cut), use an adjustment factor of 0.75.
7. Attached to Concrete with 2,500 psi min., use 1/4" x 1 1/4" Titen Turbo™.
8. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.
9. See next page for more information.


S/JCT and S/HJCT Steel-Joist Connectors




S/HJCT Skewed 45° Installation




S/HJCT Installation on Masonry Header



S/HJCT Double-Joist Installation




S/HJCT Weld-On Installation with an I-Beam. Apply 5" of total weld at left and right edges, as shown.



S/HJCT Installation with a CFS Steel Header

PDPAT-62KP fasteners installed into existing top-flange and face mount nail holes




Reference p. 204 note #4 on allowable load table for attachment to HSS tubes.

S/JCT Installed on a HSS Header with Powder-Actuated Fasteners.


Steel header thickness: $\frac{1}{4}$ " to $\frac{1}{2}$ "
Point of PDPAT-62KP must penetrate through the steel header

Steel header thickness: $>\frac{1}{2}$ " to $\frac{3}{4}$ "
 $p = 0.46$ " min. for A36 steel
 $p = 0.36$ " min. for A572 or A992 steel



S/JCT Skewed 45° Installation on HSS Header


PDPAT-62KP fasteners installed into existing top-flange nail holes



S/JCT Installed on a Steel Header with Powder-Actuated Fasteners

Steel header thickness: $\frac{1}{4}$ " to $\frac{1}{2}$ "
Point of PDPAT-62KP must penetrate through the steel header

Steel header thickness: $>\frac{1}{2}$ " to $\frac{3}{4}$ "
 $p = 0.46$ " min. for A36 steel
 $p = 0.36$ " min. for A572 or A992 steel



S/JCT Installed on a HSS Header

S/LBV and S/B Hangers

S/LBV and S/B top-flange hangers are manufactured with precision forming and quality control, providing dimensional accuracy and helping to ensure proper bearing area and connection. These hangers are designed for attaching to cold-formed steel members with screws or to structural steel with powder-actuated fasteners or welds.

Material: S/LBV — 68 mil (14 ga.); S/B — 97 mil (12 ga.)

Finish: Galvanized (G90)

Installation:

Cold-Formed Steel:

- S/LBV and S/B may be attached to cold-formed steel supporting members with screws to the face and top flanges and provide capacities for downward and uplift.




Structural Steel:

- S/LBV and S/B may be attached to structural steel support members with powder-actuated fasteners or welds. For powder-actuated fasteners use PDPAT-62KP (0.157" x 5/8") and provide full penetration as required. For welds use a minimum of 1/8" x 2" fillet weld on each top flange as required. Distribute the weld equally on both flanges. Capacities are provided for downward loads.


Skew Options:

- S/LBV and S/B may be skewed up to a maximum of 45°. Widths for skewable sections are limited to a maximum of 5.25" (specify right or left skew).


Codes: See p. 15 for Code Reference Key Chart



S/LBV
Weld-On Applications
(S/B similar)




S/LBV Installed to a
CFS Header with Screws
(S/B similar)




S/LBV Installed to a
Steel Beam with PAF(s)
(S/B similar except 8 PAF(s))

S/LBV and S/B Hangers



S/LBV with CFS Joist Fastened on One Side of Hanger
(S/B similar)



S/B with CFS Joist Fastened on Both Sides of Hanger
(S/LBV similar)

S/LBV and S/B Hanger Allowable Loads (lb.)

Joist Depth (in.)	Model	Base Header Material	Hanger Config.	Fasteners		Allowable ASD Loads (lb.)					Code Ref.	
						One or Both Sides ⁷		CFS Joist Fastened on Both Sides of Hanger ⁷		CFS Joist Fastened on One Side of Hanger ⁷		
						68 mil (14 ga.)	97 mil (12 ga.)	68 mil (14 ga.)	97 mil (12 ga.)	68 mil (14 ga.)		97 mil (12 ga.)
		Top	Face	Joist	Uplift	Down	Down	Down	Down			
12 to 14	S/LBV	CFS	Straight	(4) #10	(4) #10	(3) #10	1,010	2,660	2,660	1,625	1,625	IBC, LA, FL
			Skewed	(4) #10	(4) #10	(3) #10	1,010	1,875	1,875	1,145	1,145	
		A36 steel 3/16" min.	Straight	(4) 1/8" x 2" weld	—	(3) #10	—	2,235	2,235	2,235	2,235	
				(4) 0.157" x 5/8" PAF	—	(3) #10	—	2,440	2,440	2,440	2,440	
	S/B	CFS	Straight	(8) #10	(4) #14	(3) #14	1,855	3,535	5,040	3,100	4,425	
			Skewed	(8) #10	(4) #14	(3) #14	1,855	2,490	3,555	2,185	3,120	
A36 steel 3/16" min.	Straight	(4) 1/8" x 2" weld	—	(3) #14	—	3,595	5,125	3,155	4,500			
		(8) 0.157" x 5/8" PAF	—	(3) #14	—	3,915	5,585	2,890	4,125			
10 and shorter	S/LBV	CFS	Straight	(4) #10	(4) #10	(3) #10	1,010	3,145	3,145	1,920	1,920	
			Skewed	(4) #10	(4) #10	(2) #10 for Both Sides (3) #10 for One Side	1,010	2,220	2,220	2,005	2,005	
		A36 steel 3/16" min.	Straight	(4) 1/8" X 2" weld	—	(3) #10	—	2,645	2,645	2,645	2,645	
				(4) 0.157 X 5/8" PAF	—	(3) #10	—	2,885	2,885	2,885	2,885	
	S/B	CFS	Straight	(8) #10	(4) #14	(3) #14	1,855	4,180	5,965	3,675	5,240	
			Skewed	(8) #10	(4) #14	(3) #14	1,855	2,950	4,205	2,520	3,595	
		A36 steel 3/16" min.	Straight	(4) 1/8" X 2" weld	—	(3) #14	—	4,250	6,065	3,735	5,330	
				(8) 0.157 X 5/8" PAF	—	(3) #14	—	4,635	6,610	3,420	4,880	

1. Designer shall ensure that the joist member adequately transfers load to hanger. The designer is responsible for header design.
2. Load is based on the Simpson Strong-Tie® PDPAT-62KP (0.157" x 5/8") powder-actuated fasteners. Steel headers with thicknesses between 1/4" and 3/4" having minimum F_y = 36 ksi. A Red (level 5) or Purple (level 6) powder load may be required to achieve proper penetration.
3. Tabulated loads are based on testing with full bearing of 2 1/2" flange-depth.
4. Joist fastener quantity shown is for each side of hanger. For installations with fasteners on both sides of hanger, the total quantity of joist fasteners is twice the tabulated quantity.
5. Hanger capacities may be increased using a web stiffener, but the value shall not exceed hanger capacity shown for 97mil (12 ga.) and 10" and shorter members. Allowable hanger loads using a web stiffener are by others.
6. CFS joist members shall have a minimum yield strength of 33 ksi for 43 mil (18 ga.) and thinner and 50ksi for 54mil (16 ga.) and thicker.
7. To determine hanger capacity for 54 mil (16 ga.) and lighter joists without a web stiffener, use an adjustment factor from 97mil (12 ga.) as shown in table to the right.

Model	Adjustment Factor (joists must have h/t <200)											
	CFS Joist Fastened on Both Sides of Hanger			CFS Joist Fastened on One Side of Hanger								
	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)						
	Uplift	Down	Uplift	Down	Uplift	Down						
S/LBV	0.70	0.32	1.00	0.42	1.00	0.79	0.52	0.26	0.78	0.33	1.00	0.79
S/B	0.43	0.22	0.64	0.29	1.00	0.56	0.32	0.22	0.48	0.29	0.98	0.56

Example: The capacity of 800S162-54 (50 ksi) joist without a web stiffener attached to One side of the S/LBV to CFS header (Straight) is:

Uplift Allowable Load: 1,010 x (Adjustment factor = 1.00) = 1,010 lb.
Down Allowable Load: 1,920 x (Adjustment factor = 0.79) = 1,517 lb.

S/LBV and S/B Hangers


The Standard Hanger Sizes table below are hangers with common widths and heights.

Standard Hanger Sizes

Joist width (in.)	S/LBV	S/B	W (in.)	H (in.)
1½	S/LBV1.68/6	S/B1.68/6	1½	6
	S/LBV1.68/8	S/B1.68/8		8
	S/LBV1.68/10	S/B1.68/10		10
	S/LBV1.68/12	S/B1.68/12		12
	S/LBV1.68/14	S/B1.68/14		14
2	S/LBV2.12/6	S/B2.12/6	2½	6
	S/LBV2.12/8	S/B2.12/8		8
	S/LBV2.12/10	S/B2.12/10		10
	S/LBV2.12/12	S/B2.12/12		12
	S/LBV2.12/14	S/B2.12/14		14
2½	S/LBV2.56/8	S/B2.56/8	2¾	8
	S/LBV2.56/10	S/B2.56/10		10
	S/LBV2.56/12	S/B2.56/12		12
3	S/LBV3.12/8	S/B3.12/8	3½	8
	S/LBV3.12/10	S/B3.12/10		10
	S/LBV3.12/12	S/B3.12/12		12
(2) 1½	S/LBV3.38/6	S/B3.38/6	3¾	6
	S/LBV3.38/8	S/B3.38/8		8
	S/LBV3.38/10	S/B3.38/10		10
	S/LBV3.38/12	S/B3.38/12		12
	S/LBV3.38/14	S/B3.38/14		14
(2) 2	S/LBV4.18/6	S/B4.18/6	4¾	6
	S/LBV4.18/8	S/B4.18/8		8
	S/LBV4.18/10	S/B4.18/10		10
	S/LBV4.18/12	S/B4.18/12		12
	S/LBV4.18/14	S/B4.18/14		14

Standard size ordering:


EX1: Joist 800S162-54 using an S/LBV hanger.




The S/ hangers can be ordered special to fit different width, height or skew from the standard hangers. Below is a table with base model and the modified options.

Hanger Modification Options: Custom Width, Height and Skew

S/LBV	S/B	W (in.)	Modified W range, W ₁ (in.)	H ₁ (in.)	Skew
S/LBV1.56X	—	1¾	1.56	S/LBV 6 to 20 S/B 6 to 30	Left or right 0° to 45°
S/LBV1.68X	S/B1.68X	1½	1.57 to 1.68		
S/LBV2.12X	S/B2.12X	2½	1.69 to 2.12		
S/LBV2.56X	S/B2.56X	2¾	2.13 to 2.56		
S/LBV3.12X	S/B3.12X	3½	2.57 to 3.12		
S/LBV3.38X	S/B3.38X	3¾	3.13 to 3.38		
S/LBV4.18X	S/B4.18X	4½	3.39 to 4.18		
S/LBV5.25X	S/B5.25X	5¼	4.19 to 5.25		
—	S/B7.25X	7¼	5.26 to 7.25		



S/LBV2.12 X W₁ = Specify H₁ = Specify SKL##



Customizable Options for Hangers



Optional Modified Width (W₁) is defined in the W₁ range from the table and measured in 1/16" increments less than the base model width. For example, if a 2.25" wide S/LBV hanger is needed, start with the wider S/LBV2.56X base model and add "W₁ = 2.25" after X. If W₁ is left blank, then the width of the base model will be used.

Height 1 (H₁) is the modified hanger height defined in the H₁ range from the table and measured in 1/16" increments. For example, if a 9.25" long hanger height is needed, add "H₁ = 9.25" after X or the W₁ value if also modifying the width.


Skew is the modified skew slope where SKL is for left skew or SKR for right skew followed by a value for the skew angle ranging from 0 to 45°. For example, add "SKL20" after the H₁ value for a 20° left skewed hanger.

For more examples of modified hangers, see EX1 and EX2 below:

EX1: Joist 800S162-54 using S/LBV hanger skewed right 20°.



EX2: Need a 12 ga. hanger with a W₁ = 2¼" and a H₁ = 9¼".



Top View S/B Hanger Skewed Right (S/LBV similar)

S/DHUTF Drywall Hangers

The S/DHUTF top-mount hanger is designed to carry joist loads to a CFS stud wall through two layers of 5/8" gypsum board (drywall). This hanger installs after the drywall is in place and comes in sizes that accommodate most typical joists used in multi-family and commercial construction.


Material: 97 mil (12 ga.)

Finish: Galvanized (G90)

Installation:

- Use all specified fasteners; see General Notes
- Hanger to be framed in-line with vertical wall stud
- Drywall is installed first
- Wall top track must be restrained to counteract load eccentricity from hanger

Codes: See p. 15 for Code Reference Key Chart




S/DHUTF
US Patent.
See strongtie.com/patent.

Model No.	Dimensions (in.)	
	W	H
Standard Hanger Sizes		
S/DHU1.68/8TF	1 11/16	8
S/DHU1.68/10TF		10
S/DHU1.68/12TF		12
S/DHU2.1/8TF	2 1/8	8
S/DHU2.1/10TF		10
S/DHU2.1/12TF		12
S/DHU2.56/8TF	2 5/16	8
S/DHU2.56/10TF		10
S/DHU2.56/12TF		12
Hanger Modification Options: Custom Width, Height and Skew		
S/DHUTFX	1 11/16 to 6 3/16	6 to 12


S/DHUTF Allowable Loads (lb.)

Model	Fasteners ⁶			Allowable Load (lb.)		Code Ref.
	Top	Face	Joist	Uplift	Down	
S/DHUTF	(6) #10	(8) #14 x 2"	(3) #10	1,230	1,700	—

1. Designer shall ensure that the joist member adequately transfers load to the hanger.
2. Tabulated loads assume (2x) 5/8" Type X drywall attached per IBC.
3. Wall studs designed per designer specifications. At a minimum, the assembly must consist of 600T350-68, Gr. 50 ksi top track and 600S162-43, Gr. 33 ksi wall studs spaced at a maximum of 24" o.c.
4. Tabulated loads are based on testing with full bearing of 3 15/16" hanger top flange. The minimum joist gauge is 54 mil (16 ga.).
5. S/DHUTF hanger can be installed 3/4" max. from the center of the vertical stud per the in-line framing specifications of the AISI General Provisions without load adjustment.
6. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



S/DHUTF
Typical Installation



Typical Installation
Over (2) Layers
of 5/8" Drywall


Hanger Modification Naming Legend

S/DHU x W=Specify H=Specify SKL#

Base Model | Width | Height | SKL = Skew Left
x = Modification | | | SKR = Skew Right
= 0° to 45°

Example: S/HDU W=2.625 H=9.25 SKL45
(Hanger 2.625" inside dimension and 9.25" height, skewed left 45°)

12" (min.) long stud piece with screws or welds to full height stud. Stud and connection per designer specifications.



Typical Top Track Splice

Note: This splice detail is for uplift and download only. If the top track is used for drag, additional detailing will be required by the designer.

WP Hanger

This series of purlin hangers offer the greatest design flexibility and versatility.

Material: Stirrup — 97 mil (12 ga.)

Finish: Simpson Strong-Tie® gray paint. Some models available hot-dip galvanized; specify HDG; see Corrosion Information on pp. 21–25.


Installation: WP hanger may be welded to steel header with $\frac{3}{16}$ " x $1\frac{1}{2}$ "-fillet welds located at each end of top flange

Options: W and H dimensions are modifiable

Sloped and/or Skewed Seat:

- WP series may be skewed to a maximum of 84° and/or sloped to a maximum of 45°.
- For slope only, skew only, or slope and skew combinations, the allowable load is 100% of the table load.
- Specify the slope up or down in degrees from the horizontal plane and/or the skew right or left in degrees from the perpendicular vertical plane. Specify whether low side, high side or center of joist will be flush with the top of the header.

Codes: See p. 15 for Code Reference Key Chart



WP

Some model configurations may differ from those shown. Call Simpson Strong-Tie for details.

Model No.	Dimensions (in.)			Fasteners ⁴		Allowable Down Load (lb.)	Code Ref.
	W	H	B	Header	Joist		
WP	1 $\frac{1}{16}$ – 7 $\frac{1}{2}$	4 – 30	2 $\frac{1}{2}$ – 5	Weld	(1) #10	3,650	—

1. For hanger heights exceeding the joist height, the allowable load is 0.50 of the table value.
2. The designer shall ensure that the joist member adequately transfers load to the hanger.
3. Not all combinations of W, H, and B dimensions are available. Contact Simpson Strong-Tie.
4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.

HU/HUC Hangers


Material: 68 mil (14 ga.)

Finish: Galvanized (G90)


Installation:

- Single Joist — Fill all round holes on one leg of HU/HUC with #10 screws to web of joist.
- Boxed Joist — Fill all round holes on both legs of HU/HUC with #10 screws to web of both joists.
- Screw attach to Steel — Fill all round holes on both flanges to structural steel support.
- Weld attach to Steel — Use 1" weld segments equally spaced top and bottom with half the segments on each side of hanger. Welds may be either lap joint (on outside edge of flanges) or flare-bevel groove (on flange bend line).

Codes: See p. 15 for Code Reference Key Chart




Flare-Bevel Groove Weld
(see detail)



Lap-Joint Fillet Weld

HU/HUC Allowable Loads (lb.)

Model No.	Fasteners		Joist Depth (in.)	Joist Thickness mil (ga.)	ASD		Code Ref.
	Face	Joist			Download (lb.)	Uplift (lb.)	
HU36/ HUC36	(8) #12	(2) #10	6	33 (20)	990	355	—
				43 (18)	1,480	525	
				54 (16)	1,480	915	
				68 (14)	1,400	1,080	
				97 (12)	1,400	1,080	
HU38/ HUC38	(10) #12	(2) #10	8	33 (20)	825	355	—
				43 (18)	1,220	525	
				54 (16)	1,220	915	
				68 (14)	1,500	1,080	
				97 (12)	1,500	1,080	
HU310/ HUC310	(14) #12	(3) #10	10	43 (18)	1,435	790	—
				54 (16)	1,585	1,495	
				68 (14)	1,995	1,620	
				97 (12)	1,995	1,620	
HU312/ HUC312	(16) #12	(3) #10	12	54 (16)	1,355	1,495	—
				68 (14)	1,985	1,620	
				97 (12)	1,985	1,620	




Flare-Bevel Groove Weld Detail


Installation for CFS Built-Up Beam

The designer is responsible for design of beam member.

1. In lieu of face fasteners, it is acceptable to weld. Design loads must not exceed the weld capacities per table and note #5 but are limited to a max of 3,280 lb. for (4) 1" segment welds, and 4,855 lb. for (6) 1" segment welds. Welds to be at top and bottom of hanger as shown in detail.
2. Loads assume E-70S-6 (60 ksi) filler rod.
3. Welds must conform to the current AWS D1.3 structural welding code for sheet steel and must be performed by a certified welder.
4. Designer shall ensure that the joist member adequately transfers load to hanger.
5. Face Fasteners to be half on each flange. For single members, attach joist fasteners to single joist. For boxed members, attach to joist with fasteners listed in table on each joist webs (joist fastener quantity doubled). Capacities listed are for a single attached member. For boxed member, capacity can be doubled.
6. The minimum thickness for face fasteners is $\frac{3}{16}$ " for structural steel.
7. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Single Member to HU



Boxed Member to HUC

L, LS and S/LS Utility Clips and Skewable Angles

L, LS, and S/LS angles are load rated, providing the correct thickness and number of fasteners for the specifier compared with field fabricated clip angles. These angles also have well-defined fastener locations, and testing ensures that the tabulated load values account for connection eccentricities. The connectors are general utility reinforcing angles with multiple uses. S/LS and LS connectors are skewable and can be used to attach members intersecting at angles.

Material: L — 54 mil (16 ga.); S/LS and LS — 43 mil (18 ga.)



Finish: Galvanized (G90)

Installation:


- Use all specified fasteners
- S/LS and LS — Field-skewable; bend one time only
- CFS framing must be constrained against rotation when using a single S/LS or LS per connection

Codes: See p. 15 for Code Reference Key Chart

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.



S/LS
US Patent.
See strongtie.com/patent.






L90

See pp. 100-104 for more utility clips options with the RCA (Rigid Connector Angle).

Model No.	Length (in.)	Fasteners ²	Allowable Load (lb.)						Code Ref.
			33 mil (20 ga.)		43 mil (18 ga.)		54 mil (16 ga.)		
			F ₄	F ₂	F ₄	F ₂	F ₄	F ₂	
L30	3	(4) #10	200	60	315	85	610	—	—
L50	5	(6) #10	475	—	675	90	750	110	
L70	7	(8) #10	705	—	760	110	1,100	110	
L90	9	(10) #10	795	—	945	110	1,740	110	
LS30	3%	(6) #10	200	—	370	—	500	—	
S/LS50	4%	(4) #10	200	—	370	—	500	—	
S/LS70	6%	(6) #10	465	—	575	—	715	—	
LS90	7%	(12) #10	465	—	895	—	915	—	

1. Loads are for one part only.
2. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



ICFVL® Ledger Connector System

The ICFVL ledger connector system is engineered to solve the challenges of mounting CFS ledgers to insulated concrete form (ICF) walls. The ICFVL is designed to provide both vertical and lateral, in-plane performance. There are many benefits over traditional anchor bolting, including better on-center spacing in most cases, faster installation and no protrusions. The embedded legs of the ICFVL are embossed for additional stiffness and the hole allows for concrete to flow through and around the connector. The exposed flange on the face of the ICF provides a structural surface for mounting a CFS ledger.

Material: ICFVL — 68 mil (14 ga.)

Finish: Galvanized (G90)

Installation:

ICFVL in ICF

- Snap a chalk line for the bottom of the ledger
- Mark required on-center spacing
- Use ICFVL to mark kerfs locations
- Cut kerfs as marked
- Insert ICFVL flush to the face of the ICF
- Pour concrete

Warning:
Industry studies show that hardened fasteners can experience performance problems in wet environments. Accordingly, use this product in dry environments only.

CFS Ledger Attachment

- Position the ledger level to the chalk line and against the ICFVL
- Attach with four #14 x ¾", #3 drill point screws (not provided)
- All screws should be located at least ½" from the edge of the ICFVL
- Space screws evenly




Codes: See p. 15 for Code Reference Key Chart

Model No.	Fasteners	Allowable ASD Load (lb.) 54mil (16 ga.) min.		Code Ref.
		Vertical (F ₄)	Lateral (F ₁)	
ICFVL6 or ICFVL8	(4) #141	2,190	1,825	—

1. Use (4) #14 x ¾" or ¼-14 x ¾", #3 drill point screws (not provided).
2. Loads apply to ICF with 4½" maximum foam thickness with the ICFVL8 and 3¼" maximum foam thickness with the ICFVL6.
3. The ICFVL must be installed not less than 4" from the top of the wall to achieve the allowable loads shown. For installations where the ICFVL is installed less than 4" from the top of the wall (including flush applications), multiply the allowable loads by 0.9
4. Concrete f_c = 2,500 psi minimum.

Ledger Thickness mil (ga.)	ICFVL Spacing to Replace Anchor Bolts on a CFS Ledger (in.) ^{1,2}							
	½"-Diameter Anchors at				¾"-Diameter Anchors at			
	12" o.c.	24" o.c.	36" o.c.	48" o.c.	12" o.c.	24" o.c.	36" o.c.	48" o.c.
54 (16)	15	30	45	48	12	24	36	48
68 (14)	11	22	33	44	9	18	27	36

1. This table addresses vertical load applications only.
2. For steel ledgers, the ICFVL spacing is closer for 68 mil ledgers than for 54 mil ledgers because the calculated load for the bolt is greater for a thicker member than for a thinner member.
3. Steel ledger values are based on steel with a minimum yield strength, F_y = 50 ksi and tensile strength F_u = 65 ksi.



ICFVL
Patent pending



Available in 100 ct. and 2,500 ct. cartons.

Reduce the chance of misinstallations using the wrong size screws; specify Simpson Strong-Tie® #14 Self-Drilling E Metal screw (Model No. E1B1414) with the ICFVL Ledger Connector System. Visit strongtie.com for details.

TB and LTB Bridging


TB and LTB bridging connectors are a cost-effective solution for bracing between floor joists when compared with field fabricated blocking and clip angles.

Material: LTB — 27 mil (22 ga.); TB — 33 mil (20 ga.)


Finish: Galvanized (G90)

Installation: Use (2) #10 screws at each end


Codes: See p. 15 for Code Reference Key Chart



LTB20



TB



Typical TB Installation

Web Height (in.)	Spacing (in.)	TB		LTB	Code Ref.
		Model No.	L (in.)	Model No.	
6	12	TB20	20	LTB20	—
8		TB20	20	LTB20	
10		TB20	20	—	
12		TB27	27	—	
14	TB27	27	—		
6	16	TB27	27	—	
8		TB27	27	—	
10		TB27	27	—	
12		TB27	27	—	
14	TB27	27	—		
10	24	TB36	36	—	
12		TB36	36	—	
14		TB36	36	—	

CS Coiled Strap

CS coiled utility straps are an ideal solution when it is desired to brace floor joist flanges with flat strap. These products are packaged in lightweight cartons (about 40 lb.) and can be cut to length on the jobsite.


Material: See table

Finish: Galvanized (G90)

Installation:

- Use all specified fasteners
- Refer to the applicable code for minimum edge and end distance

Codes: See p. 15 for Code Reference Key Chart



Typical CS Installation for Block and Strap Joist Bridging

Model No.	Total Length (ft.)	Connector Material Thickness mil (ga.)	Width (in.)	Fasteners ⁴ (At Blocking)			Allowable Tension Load (lb.)	Code Ref.
				Framing Thickness mil (ga.)				
				33 (20 ga.)	43 (18 ga.)	54 (16 ga.)		
CS20	250	33 (20)	1 1/4	(6) #10	(4) #10	(3) #10	945	IBC, FL, LA
CS16	150	54 (16)	1 1/4	(9) #10	(6) #10	(4) #10	1,550	
CS14	100	68 (14)	1 1/4	(28) #10	(18) #10	(12) #10	2,305	

1. In order to achieve the tabulated loads in the strap, attach each strap to the blocking with the tabulated number of screws.
2. Strap length at blocking to achieve tabulated load = number of tabulated screws + 1".
3. Calculate the strap value for a reduced number of screws to the blocking as follows:

$$\text{Allowable Load} = \frac{\text{No. of Screws Used}}{\text{No. of Screws in Table}} \times \text{Table Load}$$
4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.

SSP/DSP/TSP Stud Plate Ties

The SSP, DSP and TSP are pre-bent strap designed to connect double studs in either top or bottom track applications. These versatile single- and double-stud-plate connector helps to create a continuous load path in uplift resistance.


Material: SSP/DSP — 43 mil (18 ga.);
TSP — 54 mil (16 ga.)

Finish: Galvanized (G90). Some products available in ZMAX®; see Corrosion Information, pp. 21–25.

Installation:

- Use all specified fasteners; see General Notes
- DSP/SSP — top track installation; fill all round and triangle holes


Codes: See p. 15 for Code Reference Key Chart




These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Fasteners ⁴				Allowable Uplift Load (lb.)		Code Ref.
	Studs	Top Track		Bottom Track	33 mil (20 ga.)	43 mil (18 ga.)	
		CFS	Wood	CFS			
SSP	(4) #10	—	—	(2) #10	355	625	IBC, FL, LA
		—	(2) #10	—	340	600	
		(2) #10 ³	(1) #10	—	405 ¹	715 ¹	
		(2) 10d	(1) #10	—	480 ¹	840 ¹	
DSP	(8) #10	—	—	(4) #10	430	695	
		—	(4) #10	—	475	775	
		(4) #10 ³	(2) #10	—	585 ¹	955 ¹	
		(4) 10d	(2) #10	—	730 ¹	1,200 ¹	
TSP	(6) #10	—	—	(3) #10	345	645	
		—	(3) #10	—	370	700	
	(9) #10	(3) #10 ³	(3) #10	—	360 ¹	685 ¹	
		(3) 10d	(3) #10	—	480 ¹	905 ¹	


1. For wood plates, noted values only apply to DF/SP members where wood top plates are used. For SPF values, multiply by 0.86.
2. For wood plates, when cross-grain tension cannot be avoided, mechanical reinforcement to resist such forces should be considered.
3. Screws installed into wood plates with a minimum #10 x 3/4" self-drilling screw.
4. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Typical SSP Installed to Bottom Track
(DSP similar for double stud)



Typical DSP Installed to Top Track
(SSP similar for single stud)



Typical TSP Installed to Top Track with Top Plate

SP Stud Plate Ties


The SP stud plate tie is a plate-to-stud connection providing uplift resistance.

Material: See table.

Finish: Galvanized. Available with ZMAX® coating; see Corrosion Information, pp. 21–25.

Installation: Use all specified fasteners


Codes: See p. 15 for Code Reference Key Chart




These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Connector Material Thickness mil (ga.)	Dimensions (in.)		Stud Fasteners ¹	Allowable Uplift Load 33 mil (20 ga.) (lb.)	Code Ref.
		W	L			
SP4	33 (20)	3 ⁵ / ₁₆	7 ¹ / ₄	(6) #10	825	IBC, FL, LA
SP6	33 (20)	5 ⁹ / ₁₆	7 ³ / ₄	(6) #10	825	
SP8	43 (18)	7 ⁹ / ₁₆	8 ⁵ / ₁₆	(6) #10	930	
SPH4	43 (18)	3 ⁵ / ₁₆	8 ³ / ₄	(12) #10	1,490	
SPH4R	43 (18)	4 ¹ / ₁₆	8 ¹ / ₄	(12) #10	1,490	—
SPH6	43 (18)	5 ⁹ / ₁₆	9 ¹ / ₄	(12) #10	1,490	
SPH6R	43 (18)	6 ¹ / ₁₆	8 ³ / ₄	(12) #10	1,490	
SPH8	43 (18)	7 ⁹ / ₁₆	8 ³ / ₈	(12) #10	1,490	

1. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Typical SP Installation
(Wall-to-Top Track)



Typical SP Installation
(Wall-to-Bottom Track)
(SPH similar)

S/H and H Seismic and Hurricane Ties

Designed to provide seismic and wind ties for trusses or joists, this versatile line may be used for general tie purposes, strongback attachments, and as all-purpose ties where one member crosses another.

Material: See table



Finish: Galvanized (G90). Available with ZMAX® coating; see Corrosion Information, pp. 21–25.

Installation:

- Use all specified fasteners
- Hurricane ties do not replace solid blocking
- S/H2.5, S/H3 and H6 ties are only shipped in equal quantities of rights and lefts


Codes: See p. 15 for Code Reference Key Chart

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.



Model No.	Connector Material Thickness mil (ga.)	Fasteners ⁵			Allowable Load (lb.) 33 mil (20 ga.)			Code Ref.
		To Rafters/Truss	To Top Track	To Stud	Uplift	Lateral		
					F ₁	F ₂		
H2A	43 (18)	(5) #10	(1) #10	(5) #10	450	90	100	
S/H2.5	43 (18)	(4) #10	—	(4) #10	390	90	125	
S/H3	43 (18)	(2) #10	(2) #10	—	375	90	125	
H6	54 (16)	—	(8) #10	(8) #10	950	—	—	
H7Z	54 (16)	(4) #10	(2) #10	(8) #10	985	—	—	
H10S ⁴	43 (18)	(8) #10	—	(8) #10	9303	—	—	

1. Loads are based on attachment of cold-formed steel members having a minimum thickness of 33 mil (20 ga.).
2. Hurricane ties are shown installed on the outside of wall for clarity. Installation inside of wall is acceptable. For Continuous Load Path, connections in the same area must be on same side of wall.
3. For H10S connectors with CFS members having a minimum thickness of 43 mil (18 ga.), the allowable load is 1,260 lb.
4. H10S connectors can be installed 3/4" (max.) from the center of the vertical stud per the in-line framing specifications of the AISI General Provisions for reduced uplift of 890 lb., provided that the screw edges are met.
5. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



H Hybrid Connectors

Seismic and Hurricane Ties for Wood Truss or Joist-to-CFS Wall

Designed to provide seismic and wind ties for wood trusses or joists-to-CFS walls, this versatile line may be used for general purposes, strongback attachments, and as all-purpose ties where one member crosses another.

HS24 attaches the bottom chord of a truss or rafter at pitches from 0:12 to 4:12 to steel top plates.

Material: See table


Finish: Galvanized (G90).

Selected products available in stainless steel or ZMAX® coating. See Corrosion Information, pp. 21–25.

Installation:

- Use all specified fasteners; see General Notes
- H1 can be installed with flanges facing inward (reverse of illustration 1)
- Hurricane ties do not replace solid blocking
- H3 and H6 ties are only shipped in equal quantities of rights and lefts

Codes: See p. 15 for Code Reference Key Chart




These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Connector Material Thickness mil (ga.)	Fasteners ⁵			Allowable Uplift Load 33 mil (20 ga.) (160) (lb.)		Code Ref.
		To Rafters/ Truss	To Top Track	To Stud	DF/SP	SPF/HF	
H1	43 (18)	(6) 8d x 1 1/2"	(3) #10	(1) #10	600	500	—
H2A	43 (18)	(5) 8d x 1 1/2"	(1) #10	(5) #10	550	460	
H3	43 (18)	(4) 8d x 1 1/2"	(4) #10	—	365	305	
H6	54 (16)	—	(8) 8d	(8) #10	950	820	
H7Z	54 (16)	(4) 8d x 1 1/2"	(2) #10	(8) #10	985	845	
HS24	43 (18)	(8) 8d x 1 1/2"	(4) #10	(4) #10	625	520	
H10S ⁵	43 (18)	(8) 8d x 1 1/2"	—	(8) #10	930	780	


1. Allowable loads on wood have been increased 60% for wind or earthquake loading with no further increase allowed; reduce where other load duration factors govern.
2. Hurricane Ties are shown installed on the outside of wall for clarity. Installation inside of wall is acceptable. For Continuous Load Path, connections must be on same side of wall.
3. When cross-grain bending or cross-grain tension cannot be avoided, mechanical reinforcement to resist such force should be considered.
4. H10S connectors can be installed 3/4" (max.) from the center of the vertical stud per the in-line framing specifications of the AISI General Provisions for reduced uplift of 890 lb., provided that the screw edges are met.
5. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.

H Hybrid Connectors


Seismic and Hurricane Ties for Wood Truss or Joist-to-CFS Wall




1 H1 Installation




2 H2A Installation




3 H3 Installation




4 H6 Stud-to-Top-Plate Installation




5 H6 Stud-to-Band-Joist Installation



6 H7Z Installation



7 HS24 Installation



8 H10S Installation

S/H1A Seismic and Hurricane Ties

S/H1A is designed to fit within several proprietary truss chords to provide uplift resistance.


Material: 43 mil (18 ga.)

Finish: Galvanized (G90)

Installation:

- Use all specified fasteners.
- S/H1A can be installed with flanges facing outwards, reverse of illustration, when installed inside a wall for truss applications.
- S/H1A does not replace solid blocking.
- S/H1A may be used with proprietary truss sections. Contact material supplier for specific installation details.

Codes: See p. 15 for Code Reference Key Chart




Model No.	Fasteners ²			Truss Thickness mil (ga.)	Allowable Uplift Load (lb.)			Code Ref.
	Truss	Top Track	Stud		Plate/Wall Stud Thickness mil (ga.)			
					33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	
S/H1A	(4) #10	(3) #10	(1) #10	27 (22)	470	470	470	IBC, FL, LA
	(4) #10	(3) #10	(1) #10	33 (20)	510	550	690	
	(4) #10	(3) #10	(1) #10	43 (18)	510	550	690	
	(4) #10	(3) #10	(1) #10	54 (16)	520	675	850	


1. Tabulated loads based on truss members with yield strength, F_y , of 50 ksi and tensile strength, F_u , of 65 ksi. Reduce tabulated load proportionally for lower truss member steel strength. For example: 43 mil (18 ga.)

truss member with a yield strength, F_y , of 33 ksi and a tensile strength, F_u , of 45 ksi is connected to 43 mil top track and wall stud. The adjusted allowable load is then $550 \text{ lb.} \times \text{minimum } [33/50 \text{ or } 45/60] = 363 \text{ lb.}$

2. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Typical S/H1A Installation



Typical S/H1A Installation

MTSM/HTSM Twist Straps

The MTSM and HTSM offer high-strength truss-to-masonry connections.


Material: See table.

Finish: Galvanized (G90). Some products available in stainless steel and ZMAX®; see Corrosion Information, pp. 21–25.

Installation:


- Use all specified fasteners; see General Notes.
- May be attached to either side of a grouted block wall. A minimum of one #5 horizontal rebar shall be installed in the top course of this wall.

Codes: See p. 15 for Code Reference Key Chart



Model No.	Connector Material Thickness mil (ga.)	L (in.)	Fasteners ⁶				Allowable Load 33 mil (20 ga.) (lb.)	Code Ref.	
			Rafter/Stud/Joist Thickness			CMU ⁵			Concrete ^{3,5}
			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)				
MTSM16	54 (16)	16	(5) #10	(4) #10	(3) #10	(4) ¼" x 2¼" Titen Turbo™	(4) ¼" x 1¾" Titen Turbo	830	—
MTSM20		20	(5) #10	(4) #10	(3) #10	(4) ¼" x 2¼" Titen Turbo	(4) ¼" x 1¾" Titen Turbo	830	
HTSM16	68 (14)	16	(7) #10	(5) #10	(3) #10	(4) ¼" x 2¼" Titen Turbo	(4) ¼" x 1¾" Titen Turbo	1,110	
HTSM20		20	(7) #10	(5) #10	(3) #10	(4) ¼" x 2¼" Titen Turbo	(4) ¼" x 1¾" Titen Turbo	1,110	

1. All straps have additional fastener holes.
2. Twist straps do not have to be wrapped over the truss to achieve the load.
3. Minimum edge distance in concrete block for Titen Turbo screws is 1½".
4. Straps can be installed on the inside face of the wall.
5. Min. $f_m = 1,500$ psi and $f_c = 2,500$ psi.
6. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Typical MTSM20 Installation

META/HETA/HHETA Embedded Truss Anchors

The embedded truss anchor series provides an engineered method to properly attach roof trusses to concrete and masonry walls. Information regarding the use of two anchors on single- and multi-ply trusses is included below.

Material: HHETA — 14 gauge; HETA — 16 gauge; META — 18 gauge


Finish: Galvanized (G90). Some products available in ZMAX® coating; see Corrosion Information on pp. 21–25.

Installation:

- Use all specified fasteners; see General Notes.
- The META, HETA and HHETA are embedded 4" into a 6" minimum concrete beam or 8" nominal grouted block wall.
- For mislocated truss anchors which are greater than 1/8" but less than 1 1/2" from the face of the truss, a shim must be provided. Shim design by truss engineer. When gap is greater than 1 1/2", install retrofit anchors.
- In double embedded anchor installations, do not install fasteners where the straps overlap when wrapped over the truss heel.

Codes: See p. 15 for Code Reference Key Chart

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.



HETA20
(META/HHETA similar)

Single Embedded Anchor Installation

Model No.	H (in.)	Fastener ⁹ Rafter/Stud/Truss Thickness	Allowable Uplift Load (lb.)			Lateral Load ⁸		Code Ref.
			Rafter/Stud/Truss Thickness			F ₁	F ₂	
			33 mil, 43 mil and 54 mil (20 ga., 18 ga. and 16 ga.)	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	54 mil (16 ga.)	
META12	8	(7) #10	1,240	1,450	1,450	340	725	—
META16	12	(9) #10	1,450	1,450	1,450			
META18	14	(9) #10	1,450	1,450	1,450			
META20	16	(9) #10	1,450	1,450	1,450			
META22	18	(9) #10	1,450	1,450	1,450			
META24	20	(9) #10	1,450	1,450	1,450			
META40	36	(9) #10	1,450	1,450	1,450			
HETA12	8	(7) #10	1,240	1,780	1,780	340	725	
HETA16	12	(9) #10	1,595	1,810	1,810			
HETA20	16	(9) #10	1,595	1,810	1,810			
HETA24	20	(9) #10	1,595	1,810	1,810			
HETA40	36	(9) #10	1,595	1,810	1,810			
HHETA12	8	(7) #10	1,240	1,820	1,820	3405	815	
HHETA16	12	(10) #10	1,770	2,235	2,235			
HHETA20	16	(10) #10	1,770	2,235	2,235			
HHETA24	20	(10) #10	1,770	2,235	2,235			
HHETA40	36	(10) #10	1,770	2,235	2,235			


1. Allowable loads may not be increased for wind or seismic load.
2. Minimum $f'_c = 2,500$ psi. Minimum $f'_m = 1,500$ psi.
3. For simultaneous loads in more than one direction, the connector must be evaluated as described in Note d, p. 18 under General Instructions to the Designer.
4. It is acceptable to use a reduced number of fasteners provided that there is a reduction in uplift load capacity. Lateral loads do not apply when fewer fasteners are used.
5. The HHETA allowable F_1 load can be increased to 435 lb. if the strap is wrapped over the truss and a minimum of 12 fasteners are installed.
6. Minimum spacing for multiple anchor installation is two times the embedment depth for full load. See Double Embedded Anchor Installation table on next page for loads on closer spaced anchors.
7. Minimum edge distance is 1 1/2" for concrete and 2" masonry.
8. Lateral loads are limited to 54 mil (16 ga.) CFS members.
9. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.

META/HETA/HHETA Embedded Truss Anchors

Double Embedded Anchor Installation

Model No.	Qty.	Application	Fasteners ⁸			Allowable Uplift Load (lb.)			Lateral Load ⁷	
			Rafter/Stud/Truss Thickness			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	F ₁	F ₂
			33 mil, 43 mil and 54 mil (20 ga., 18 ga. and 16 ga.)							
1 1/2" Width Minimum of Rafter/Stud/Truss										
META	2	CMU	(10) #10	1,770	1,985	1,985	340	725		
		Concrete	(10) #10	1,770	1,985	1,985				
HETA	2	CMU	(10) #10	1,770	2,035	2,035	340	725		
		Concrete	(10) #10	1,770	2,035	2,035				
HHETA	2	CMU	(10) #10	1,770	2,035	2,035	340	815		
		Concrete	(10) #10	1,770	2,235	2,235				
3" Width Minimum of Rafter/Stud/Truss										
META	2	CMU	(14) #10	1,900	1,900	1,900	1,210	1,160		
		Concrete	(14) #10	2,480	2,565	2,565				
HETA	2	CMU	(12) #10	2,480	2,500	2,500	1,225	1,520		
		Concrete	(12) #10	2,480	2,700	2,700				
HHETA	2	CMU	(12) #10	2,480	2,500	2,500	1,225	1,520		
		Concrete	(12) #10	2,480	3,050	3,050				
		Concrete	(14) #10	2,480	3,350	3,350				

1. Allowable loads may not be increased for wind or seismic load.
2. Minimum $f'_c = 2,500$ psi. Minimum $f_m = 1,500$ psi.
3. For simultaneous loads in more than one direction, the connector must be evaluated as described in Note d, p. 18 under General Instructions to the Designer.
4. Minimum spacing for multiple anchor installation is two times the embedment depth for full load. See Double Embedded Anchor Installation table for loads on closer spaced anchors.
5. Install with spoons facing outward and straps spaced no more than 1/8" wider than the truss width.
6. F₁ lateral loads listed may cause an additional 1/16" deflection beyond the standard 1/8" limit there the straps are installed not wrapped over the heel as shown.
7. Lateral loads are limited to 54 mil (16 ga.) CFS members.
8. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



LTS/MTS/HTS Twist Straps

Twist straps provide a tension connection between two members. They resist uplift at the heel of a truss economically. LTS/ MTS have a 2"-bend section and HTS has a 3¼"-bend section that eliminates interference at the transition points between the two members.


Material: See table

Finish: Galvanized (G90). Some products available in stainless steel and ZMAX®; see Corrosion Information, pp. 21–25.


Installation:

- Use all specified fasteners; see General Notes.
- LTS, MTS and HTS are available with the bend reversed. Specify “-REV” after the model number, such as MTS16-REV.


Codes: See p. 15 for Code Reference Key Chart



LTS12
(MTS and HTS similar)




MTS30
(HTS30 similar)



MTS30C
(HTS30C similar)

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Connector Material Thickness mil (ga.)	L (in.)	Fasteners ⁶ (Total)			Allowable Tension Load (lb.)	Code Ref.
			Rafter/Stud/Joist Thickness				
			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	33 mil (20 ga.)	
LTS12	43 (18)	12	(10) #10	(6) #10	(6) #10	775	IBC, FL, LA
LTS16		16	(10) #10	(6) #10	(6) #10	775	
LTS18		18	(10) #10	(6) #10	(6) #10	775	
LTS20		20	(10) #10	(6) #10	(6) #10	775	
MTS12	54 (16)	12	(12) #10	(8) #10	(6) #10	995	
MTS16		16	(12) #10	(8) #10	(6) #10	995	
MTS18		18	(12) #10	(8) #10	(6) #10	995	
MTS20		20	(12) #10	(8) #10	(6) #10	995	
MTS30		30	(12) #10	(8) #10	(6) #10	995	
MTS24C		24	(12) #10	(8) #10	(6) #10	995	
MTS30C		30	(12) #10	(8) #10	(6) #10	995	
HTS16		68 (14)	16	(16) #10	(12) #10	(6) #10	
HTS20	20		(18) #10	(12) #10	(6) #10	1,450	
HTS24	24		(18) #10	(12) #10	(6) #10	1,450	
HTS30	30		(18) #10	(12) #10	(6) #10	1,450	
HTS30C	30		(18) #10	(12) #10	(6) #10	1,450	



Typical MTS Installation
Truss-to-Steel Studs

1. Not all fastener holes need to be filled, as additional fastener holes are provided. Install fasteners symmetrically.
2. Install half of the fasteners on each end of strap to achieve full loads.
3. All straps except the MTS30 and HTS30 have the twist in the center of the strap.
4. Twist straps do not have to be wrapped over the truss to achieve the load.
5. May be installed on the inside face of the stud.
6. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.

VGT and S/VGT2.5 Variable-Pitch Girder Tiedown

The variable-pitch girder tiedown, S/VGT2.5, is a high-capacity tiedown for single- or multi-ply CFS girder trusses. It attaches with self-drilling screws from the side of the truss. The VGT uses Simpson Strong-Tie® Strong-Drive® SDS Heavy-Duty Connector screws for wood truss applications. They both feature a predeflected crescent washer that allows them to accommodate top-chord pitches up to 8:12.


Material: 171 mil (7 ga.)

Finish: Galvanized (G90)

Installation:

- Use all specified fasteners
- Screw holes are configured to allow for double installation on multi-member girders
- Install washer component (provided) so that top of washer is horizontal and parallel with top of wall


Codes: See p. 15 for Code Reference Key Chart



VGT

US Patent.


See strongtie.com/patent.




S/VGT2.5

US Patent.


See strongtie.com/patent.




Typical Hybrid VGTR
Single Installation
with S/HDU4



Typical Hybrid VGT
Double Installation
with S/HDU6




Typical S/VGT2.5
Single Installation
with HDU6



Typical S/VGT2.5
Double Installation
with S/HDU6

Model No.	Quantity	No. of Truss Plies	Fasteners ⁵		Allowable Uplift Load ² (lb.)		Code Ref.
			Anchor Dia.	Girder Truss	3:12	8:12	
Cold-Formed Steel Connection					54 mil (16 ga.)		
S/VGT2.5 (min.) ⁴	1	1	(1) 5/8"	(16) #14	3,050	2,620	—
	2	2	(2) 5/8"	(32) #14	6,100	5,240	
S/VGT2.5 (max.)	1	1	(1) 5/8"	(20) #14	3,860	3,130	
	2	2	(2) 5/8"	(40) #14	7,720	6,260	
Hybrid Connection					Allowable Uplift Load³ up to 8:12 (lb.)		Code Ref.
					DF/SP (160)	SPF/HF (160)	
VGT	1	2	(1) 5/8"	(16) 1/4" x 3" SDS	4,940	3,555	IBC, FL, LA
	2	2	(2) 5/8"	(32) 1/4" x 3" SDS	7,185	5,175	
	2	3	(2) 5/8"	(32) 1/4" x 3" SDS	8,890	6,400	
VGTR/L	1	2	(1) 5/8"	(16) 1/4" x 3" SDS	2,225	1,605	
	2	2	(2) 5/8"	(32) 1/4" x 3" SDS	5,545	3,990	



Typical S/VGT2.5
Installation in CMU

1. Designer shall insure attached members are adequately designed to resist applied loads.
 2. Straight-line interpolation can be used to determine allowable loads for pitches between 3:12 and 8:12.
 3. Allowable loads on wood have been increased 60% for wind or earthquake loading with no further increase allowed; reduce where other load duration factors govern.
 4. For (min.) tabulated values, not all screw holes need to be filled. Install screws symmetrically.
 5. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.

LTA2, S/HGAM10 and H10S Seismic and Hurricane Ties

The LTA2 develops high uplift at a minimum heel height. Great in areas where a strap over the heel is not required. The side tab acts as a locator in the masonry block and the four embedded hooks provide for a positive bond in the concrete grout.

The H10S and the S/HGAM10 attaches to truss joist and provides good uplift resistance.

Material: See table

Finish: Galvanized (G90)


Installation:

- Use all specified fasteners; see General Notes.
- S/HGAM10 can be installed into grouted concrete block.
- Titen Turbo™ screws are provided.
- Hurricane ties do not replace solid blocking.
- Attach to grouted concrete block with a minimum one #5 rebar horizontal in the top lintel block.

Codes: See p. 15 for Code Reference Key Chart


Ordering Information:

- The HGAM10KT is a kit of (10) connectors with (40) ¼" x 2¾" Titen Turbo screws.




LTA2

US Patent.
See strongtie.com/patent.



H10S



S/HGAM10

Model No.	Connector Material Thickness mil (ga.)	Fasteners ⁵			Allowable Uplift Load (lb.)		Code Ref.
		To Rafter/ Truss ⁵	To CMU	To Concrete	33 mil (20 ga.)	43 mil (18 ga.)	
LTA2 perpendicular-to-wall installation	43 (18)	(10) #10	Embed	Embed	1,295	1,425	—
LTA2 parallel-to-wall installation	43 (18)	(10) #10	Embed	Embed	1,295	1,390	
S/HGAM10KT	68 (14)	(4) #14	(4) ¼" x 2¾" Titen Turbo	(4) ¼" x 1¾" Titen Turbo	810	850	
H10S	43 (18)	(8) #10	(2) ⅝" x 4" Titen HD®	(2) ⅝" x 4" Titen HD	915	1,245	

1. Min. $f_m = 1,500$ psi and $f_c = 2,500$ psi.


2. Minimum edge distance is 1½" for Titen Turbo screws.

3. The products shall be installed such that the Titen Turbo screws and Titen HD anchors are not exposed to the weather.


4. Visit strongtie.com for Titen Turbo screw and Titen HD information.

5. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.


LTA2, S/HGAM10 and H10S Seismic and Hurricane Ties




Typical LTA2 Installation
(perpendicular to wall)



Typical LTA2 Installation
(parallel to wall)



Typical S/HGAM10
Installation



H10S Installation

TJC Jack Truss and Rafter Connector

TJC is a versatile connector for skewed members. Adjustable from 0° to 67.5° (shipped with 67.5° bend). Screw hole locations allow for easy installation.


Material: 54 mil (16 ga.)

Finish: Galvanized (G90)

Installation:

- Use all specified fasteners; see General Notes
- Position the skewed member on the inside of the bend line with the end of the member flush with the bend line
- Bend the TJC to the desired position (one bend cycle only)


Codes: See p. 15 for Code Reference Key Chart




TJC57

Model No.	Fasteners ²		Member Thickness mil (ga.)	Allowable Load F ₄ (lb.)			Code Ref.
	Carrying Member	Carried Member		0°	1°–60°	61°–67.5°	
TJC37 (min.)	(4) #10	(4) #10	43 (18)	660	565	475	IBC, FL, LA
TJC37 (max.)	(6) #10	(6) #10	43 (18)	680	630	530	
TJC57 (min.)	(8) #10	(8) #10	43 (18)	1,345	1,335	1,260	
TJC57 (max.)	(8) #10	(8) #10	54 (16)	1,830	1,830	1,830	


1. Reference the illustration for the required screw pattern of the TJC57.
2. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.




TJC57
Screw Pattern



Top View Installation



Typical TJC57
Installation



TJC37

LS and S/LS Skewable Angles

LS and S/LS skewable angles are a cost-effective method for connecting roof rafters to hip rafters.

Material: 43 mil (18 ga.)

Finish: Galvanized (G90)

Installation:


- Use all specified fasteners
- Field-skewable; bend one time only

Codes: See p. 15 for Code Reference Key Chart

Model No.	Length (in.)	Fasteners ²	Allowable Load (lb.)			Code Ref.
			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	
			F ₄	F ₄	F ₄	
LS30	37%	(6) #10	200	370	500	—
S/LS50	47%	(4) #10	200	370	500	
S/LS70	63%	(6) #10	465	575	715	
LS90	77%	(12) #10	465	895	915	

1. Loads are for one part only.

2. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Typical Installation Between Roof Rafter and Hip Rafter

AHEP Adjustable Hip-End Purlin

The Simpson Strong-Tie AHEP is a structural purlin that also serves as an installation aid during the truss-erection process. The AHEP attaches to the step-down hip trusses at the leading edge, eliminating the need for drop top chords and C-stud fillers. The AHEP installs linearly, aligned with the end fillers, to maintain sheathing spacing from eave to peak. Roof sheathing/decking attaches directly to the purlin. Adjustable in length, the AHEP is designed to accommodate a pitch range of 3:12 to 9:12.


Material: 33 mil (20 ga.)

Finish: Galvanized

Installation:

- Use all specified fasteners; see General Notes

Codes: See p. 15 for Code Reference Key Chart



Model No.	Fasteners ³		Sheathing Option	Allowable Download 33 mil (20 ga.) (lb.)				Code Ref.
	Side Flanges	Truss Ends		3:12 Pitch		9:12 Pitch		
				L/180	3/16"	L/180	3/16"	
AHEP	(4) #10	(4) #10	None	285	360	160	175	—
			1/2" wood sheathing	285	360	205	225	

1. Designer shall ensure attached members are adequately designed to resist applied loads.

2. Straight-line interpolation can be used to determine allowable loads for pitches between 3:12 and 9:12.

3. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie fasteners.

STC/STCT/DTC Roof Truss Clips

For alignment control between a roof truss and nonbearing walls; the 1 1/2" slot permits vertical truss chord movement when loads are applied.


Material: 43 mil (18 ga.)

Finish: Galvanized (G90)

Installation:

- Use all specified fasteners; see General Notes
- Use STC or DTC depending on required loads
- STC/STCT/DTC may be used with proprietary material sections. Contact material supplier for specific installation details
- Use STCT where truss or rafter is separated from the top plate of the nonbearing wall
- Install slot screws in the middle of the slot

Codes: See p. 15 for Code Reference Key Chart




Model No.	Fasteners ³		Allowable Load 33 mil (20 ga.) (lb.)						Code Ref.
	Base	Slot	Without Gap		1/4" Max. Gap		1/4" < Gap ≤ 1/2"		
			F ₁	F ₄	F ₁	F ₄	F ₁	F ₄	
STC	(2) #8	(1) #8	185	35	135	35	75	35	IBC, FL, LA
STCT	(2) #8	(1) #8	—	—	—	—	—	—	—
DTC	(4) #8	(2) #8	200	160	200	160	145	160	IBC, FL, LA

1. Truss or rafter must be bearing on top plate to achieve the allowable loads under "Without Gap."

2. Clips are required on both sides of the truss to achieve F₁ loads in both directions (stagger parts to avoid screw interferences).

3. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.

To allow for vertical truss movement, screws into the truss or rafter should not be driven completely flush against the connector.



Typical STC Installation

S/HTC Heavy Truss Clips

S/HTC provides a slotted connection from the truss or joist to the top track when isolation of two members is required.


Material: 43 mil (18 ga.)

Finish: Galvanized (G90)

Installation:

- Use all specified fasteners
- Screws in vertical slots shall not be driven completely flush against the connector when vertical movement is desired


Codes: See p. 15 for Code Reference Key Chart



S/HTC4

Model No.	Fasteners ³		Allowable Load 43 mil (18 ga.) (lb.)				Code Ref.
	Top Track	Truss	Without Gap ¹		With 1 1/4" Gap ²		
			F ₁	F ₄	F ₁	F ₄	
S/HTC4	(4) #8	(3) #8	320	460	85	175	—

1. Truss or rafter must be bearing on top plate to achieve the allowable loads under "Without Gap."
2. Installed with maximum 1 1/4" space between rafter or truss and top plate under "With 1 1/4" Gap." Where loads are not required, space is not limited to 1 1/4".
3. See the current *Fastening Systems* catalog at strongtie.com for more information on Simpson Strong-Tie® fasteners.



Typical S/HTC4 Installation

GP Gusset Plates

The GP gusset plate is designed to secure strapped shearwalls, truss connectors, miscellaneous wall connectors and other framing applications. The GP66 (6" x 6") and GP69 (6" x 9") have holes conveniently located 1" center-to-center to make screw installation easy and quick. The GP612 (6" x 12") and GP1212 (12" x 12") have holes on the outside edges and dimples in the center. The dimples act as screw locators while allowing strap brace attachment to gusset plates without prepunched holes getting in the way.

Features:

- Multiple stocked sizes and thicknesses to meet job site needs.
- Prepunched holes for easy and quick installation.
- Flexibility of dimples at center of GP612 and GP1212 models allow cross-bracing to attach anywhere in center of gusset plate without hole interference. On applications where gusset plate is attached to CFS framing, dimples act as screw locators, making fastening easier.

Material: 43 mil (18 ga.) — 33 ksi; 54 mil (16 ga.) — 50 ksi; 68 mil (14 ga.) — 50 ksi; 97 mil (12 ga.) — 50 ksi

Finish: Galvanized (G90)

Ordering Information:

Model No.	Ordering SKU	Size (in.)	Thickness mil (ga.)	Connector Quantity
GP66/54	GP66/54-R50	6 x 6	54 (16)	50
GP69/43	GP69/43-R50	6 x 9	43 (18)	50
GP69/54	GP69/54-R50		54 (16)	50
GP612/68	GP612/68-R25	6 x 12	68 (14)	25
GP1212/68	GP1212/68-R15	12 x 12	68 (14)	15
GP1212/97	GP1212/97-R10		97 (12)	10

For more comprehensive information and Design Example on the GP Gusset plate, please refer to p. 113.



HRS/ST/FHA/PS/LSTA/LSTI/MST/MSTA/MSTC/MSTI Strap Ties

Straps are load rated and provide the correct thickness and number of fasteners the specifier is looking for compared with field fabricated straps.


Install strap ties where top or bottom plates are cut, at wall intersections, and as ridge ties. Reduce the allowable load based on the size and quantity of fasteners used.

Refer to applicable code for minimum edge and end distances.

Finish: PS — hot-dip galvanized (HDG); all others — galvanized. Some products are available in stainless steel or ZMAX®; see Corrosion Information, pp. 21–25.


Installation: Use all specified fasteners; see General Notes

Codes: See p. 15 for Code Reference Key Chart



Model No.	Connector Material Thickness mil (ga.)	Dimensions (in.)		Bolts		Code Ref.
		W	L	Quantity	Diameter (in.)	
PS218	171 (7)	2	18	4	3/4	—
PS418		4	18	4	3/4	
PS720		6 3/4	20	8	1/2	

PS strap design loads must be determined by the designer for each illustration. Hole diameter in the part may be oversized to accommodate the HDG. Designer must determine if the oversize creates an unacceptable installation.



HRS/ST/FHA/PS/LSTA/LSTI/MST/MSTA/MSTC/MSTI Strap Ties

Codes: See p. 15 for Code Reference Key Chart

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Connector Material Thick. mil (ga.)	Dimensions (in.)		Fasteners ⁴ (Total)			Allowable ASD Tension Load (lb.)			Code Ref.
				Rafter/Stud/Joist Thickness			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	
				33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)				
W	L	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)						
LSTA9	33 (20)	1 ¼	9	(8) #10	(8) #10	(8) #10	705	1,120	1,190	IBC, FL, LA
LSTA12		1 ¼	12	(10) #10	(10) #10	(8) #10	885	1,190	1,190	
LSTA15		1 ¼	15	(12) #10	(12) #10	(10) #10	1,060	1,190	1,190	
LSTA18		1 ¼	18	(14) #10	(12) #10	(10) #10	1,190	1,190	1,190	
LSTA21		1 ¼	21	(14) #10	(12) #10	(10) #10	1,190	1,190	1,190	
LSTA24		1 ¼	24	(14) #10	(12) #10	(10) #10	1,190	1,190	1,190	
ST292		2 ⅞	9 ⅞	(12) #10	(10) #10	(10) #10	1,060	1,240	1,240	
ST2122		2 ⅞	12 ⅞	(16) #10	(12) #10	(10) #10	1,415	1,502	1,502	
ST2115		¾	16 ⅞	(8) #10	(6) #10	(4) #10	630	630	630	
ST2215		2 ⅞	16 ⅞	(20) #10	(14) #10	(10) #10	1,765	1,825	1,825	
LSTA30	43 (18)	1 ¼	30	(18) #10	(12) #10	(10) #10	1,555	1,555	1,555	
LSTA36		1 ¼	36	(18) #10	(16) #10	(14) #10	1,555	1,555	1,555	
LSTI49		3 ¾	49	(32) #10	(32) #10	(20) #10	2,830	4,050	4,050	
LSTI73		3 ¾	73	(46) #10	(32) #10	(20) #10	4,050	4,050	4,050	
MSTA9		1 ¼	9	(8) #10	(8) #10	(8) #10	705	1,050	1,555	
MSTA12		1 ¼	12	(10) #10	(10) #10	(8) #10	885	1,315	1,555	
MSTA15		1 ¼	15	(12) #10	(12) #10	(10) #10	1,060	1,555	1,555	
MSTA18		1 ¼	18	(14) #10	(12) #10	(10) #10	1,235	1,555	1,555	
MSTA21		1 ¼	21	(16) #10	(12) #10	(10) #10	1,415	1,555	1,555	
MSTA24		1 ¼	24	(18) #10	(12) #10	(10) #10	1,555	1,555	1,555	

Table continued on the next page.

HRS/ST/FHA/PS/LSTA/LSTI/MST/MSTA/MSTC/MSTI Strap Ties

Codes: See p. 15 for Code Reference Key Chart

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Connector Material Thick. mil (ga.)	Dimensions (in.)		Fasteners ⁴ (Total)			Allowable ASD Tension Load (lb.)			Code Ref.
				Rafter/Stud/Joist Thickness			33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)	
		W	L	33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)				
MSTA30	54 (16)	1 ¼	30	(22) #10	(16) #10	(12) #10	1,945	1,950	1,950	IBC, FL, LA
MSTA36		1 ¼	36	(24) #10	(18) #10	(16) #10	1,950	1,950	1,950	
ST6215		2 ½	16 ½	(20) #10	(16) #10	(10) #10	1,765	2,025	2,025	
ST6224		2 ½	23 ½	(28) #10	(20) #10	(12) #10	2,455	2,455	2,455	
ST9		1 ¼	9	(8) #10	(8) #10	(8) #10	705	1,050	1,350	
ST12		1 ¼	11 ½	(10) #10	(10) #10	(8) #10	885	1,315	1,350	
ST18		1 ¼	17 ¾	(14) #10	(12) #10	(12) #10	1,235	1,350	1,350	
ST22		1 ¼	21 ½	(20) #10	(20) #10	(20) #10	1,350	1,350	1,350	
MSTC28		3	28 ¼	(36) #10	(36) #10	(30) #10	3,180	4,600	4,600	
MSTC40		3	40 ¼	(52) #10	(46) #10	(46) #10	4,595	4,600	4,600	
MSTC52		3	52 ¼	(54) #10	(42) #10	(42) #10	4,600	4,600	4,600	
MSTC66		68 (14)	3	65 ¾	(66) #10	(46) #10	(30) #10	5,795	5,795	
MSTC78	3		77 ¾	(66) #10	(46) #10	(30) #10	5,795	5,795	5,795	
ST6236	2 ½		33 ¾	(40) #10	(30) #10	(18) #10	3,535	3,760	3,760	
HRS6	97 (12)	1 ¾	6	(6) #10	(6) #10	(6) #10	530	790	1,600	—
HRS8		1 ¾	8	(10) #10	(10) #10	(10) #10	885	1,315	2,670	
HRS12		1 ¾	12	(14) #10	(14) #10	(12) #10	1,235	1,840	2,710	
MSTI26		2 ½	26	(26) #10	(26) #10	(22) #10	2,300	3,420	5,025	
MSTI36		2 ½	36	(36) #10	(36) #10	(22) #10	3,180	4,735	5,025	
MSTI48		2 ½	48	(48) #10	(40) #10	(22) #10	4,240	5,025	5,025	
MSTI60		2 ½	60	(58) #10	(40) #10	(22) #10	5,025	5,025	5,025	
MST27		2 ½	27	(30) #10	(30) #10	(22) #10	2,650	3,945	5,025	
MST37		2 ½	37	(42) #10	(40) #10	(34) #10	3,710	5,025	5,025	
MST48		2 ½	48	(54) #10	(54) #10	(46) #10	4,770	5,155	5,155	
MST60	118 (10)	2 ½	60	(68) #10	(68) #10	(62) #10	5,820	6,420	6,650	
MST72		2 ½	72	(80) #10	(72) #10	(64) #10	6,650	6,650	6,650	

1. Use half of the fasteners in each member being connected to achieve the listed loads.

2. Loads are based on lesser of steel capacity or fastener calculation.

3. Not all fastener holes need to be filled, as additional fastener holes are provided. Install fasteners symmetrically.

4. See the current *Fastening Systems* catalog on strongtie.com for more information on Simpson Strong-Tie® fasteners.



CS/CMST Coiled Straps

CMSTC provides countersunk fastener slots that provide a lower screw head profile. CS, CMST and CMSTC are continuous utility straps which can be cut to length on the jobsite. Packaged in lightweight cartons (about 40 lb.).

Finish: Galvanized. Some products available in ZMAX® coating; see Corrosion Information, pp. 21–25.


Installation:

- Use all specified fasteners; see General Notes.
- Refer to the applicable code for minimum edge and end distances.
- The table shows the maximum allowable loads and the screws required to obtain them. See footnote #1. Fewer screws may be used; reduce the allowable load by the code lateral load for each fastener subtracted from each end.




Typical CS Installation as a Floor-to-Floor Tie


Codes: See p. 15 for Code Reference Key Chart



CS16 Hole Pattern
(all other CS straps similar)



CMST14 Hole Pattern
(CMST12 similar)



CMSTC16 Hole Pattern

Gauge stamped on part for easy identification.

These products are available with additional corrosion protection. Additional products on this page may also be available with this option. Check with Simpson Strong-Tie for details.

Model No.	Total Length	Connector Material Thickness mil (ga.)	Width (in.)	OSB Sheathing (in.)	Fasteners ¹¹ (Total)			Allowable Tension Load (lb.)	Code Ref.
					Rafter/Stud Thickness				
					33 mil (20 ga.)	43 mil (18 ga.)	54 mil (16 ga.)		
CMST12 ²	40'–3"	97 (12)	3	None	(104) #10	(70) #10	(40) #10	9,080	IBC, FL, LA
CMST14 ²	52'–6"	68 (14)	3	None	(72) #10	(50) #10	(28) #10	6,365	
CMSTC16 ³	54'	54 (16)	3	None	(54) #10	(36) #10	(30) #10	4,600	—
				None	(54) GDPSK-138KT	(36) GDPSK-138KT	(30) GDPSK-138KT	5,640	
				3/4	(54) PPHD134S1016	(36) PPHD134S1016	(30) PPHD134S1016	5,215	
				7/16				4,735	
CS14	100'	68 (14)	1 1/4	None	(28) #10	(18) #10	(12) #10	2,305	IBC, FL, LA
CS16	150'	54 (16)	1 1/4	None	(18) #10	(12) #10	(8) #10	1,550	
CS20	250'	33 (20)	1 1/4	None	(12) #10	(8) #10	(6) #10	945	

1. Use half of the fasteners in each member being connected to achieve the listed loads.
2. For CMST straps: End Length (inches) = 1/2 total fasteners x 7/8" + 1" when all holes filled. Double length if only round holes filled.
3. For CMSTC16 straps: End Length (inches) = 1/2 total fasteners x 3/4" + 1" when all holes filled. Double length if only round holes filled.
4. For CS straps: End Length (inches) = 1/2 total fasteners + 1".
5. Total Cut Length = End Length + Clear Span + End Length.
6. Calculate the connector value for a reduced number of screws as follows: Allowable Load = $\frac{\text{No. of Screws Used}}{\text{No. of Screws in Table}} \times \text{Table Load}$

Example: CMSTC16 on 54 mil with 24 screws: $\frac{24 \text{ Screws (Used)}}{30 \text{ Screws (Table)}} \times 4,600 \text{ lb.} = 3,680 \text{ lb.}$

7. Loads are based on lesser of steel strap capacity and AISI S100 fastener calculation.
8. Tabulated values are based on Strong-Drive® PPHD134S1016, Head Screw 0.333" diameter x 1 1/4" length and Spiral Knurl Gas Pins GDPSK -138KT Head Screw 0.24" diameter x 1 3/8" length.
9. Use 54 mil allowable loads for stud thicknesses greater than 54 mil.
10. Allowable loads are based on cold-form steel members with a minimum yield strength of 33 ksi for 33 mil and 43 mil, and 50 ksi for 54 mil and thicker.
11. See the current *Fastening Systems* catalog on strongtie.com for more information on Simpson Strong-Tie® fasteners.

WBT Wall Brace Tensioner

The WBT Wall Brace Tensioner is an easy to use device that can reduce the slack from cold-formed steel (CFS) strap bracing. With the ability to pull as much as ½" of slack for a single strap, the WBT can play an important role in reducing deflection in braced wall panels, making installation of cladding easier. Tightening the wall straps is not the easiest jobsite installation task, but this tensioner improves the efficiency of setting the straps to a desired tightness with less hassle.

Features:

- Removes up to ½" of slack from a single strap
- Can be used on straps up to 6" wide, 14 ga. (68 mil) thick
- Max torque on bolt in strap is 115 in.-lb.
- Compatible with generic strap and Simpson Strong-Tie® CS Coil Strap
- Sold in a box of (30) WBT connectors, including (30) bolts and nuts

Material:

- Connector: 10 ga.
- Finish: G90
- Bolt: M6 (6mm) ASTM A307 Grade A Class 5
- Nut: ASTM A563 Grade A



Load Capacity: Design strap for net section capacity at WBT hole in addition to other applicable limits states per AISI requirements

Installation:

- Place WBT near center of diagonal brace
- Drill ¼"-dia. hole through the center of strap width
- Install bolt through strap hole and WBT with nut facing towards the wall cavity
- Tightening the nut requires 10 mm hex head socket setter
- Tighten until the slack is taken out of the strap

Ordering Information and Dimensions:

Model No.	Thickness (mil)	Width	Length	Height	Bolt	Coating (Connector)	Coating (Bolt and Nut)	Packaging Qty
WBT-KT30	118	1 ¼"	2 ¾"	1 ⅜"	6 mm (¼")	Zinc Galvanized G90	Zinc Electroplate (5µm)	30



LTP5 Lateral Tie Plate

The LTP5 is designed to transfer shear forces for plate-to-rim joist or blocking connections. This lateral tie plate can be securely installed over plywood sheathing or directly to the framing members. The embossments enhance performance and allow for design flexibility.


Material: 33 mil (20 ga.)

Finish: Galvanized

Installation:

- Use all specified fasteners; see General Notes

Codes: See p. 15 for Code Reference Key Chart




LTP5

Model No.	Type of Connection	Direction of Load	Fasteners ⁴		Allowable Load 43 mil (18 ga.) (lb.)	Code Ref.
			To Rim Joist	To Sheathing and Track		
LTP5	1	G	(7) #10	(7) #10	1,045	IBC, FL, LA
	2		(7) #10	(7) #10	1,110	
	3		(7) 8d x 1 1/2"	(7) #10	730	

1. Allowable loads are based on steel (stud and sheet) of 43 mil (18 ga.) minimum.

2. Allowable load for Type 3 connection assumes $C_D = 1.60$.

3. See the current *Fastening Systems* catalog on strongtie.com for more information on Simpson Strong-Tie® fasteners.



Note: When attaching an LTP5 framing anchor over sheathing, the screws must penetrate and engage the steel framing. A minimum of three threads shall penetrate past the steel.

Strong-Wall® High-Strength Steel Shearwalls (SSWH)

Features and Benefits:

Code Listed

- New ICC-ES ESR-1679 code report evaluated to the 2024 IRC/IBC

Higher Capacity = Lower Cost

- The new SSWH™ walls have the highest seismic rating allowing designers to reduce wall size

Easier for All Trades


- An easy-to-use anchor-bolt template for concrete contractors; predrilled holes where electricians need them for wiring

Support and Service

- Simpson Strong-Tie provides the best engineering technical support and experienced field representation available

Codes: ICC-ES ESR-1679; City of L.A. RR25625; State of Florida FL5113

Please visit strongtie.com/products/lateral-systems for load tables, structural details and anchorage information.



SSWH Cold-Formed Steel Applications
(Standard, Raised Floor and Two-Story)

Strong-Wall Shearwall Selector Application

This application helps design professionals select an appropriate Simpson Strong-Tie® High-Strength Steel Shearwall and High-Strength Wood Shearwall.

Optimized Solution


Provides the most cost-effective Strong-Wall solution based on the input shear load.

Manual Solution

Allows designers to choose which type and number of walls meet their requirements.

- Finds lowest cost solution
- Provides actual drift and uplift values
- Provides solutions for different model Codes
- Includes new anchorage solutions
- Saves, exports and prints solutions

You can find the Strong-Wall Shearwall Selector application at strongtie.com/webapps/strongwallshearwallselector.



PSPNZ Protecting Shield Plate

PSPN58Z and PSPN516Z protecting shield plate fastener stoppers meet IRC, IBC and the International Plumbing Code. PSPN516Z meets the code plumbing protection requirements as well as having additional fasteners if the designer chooses to use it as a track splice strap.

Material: 54 mil (16 ga.)

Finish: ZMAX® coating

Installation:

- Flatten prongs with hammer as needed
- Use #10 screws

Codes: See p. 15 for Code Reference Key Chart





- PSPN516Z at top plates
 - International Residential Code — 2015/2018 P2603.2.1
 - International Plumbing Code — 2015/2018 305.6
- PSPN516Z at bottom plate.
 - International Plumbing Code — 2015/2018 305.6
- PSPN58Z at top plates and bottom plate.
 - International Plumbing Code — 2015/2018 305.6

Note that the IBC section 2308.5.8 (2018 IBC) and 2308.5.7 (2015 IBC) and the IRC section R602.6.1 require a 54 mil (16 ga.) strap with (6)16d nails and (8)16d nails respectively each side at a hole or notch in a wood top, sill or sole plate. The designer or local building jurisdiction may permit an equivalent fastener strength (e.g., screws in lieu of nails) to be used for the same condition in a CFS top or bottom track.

For more information, see pp. 21–25.

Model No.	W (in.)	L (in.)	Code Ref.
PSPN58Z	5	8	—
PSPN516Z	5	16 ⁵ / ₁₆	

- #10 self-tapping screws may be used to attach PSPNZ to CFS framing with quantity determined by designer.
- PSPN516Z with (6) #10 self-tapping screws each side achieves an allowable shear capacity of 1,060 lb. and 1,580 lb. to 33 mil (20 ga.) track and to 43 mil (18 ga.) track, respectively.



Simpson Strong-Tie Limited Warranty

Effective Date: March 18, 2021

This Limited Warranty applies to all Simpson Strong-Tie products ("Products") purchased after the Effective Date while this Limited Warranty remains in effect, other than those Simpson Strong-Tie products that have a separate Limited Warranty applicable to such products. For purchases after the Effective Date, please consult strongtie.com/limited-warranties, as this Limited Warranty may be updated by Simpson from time to time. All future purchases of Products are subject to the terms of the Limited Warranty in effect as of the purchase date.

This Limited Warranty must be read in conjunction with all applicable General Notes, General Instructions for the Installer, General Instructions for the Designer, Building Codes, Corrosion Information, and Terms & Conditions of Sale, along with any other information or specifications published by Simpson Strong-Tie Company Inc. ("Simpson") or available on the strongtie.com website ("Website") or on the product package, label or product manual. All of this information is referred to collectively as the "Simpson Strong-Tie Documentation." All applicable Simpson Strong-Tie Documentation must be carefully reviewed each time any Product is used.

Simpson Strong-Tie warrants, to the original purchaser only, that each Product will be free from substantial defects in materials, manufacturing and design if properly specified, installed, and maintained, and when used in accordance with the design limits and the structural, technical, and environmental specifications in the Simpson Strong-Tie Documentation. This Limited Warranty is void and does not apply to any (a) Product purchased from an unauthorized dealer, retailer or distributor, (b) Product deterioration or damage due to environmental conditions or inadequate or improper handling, transportation, storage or maintenance, (c) cosmetic defects, including discoloration, (d) failure or damage caused by improper installation, application, mixing or preparation, (e) use of a Product in temperatures or environmental conditions outside the ranges specified for such Product in the Simpson Strong-Tie Documentation, (f) use of a Product outside of its shelf-life specifications, (g) normal wear and tear, (h) failure or damage caused by the use of a Product with any fasteners, pins, screwstrips, products or accessories other than authentic Simpson Strong-Tie products, (i) Product that was subjected to negligence or excessive or improper use, including any use not in accordance with the Simpson Strong-Tie Documentation, (j) failure or damage caused by the building site, foundation, or any third-party products, building materials or components, (k) failure or damage caused by use of a Product in a structure that has a design or other defect or that does not comply with all applicable building codes, laws, rules and regulations, (l) modified Product, or any nonstandard use or application of a Product, (m) failure or damage caused by corrosion, termites or other wood destroying organisms, animal or insect activity, wood fungal decay, rot, mold, mildew, exposure to chemicals or other hazardous substances, a corrosive environment or materials, inadequate moisture protection, or premature deterioration of building materials, (n) failure or damage caused by an act of God, including any hurricane, earthquake, tornado, lightning, ice, snow, high wind, flood or other severe weather or natural phenomena, (o) installation services or workmanship, including any failure or damage caused by installation of any Product, whether or not in accordance with the Simpson Strong-Tie Documentation, or (p) failure or damage caused by the gross negligence, willful misconduct, or other acts or omissions of the builder, general contractor, installer or any third party, including the building owner. Notwithstanding the foregoing, Simpson Strong-Tie disclaims and does not provide any warranty related to the design of any custom-order or non-catalog Product.

Although Products are designed for a wide variety of uses, Simpson Strong-Tie assumes no liability for confirming that any Product is appropriate for an intended use, and each intended use of a Product must be reviewed and approved by qualified professionals. Each Product is designed for the load capacities and uses listed in the Simpson Strong-Tie Documentation, subject to the limitations and other information set forth in the Simpson Strong-Tie Documentation.

Due to the particular characteristics of potential impact events such as earthquakes and high velocity winds, the specific design and location of the structure, the building materials used, the quality of construction, or the condition of the soils or substrates involved, damage may nonetheless result to a structure and its contents even if the loads resulting from the impact event do not exceed Simpson Strong-Tie's specifications and the Products are properly installed in accordance with applicable building codes, laws, rules and regulations.

Product demonstrations, training, operator examinations, technical and customer support and other services provided by Simpson Strong-Tie are based on Simpson Strong-Tie's present knowledge and experience, are conducted for illustrative or instructive purposes only, do not constitute a warranty of Product capabilities, specifications or installation and do not modify the applicable Limited

Warranty for Products set forth herein. Any services provided by Simpson Strong-Tie are provided without any representation or warranty of any kind, and Simpson Strong-Tie assumes no liability for any representations or statements made as part of such Product demonstrations, training, operator examinations or other services. In the event of any inconsistency between any information provided during any such demonstration or service, and the information in any applicable Simpson Strong-Tie Documentation, the information in the Simpson Strong-Tie Documentation shall govern. In the event of any inconsistency between any information provided on the Website, and the information in any other Simpson Strong-Tie Documentation, the information on the Website shall govern.

ALL WARRANTY OBLIGATIONS OF SIMPSON STRONG-TIE SHALL BE LIMITED, AT SIMPSON STRONG-TIE'S ABSOLUTE DISCRETION, TO EITHER REPAIRING THE DEFECTIVE PRODUCT OR PROVIDING A REPLACEMENT FOR THE DEFECTIVE PRODUCT. THIS REMEDY CONSTITUTES SIMPSON STRONG-TIE'S SOLE OBLIGATION AND LIABILITY AND THE SOLE AND EXCLUSIVE REMEDY OF PURCHASER AND, WITHOUT LIMITING THE GENERALITY OF THE FOREGOING, EXCLUDES ANY LABOR OR OTHER COSTS INCURRED IN CONNECTION WITH A WARRANTY CLAIM. PURCHASER ASSUMES ALL RISK AND LIABILITY ASSOCIATED WITH ANY USE OF THE PRODUCT, INCLUDING BUT NOT LIMITED TO SUITABILITY FOR ITS INTENDED USE.

THE LIMITED WARRANTY HEREIN IS EXPRESSLY IN LIEU OF ALL OTHER WARRANTIES, AND, WHERE LAWFUL, SIMPSON STRONG-TIE DISCLAIMS ALL OTHER WARRANTIES, INCLUDING BUT NOT LIMITED TO IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE AND WARRANTIES ARISING FROM COURSE OF PERFORMANCE, COURSE OF DEALING OR TRADE USAGE. IN NO EVENT WILL SIMPSON STRONG-TIE BE LIABLE FOR INCIDENTAL, CONSEQUENTIAL, PUNITIVE OR SPECIAL DAMAGES OR DIRECT OR INDIRECT LOSS OF ANY KIND, INCLUDING BUT NOT LIMITED TO PROPERTY DAMAGE, DEATH AND PERSONAL INJURY. SIMPSON STRONG-TIE'S ENTIRE LIABILITY IS LIMITED TO THE PURCHASE PRICE OF THE DEFECTIVE PRODUCT. SOME STATES DO NOT ALLOW LIMITATIONS ON HOW LONG AN IMPLIED WARRANTY LASTS, OR THE EXCLUSION OR LIMITATION OF INCIDENTAL OR CONSEQUENTIAL DAMAGES, SO THE ABOVE LIMITATION OR EXCLUSION MAY NOT APPLY TO YOU. THIS WARRANTY GIVES YOU SPECIFIC LEGAL RIGHTS, AND YOU MAY ALSO HAVE OTHER RIGHTS WHICH VARY FROM STATE TO STATE.

To obtain warranty service, you must contact Simpson Strong-Tie promptly at (800) 999-5099 or at Simpson Strong-Tie Company Inc., 5956 West Las Positas Boulevard, Pleasanton, CA 94588, regarding any potential claim, no later than sixty (60) days after you discover the potential claim. Upon request by Simpson Strong-Tie, you must provide Simpson Strong-Tie with: (a) proof of purchase and written records evidencing, in reasonable detail, the date and manner of installation, application, mixing and preparation of the Products, as applicable, (b) a reasonable opportunity to inspect the site where the Product was installed, and (c) samples of the Products from the actual installation in sufficient quantities in order for Simpson Strong-Tie to perform testing to determine whether or not the Product failed as set forth herein. Simpson Strong-Tie may, in its absolute discretion, request that you return the allegedly defective Products to Simpson Strong-Tie, in which case Simpson Strong-Tie will issue a Return Materials Authorization (RMA), which must be completed and returned to Simpson Strong-Tie with the Product. Simpson Strong-Tie is not responsible for any costs or expenses incurred in connection with any inspection (other than by Simpson Strong-Tie employees) or in connection with the return of Products to Simpson Strong-Tie, but Simpson Strong-Tie shall bear all costs and expenses incurred in connection with the shipment of replacement Products in the event that Simpson Strong-Tie determines that the Product should be replaced in accordance with this Limited Warranty. If Simpson Strong-Tie elects to repair or replace the Product, Simpson Strong-Tie shall have a reasonable time to do so.

No one is authorized to change or add to this Limited Warranty. If at any time Simpson Strong-Tie does not enforce any of the terms, conditions or limitations stated in this Limited Warranty, Simpson Strong-Tie shall not have waived the benefit of said term, condition or limitation and can enforce it at any time. This Limited Warranty is extended only to the original purchaser and is not transferable. It is not intended nor shall it be construed to create rights in any third party.

Envision excellence with ease.



CFS Designer™ software.

Developed by the engineers at Simpson Strong-Tie, CFS Designer makes it easy to design cold-formed steel structures. A modern platform and intuitive user interface enable fast input and simplify file management — so you can move ahead with speed, accuracy and efficiency.

SIMPSON
Strong-Tie

Download CFS Designer at
strongtie.com/cfsdesigner
or call your representative
at (800) 999-5099 to learn more.





SIMPSON
STRONG-TIE
U.S. PATENT
8,813,456

SIMPSON
STRONG-TIE
U.S. PATENT
8,813,456

Use & Warning
strongtie.com